

# DRAFT ENVIRONMENTAL IMPACT ASSESSMENT REPORT

Of

## EXTRACTION OF RIVERBED SAND DEPOSITION

From

### AUSGRAM-II SAND MINE (MIN\_EBUR\_24)

MOUZA – MALOCHA

Plot No.- 254(P), 251 (P), 201(P), & 263(P), J.L. NO- 36, P.S. – Burdwan, State – West Bengal

Production Capacity: 9,27,810.00 Cu. M. of Sand

Lease Area: 9.15 Ha (Non-Forest)

Screening Category: B1

#### LESSEE :

West Bengal Mineral Development & Trading Corporation Limited

WBIIDC Building, 3rd Floor, DJ-Block, DJ-10, Sector- II,  
Bidhanagar (Salt Lake City),  
Kolkata: 700091



TOR LETTER NO.: 2529/EN/T-II-1/518/2023


SEIAA Proposal No.: SIA/WB/MIN/440218/2023

Prepared by:

**INDIAN MINE PLANNERS AND CONSULTANTS**

(A NABET Accredited 'A' Grade Consultants)

Room No. 409, 4th Floor, DLF Galleria, New Town,  
Action Area 1, Kolkata -700156, West Bengal



Laboratory Partner:

**N.D. International**

(A NABL Accredited Laboratory)

107B, Block-F, New Alipore, Kolkata-700053

(Baseline Data: March-May 2023)

December - 2023



Job No: - ENV-22/1

Issue No: - 01



## INDIAN MINE PLANNERS & CONSULTANTS

(Geology, Mining, Environment & Allied Engineering)

ISO 9001:2015 Certified

QCI-NABET

Accredited Prospecting Agency (APA), Mining Plan Preparing Agency (MPPA),  
EIA Consultant Organisation (ECO) & Exploration Agencies in Mineral Sector (AEA)



GSTIN: 19AACFI9674G1ZX

# DECLARATION BY THE APPLICANT

I do hereby declare that the EIA/EMP report in respect of **Ausgram – II Sand Mine (MIN\_EBUR\_24)** over an area of **9.15 Ha (22.61 Acres)** on **Ajoy River** at JL No. – 36; Plot No. – 254(P), 251(P), 201(P) & 263(P); Mouza – Malocha; P.S. – Burdwan; District – Purba Bardhaman, West Bengal (Proposal No. **SIA/WB/MIN/440218/2023**) has been prepared by **M/S Indian Mine Planners & Consultants**, Kolkata as per the TOR prescribed by SEIAA West Bengal vide letter No. **2529/EN/T-II-1/518/2023 dated 09.11.2023**.

The contents (information and Data) of the report about my project is correct and true to my knowledge & Belief.

**WBMDTCL**

WBIIDC Building, 3rd Floor, DJ-10,  
DJ Block, Sector II, Salt Lake City  
Kolkata – 700091, West Bengal

**Samik Panigrahi, WBCS (Exe.)**

General manager (Sand & Admin)  
W.B. Mineral Dev. & Trading Corp. Ltd.



## INDIAN MINE PLANNERS & CONSULTANTS

(Geology, Mining, Environment & Allied Engineering)

ISO 9001:2015 Certified

QCI-NABET

Accredited Prospecting Agency (APA), Mining Plan Preparing Agency (MPPA),  
EIA Consultant Organisation (ECO) & Exploration Agencies in Mineral Sector (AEA)



GSTIN: 19AACFI9674G1ZX

# UNDERAKING BY THE CONSULTANT

This is to certify that we, M/s Indian Mine Planners & Consultants having NABET Accreditation no. **NABET/EIA/2023/SA-0182** [ Sl. No. 1 (a) (i), Cat 'A'] dated December 20, 2022, have prepared in EIA/EMP report of “**Ausgram – II Sand Mine (MIN\_EBUR\_24)**” for extraction of **3.276 Cr. Cft.** Of sand from the Ajoy riverbed over an area 9.15 Ha. At Mouza: Malocha, JL No. – 36; Plot No. – 254(P), 251(P), 201(P) & 263(P); P.S.:Burdwan, District: Purba Bardhaman on behalf of West Bengal Mineral Development & Trading Corporation Ltd. (Project Proponent) as per TOR prescribed by SEAC West Bengal vide letter No. **2529/EN/T-II-1/518/2023 dated 25.04.2023.**

The information and data provided in the EIA/EMP report is true to its form and is verified by the respective EC & FAE's in due course of time.

Dr. N. B. Chanda  
EIA Coordinator & Managing Partner  
M/S Indian Mine Planners & Consultants  
Date: 5.10.2023

## DECLARATION BY THE APPLICANT


I, hereby, certify that I was a part of the EIA team in the following capacity that developed the above EIA.

### EIA Coordinator:

Name: Dr. N.B. Chanda

Signature and Date: 26.07.2023

Period of involvement: March 2023 onwards







### Functional area Experts:

S No	Functional area	Functional Area Experts	Involvement (period and task**)	Signature & Date
1.	AP	Dr. N B Chanda	<ul style="list-style-type: none"> <li>• Identification of baseline monitoring stations and study of the monitored data with respect to the applicable standards.</li> <li>• Identification of sources of air pollution comprising dust, gaseous emission due to mining &amp; other activities</li> <li>• Identification of Impacts &amp; suggestion of mitigation measures</li> </ul> Period March 2023 onwards	
2.	AQ	Dr. A S Shannigrahi	<ul style="list-style-type: none"> <li>• Quantification of emission particulars</li> <li>• Air quality modeling for prediction of post project impact on the air quality of the study area</li> <li>• Analysis of the Isopleth generated</li> <li>• Arriving at the post project cumulative concentration at the AAQ monitoring locations</li> </ul> Period March 2023 onwards	
3.	WP	Dr. N B Chanda	<ul style="list-style-type: none"> <li>• Identification of baseline monitoring stations and study of the monitored data with respect to the applicable standards.</li> <li>• Identification of Water requirement &amp; Source</li> <li>• Preparation of water balance diagram</li> <li>• Identification of Water polluting sources</li> <li>• Impact of the project on the water</li> </ul>	






			<p>quality, both surface and groundwater</p> <ul style="list-style-type: none"> <li>• Suggestion of Mitigation measures to control water pollution</li> </ul> <p>Period March 2023 onwards</p>	
4.	SW + HW	Sanjib Chattopadhyay	<ul style="list-style-type: none"> <li>• Quantification of mineral &amp; waste from mining operation</li> <li>• Waste disposal method evaluation</li> <li>• Providing dump management plan</li> <li>• Providing Surface Runoff Management Structure Requirements.</li> <li>• Identification of Hazardous waste and its details of disposal</li> </ul> <p>Period March 2023 onwards</p>	
5.	SE	Mrs. Nidhi Singh Rathod	<ul style="list-style-type: none"> <li>• Identification of villages in the study area and finalization of demographic profile of the villages within the study area.</li> <li>• Perusal of socio economic report done by client</li> <li>• Validation and incorporation of relevant portions in the report.</li> </ul> <p>Period March 2023 onwards</p>	
6	EB	Prof. Tapan Mishra	<ul style="list-style-type: none"> <li>• Perusal of existing data relevant to this project.</li> <li>• Studying the details of flora and fauna, separately for core, buffer zone and forest area based on primary field survey.</li> <li>• Identification of species</li> <li>• Indicating the Schedule of the fauna present in the study area</li> <li>• Assessment of impact on Biological environment and suggestion of mitigative measures</li> <li>• Collecting &amp; providing details of existing and proposed Green belt development /plantation in the core zone</li> </ul> <p>Period March 2023 onwards</p>	
7	HG	Debashish Ghosh	<ul style="list-style-type: none"> <li>• Study of existing surface drainage arrangements in the core and buffer zone, impact due to mining on these drainage courses and suggestion of mitigative measures</li> <li>• Perusal of site specific ground water table details for the core zone and the study area.</li> <li>• Studied the hydrological aspects of surface and groundwater in study area</li> </ul>	






			<ul style="list-style-type: none"> <li>• Estimation of stage of ground water development as per CGWA norms</li> <li>• Study about impact on the hydrology due to mining operation</li> <li>• Suggesting mitigative measures like RWH for enhancement of ground water level</li> </ul> <p>Period March 2023 onwards</p>	
8	GEO	Dr. N B Chanda	<ul style="list-style-type: none"> <li>• Study of geology of the ML area and the surrounding areas.</li> <li>• Provide details about Mineral composition Period March 2023 onwards</li> </ul>	<i>N B Chanda</i>
9	SC	G C Das	<ul style="list-style-type: none"> <li>• Study of soil profile</li> <li>• Fixing of Soil sampling locations and perusal of analysis results.</li> <li>• Assessment of Impact on soil and suggesting plantation scheme.</li> </ul> <p>March 2023 onwards</p>	<i>G C Das</i>
10	NV	Sanjib Chattopadhyay	<ul style="list-style-type: none"> <li>• Identification of baseline monitoring stations and study of the monitored data with respect to the applicable standards.</li> <li>• Predict the noise level and vibration level due to proposed mining operation based on scientific evaluation.</li> <li>• Suggesting the Mitigation measures to control noise pollution</li> <li>• Suggesting the Mitigation measures to control ground vibration</li> </ul> <p>Period March 2023 onwards</p>	<i>Sanjib Chattopadhyay</i>
11	LU	G C Das	<ul style="list-style-type: none"> <li>• Collection of Remote sensing satellite data to study the land use pattern.</li> <li>• Primary field survey and limited field verification for land categorization in the study area</li> <li>• Preparation of Land use map using Satellite data of the project area separately for the core zone.</li> </ul> <p>Period March 2023 onwards</p>	<i>G C Das</i>
12	RH	Debasish Basu	<ul style="list-style-type: none"> <li>• Identified Major risks involved in the project Mitigation measures suggested to avoid risk.</li> <li>• Preparation of onsite and offsite emergency management plan.</li> </ul> <p>Period March 2023 onwards</p>	<i>Debasish Basu</i>






## Table of Contents

1	CHAPTER -1 .....	1
	1.1 INTRODUCTION.....	1
	1.2 Purpose of the Report: .....	1
	1.3 Identification of project proponent .....	2
	1.4 Brief Description of Nature, Size, and Location of the project: .....	2
	1.5 Scope of the study .....	6
	1.6 Compliance for Term of Reference (TOR) .....	6
2	CHAPTER -2 .....	23
	2.1 Project description:.....	23
	2.2 Type of the Project:.....	23
	2.3 Need of the project:.....	23
	2.4 Description of Mining Lease Area.....	23
	2.5 Location Details and Connectivity.....	24
	2.6 Geological profile of the area.....	24
	2.7 Geology .....	25
	2.8 Kangshabati River:.....	27
	2.9 Geomorphology .....	30
	2.10 Soil .....	32
	2.11 Drainage .....	34
	2.12 Climate and Rainfall .....	36
	2.13 Temperature .....	37
	2.14 Relative Humidity, Wind speed & Wind direction.....	37
	2.15 Hydrogeology .....	38
	2.16 Seismicity of the area .....	39
	2.17 Available reserves and production: .....	40




2.18 Production of sand: .....	42
2.19 Working Depth.....	43
2.20 Year Wise Development .....	43
2.21 Life of mine.....	43
2.22 Mining Method .....	44
2.23 Conceptual Plan of Mining .....	45
2.24 Machinery Requirement.....	46
2.25 Transportation of Minerals .....	46
2.26 Mine drainage .....	48
2.27 Stacking of mineral rejects and disposal of waste .....	48
2.28 Use of Minerals.....	49
2.29 Utilities and Proposed Site Facilities .....	49
2.30 Project Cost.....	51
<b>3 CHAPTER – 3 .....</b>	<b>52</b>
3.1 Description of Environment: .....	52
3.2 Study area and Sampling Site .....	52
3.3 Land Environment:.....	53
3.4 Land Use Land Cover of the Study Area.....	53
3.5 Conclusion of land use and land cover analysis .....	56
3.6 Soil .....	56
3.7 Conclusion of soil parameters analysis.....	58
3.8 Air Environment:.....	58
3.9 Wind Rose Observations.....	62
3.10 Ambient Air Environment: .....	62
3.11 Ambient Air Quality .....	62
3.12 Conclusion of ambient air quality:.....	65







3.13 Ambient Noise Environment:.....	66
3.14 Water Environment: .....	68
3.15 Observation & Analysis of Surface Water Quality .....	72
3.16 Biological Environment: .....	72
3.17 Existing Species Diversity and Ecological Structure of the Study Area ....	73
3.18 Socio-Economic Environment: .....	77
3.19 Objective: .....	77
3.20 Data collection: .....	77
<b>4 CHAPTER – 4 .....</b>	<b>80</b>
4.1 Anticipated Environmental Impacts and Mitigation Measures:.....	80
4.2 Land Environment: .....	80
4.3 Water Environment: .....	81
4.4 Air Environment: .....	82
4.5 Noise Environment: .....	83
4.6 Biological Environment: .....	84
4.7 Socio -Economic Environment: .....	85
4.8 Corporate Environment Responsibility .....	86
4.9 Green Belt Development Plan: .....	86
4.10 Traffic Analysis: .....	86
<b>5 CHAPTER – 5 .....</b>	<b>89</b>
5.1 Analysis of Alternatives (Technology & Site):.....	89
<b>6 CHAPTER – 6 .....</b>	<b>90</b>
6.1 Environmental Management Program: .....	90
6.2 Environmental Monitoring and Reporting Procedure.....	90
6.3 Environment Management Cell: .....	90
6.4 Environmental Monitoring Schedule:.....	91
6.5 Methodology Adopted: .....	91



6.6 Detailed budget & procurement schedules: .....	91
6.7 Conclusion: .....	91
7 CHAPTER – 7 .....	92
7.1 Additional Studies: .....	92
7.2 Risk Analysis .....	92
7.3 Risk Prioritization Based on Hazards of Mining .....	92
7.4 Mitigation Measures: .....	92
7.5 Measures to prevent incidents during Inundation/Flooding: .....	93
7.6 Precautionary Measure for sudden release of water from Upstream: .....	93
7.7 Physical Hazards due to mining operations: .....	93
7.8 Management of Health hazards: .....	94
7.9 Disaster Management Plan: .....	94
7.10 Socio Economic Impact assessment: .....	95
7.11 Assessment Resettlement and Rehabilitation: .....	95
8 CHAPTER – 8 .....	96
8.1 Project Benefits: .....	96
8.2 Employment: .....	96
8.3 Improvements in Physical Infrastructure .....	97
8.4 Improvements in Social Infrastructure .....	97
8.5 Plantation: .....	97
8.6 Other Benefits: .....	97
9 CHAPTER – 9 .....	98
9.1 Environmental Cost Benefit Analysis .....	98
10 CHAPTER – 10 .....	99
10.1 Environment Management Plan: .....	99
10.2 Air Quality Management: .....	99
10.3 Noise Pollution Control .....	100



10.4 Water Requirement and Supply .....	100
10.5 Water Quality Management: .....	100
10.6 Water pollution control measures: .....	101
10.7 Waste Management: .....	101
10.8 Land Environment: .....	101
10.9 Biological Environment: .....	102
10.10 Plantation Programme .....	102
10.11 Socio-Economic Environment: .....	103
10.12 Employment Potential: .....	103
10.13 Occupational Health & Safety Measures: .....	103
10.14 Site Services .....	104
10.15 Safety Provision: .....	104
10.16 Environmental Monitoring Programme: .....	104
10.17 Budget for Environmental Protection: .....	104
10.18 Corporate Environmental Responsibility and Health and hygiene .....	104
10.19 Environment Policy .....	105
10.20 Organization Manpower: .....	106
<b>11 CHAPTER – 11 .....</b>	<b>107</b>
11.1 Summary and Conclusion: .....	107
11.2 Environmental Monitoring Programme: .....	109
11.3 Environment Management Plan: .....	109
11.4 Details of Plantation: .....	110
11.5 Measures for Air pollution and Dust suppression: .....	110
11.6 Measures related to transportation: .....	111
11.7 Measures for controlling No <sub>x</sub> level: .....	111
11.8 Measures for controlling noise pollution: .....	111
11.9 Measures on water quality management: .....	111



12	CHAPTER – 12 .....	112
12.1	Disclosure of the Consultant .....	112
12.2	EIA TEAM.....	113
12.3	Laboratory Partner .....	113
12.4	Related all documents are attached as Annexures.....	113



## List of Figures

Figure 1-1: Malocha sand mine unit .....	3
Figure 1-2: The map showing the core zone (Mine lease area) and Buffer zone.....	4
Figure 1-3: Map showing core zone and buffer zone of the lease area along with eco-sensitive zones.....	4
Figure 1-4: The Location Plan of Sand Mining Unit, Malocha. ....	7
Figure 2-1: Physiographic Map of the Jhargram district.....	25
Figure 2-2: Geological Map of the Jhargram district.....	26
Figure 2-4: Map showing major Rivers of the along which profile section drawn .....	29
Figure 2-5: Profile Section of Kangshabati River.....	28
Figure 2-6: Cross section of Kangshabati River .....	28
Figure 2-7: Drainage Map of the district.....	29
Figure 2-8: Geomorphological Map of Jhargram .....	31
Figure 2-9: Soil Pattern of Jhargram. ....	32
Figure 2-10: Drainage Map of the study Area .....	34
Figure 2-11: Graphical representation of rainfall of Jhargram district .....	35
Figure 2-12: Hydrogeological Map of the district. ....	37
Figure 2-13: Graphical representation of pre and post monsoon water level data .....	37
Figure 2-14: Earthquake zonation map of Jhargram district.....	38
Figure 2-15: Mining location in lease area marked as red polygon. ....	40
Figure 2-16: Model Scheme of extraction of river bed sand in Mining Contract Area. ....	44
Figure 2-17: Cross section of Mining Block.....	44
Figure 2-18: Conceptual longitudinal section of River channel. ....	45
Figure 3-1: Land use & Land cover of Jhargram .....	55
Figure 3-2: Pie chart showing land use distribution of Jhargram district .....	56
Figure 3-3: Land use and Land cover of distribution of 10km buffer zone of the project area ..	56
Figure 3-4: Soil Monitoring Locations.....	58
Figure 3-5: Soil Sampling .....	58
Figure 3-6: Ambient Air Quality Monitoring. ....	59
Figure 3-7: Onsite meteorological study.....	60
Figure 3-8: Wind Rose Diagram.....	60
Figure 3-9: Wind Class Frequency Distribution.....	61
Figure 3-10: Ambient Air Quality Sampling.....	65
Figure 3-11: Ambient Noise Monitoring Locations.....	66




Figure 3-12: Ambient Noise Monitoring at site.....	66
Figure 3-13: Bar Diagram showing day and night time noise level at monitoring locations....	67
Figure 3-14: Groundwater Quality Monitoring Locations.....	68
Figure 3-15: Groundwater Sampling.....	70
Figure 3-16: Surface water Quality Monitoring Locations.....	70
Figure 3-17: Surface Water sampling .....	71
Figure 3-18: Biodiversity around the project site.....	74
Figure 3-19: Pie Diagram showing distribution of male and female population Jhargram .....	78
Figure 3-20: Pie Diagram showing total, male and female literacy rates Jhargram .....	79
Figure 3-21: School near the project site .....	79
Figure 3-22: Hospital & Health centre near the project site .....	79

## List of Tables

Table 1-1: Geographical Co-ordinates of the Mine lease area .....	3
Table 1-2: Salient features of the project site.....	5
Table 1-3: Point Wise Compliance for TOR.....	7
Table 2-1: Location Details and Connectivity .....	24
Table 2-2: Geological Succession of Jhargram.....	27
Table 2-3: Drainage system of Kangshabati River .....	27
Table 2-4: Salient features of Kangshabati River .....	28
Table 2-5: Place of origin of Kangshabati River.....	28
Table 2-6: Sediment Load Comparison between pre and post monsoon period of Kangshabati River .....	30
Table 2-7: Replenishment Rate of Kangshabati River.....	30
Table 2-8: Annual rainfall recorded in Jhargram district.....	35
Table 2-9: Monthly mean temperature (°C) distribution of Jhargram district .....	36
Table 2-10: Consideration of Resource and Reserve Calculation of the lease area.....	39
Table 2-11: Geological Reserve of Lease Area .....	39
Table 2-12: Minalable Reserve of Sand Deposit .....	39
Table 2-13: Year wise Production of Sand from project site. ....	41
Table 2-14: List of Machinery .....	45
Table 2-15: Manpower Requirement .....	46
Table 2-16: Water Requirement. ....	49
Table 2-17: Land use of project site before and after project activity .....	51
Table 3-1: Salient Features of Baseline Environmental Studies. ....	53
Table 3-2: Land utilization statistics of the district.....	55
Table 3-3: Land use and land cover of the buffer zone.....	55
Table 3-4: GPS Coordinate of Soil Sample collection location .....	57
Table 3-5: Soil parameters lab analysis results. ....	57
Table 3-6: GPS Coordinates of Air Sample collection location .....	62
Table 3-7: Particulate Matter concentration at different site – PM10. ....	62
Table 3-8: Particulate Matter concentration at different site– PM 2.5 .....	62
Table 3-9: Sulphur dioxide (SO <sub>2</sub> ) concentration at different site.....	62
Table 3-10: Nitrogen dioxide (NO <sub>2</sub> ) Free Silica (Si) concentration at different site.....	62
Table 3-11: Carbon Monoxide (CO) concentration at different site.....	62
Table 3-12: Free Silica (Si) concentration at different site.....	63



Table 3-13: Monitoring results of the Noise level in and around project site.....	67
Table 3-14: GPS Coordinates of Ground water Sample collection location.....	68
Table 3-15: GPS Coordinates of Surface water Sample collection location.....	69
Table 3-16: Analysis results of ground water .....	70
Table 3-17: Analysis results of surface water .....	70
Table 3-18: List of Tree species found within 5km radius of the mining lease area .....	73
Table 3-19: List of Shrub species found within 5km radius of the mining lease area .....	73
Table 3-20: List of Herb species found within 5km radius of the mining lease area.....	73
Table 3-21: List of Faunal Species Found within 5 km radius of the mining lease area.....	75
Table 3-22: Nearest Communication & Infrastructure from the project site.....	79
 Table 4-1: Anticipated Impacts on Land Environment.....	 81
Table 4-2: Anticipated Impacts on Water Environment. ....	82
Table 4-3: Anticipated Impacts on Air Environment.....	83
Table 4-4: Anticipated Impacts on Noise Environment.....	84
Table 4-5: Anticipated Impacts on Socio-economic Environment. ....	86
Table 4-6: Anticipated Impacts on Corporate Environment Responsibility .....	87
Table 7-1: Management of Health Hazards. ....	93
Table 10-1: Proposed Budget for Environmental Monitoring/Protection.....	103
Table 10-2: Proposed Budget for CER.....	104
Table 10-3: Manpower requirement for Environment Management & Monitoring .....	105
Table 11-1: Salient Features of Baseline Environmental Studies. ....	107
Table 12-1: EIA Team.....	112
Table 12-2: Laboratory Partner. ....	112






### **List of Abbreviations**

<b>Abbreviation</b>	<b>Definitions</b>
<b>AAQ</b>	Ambient Air Quality
<b>bgl</b>	Below Ground Level
<b>BOD</b>	Biochemical Oxygen Demand
<b>COD</b>	Chemical Oxygen Demand
<b>CPCB</b>	Central Pollution Control Board
<b>CSR</b>	Corporate Social Responsibility
<b>dB</b>	Decibel
<b>DO</b>	Dissolved Oxygen
<b>EAC</b>	Expert Appraisal Committee
<b>EIA</b>	Environmental Impact Assessment
<b>EMC</b>	Environmental Management Cell
<b>EMP</b>	Environment Management Plan
<b>EPA</b>	The Environment Protection Act
<b>GLC</b>	Ground Level Concentration
<b>Ha</b>	Hectare
<b>Ham</b>	Hectare Meter
<b>HFL</b>	High Flood Level
<b>KLD</b>	Kilo litre Per Day
<b>Km</b>	Kilo Meter
<b>Leq</b>	Equivalent Noise Level
<b>LFL</b>	Low Flood Level
<b>LOS</b>	Level of Service
<b>MoEF</b>	Ministry of Environment and Forest & Climate Change
<b>NABET</b>	National Accreditation Board for Education and Training
<b>NGO</b>	Non Governmental Organisation
<b>NH</b>	National Highway
<b>NOC</b>	No Objection Certificate
<b>OSHA</b>	Occupational Safety and Health Administration
<b>PCU</b>	Passenger Car Unit
<b>PM</b>	Particulate Matter
<b>PUC</b>	Pollution Under Control
<b>QCI</b>	Quality Council of India
<b>R &amp; R</b>	Rehabilitation & Resettlement
<b>RBM</b>	River Bed Material
<b>RL</b>	Reduced Level
<b>SEAC</b>	State Expert Appraisal Committee
<b>SH</b>	State Highway
<b>SPCB</b>	State Pollution Control Board
<b>T/cum</b>	Tons Per Cubic Meter
<b>TKN</b>	Total Kjeldahl Nitrogen




**DRAFT EIA REPORT FOR “AUSGRAM-II SAND MINE (MIN\_EBUR\_24)”**  
**MINE AREA:** 9.15 Ha, **J.L. NO.:** 36, **PLOT NO.:** 254(P),251(P),201(P) & 263(P)  
**MOUZA:** Malocha, **P.S.:** Burdwan, **BLOCK:** Ausgram-II, **DISTRICT:** Purba Bardhaman

<b>TOR</b>	Term of Reference
<b>TPA</b>	Tonnes Per Annum
<b>UNFC</b>	United Nations Framework Classification
<b>VWG</b>	Village Working Group



## **List of Annexure:**

<b>Annexure no</b>	<b>Details</b>
Annexure -I	Mining Plan Approval letter
Annexure -II	Terms of Reference (TOR) letter
Annexure -III	Letter of Intent
Annexure -IV	Approved Mining Plan
Annexure -V	Project site located on Toposheet
Annexure -VI	Soil Test Report
Annexure -VII	Ambient Air Quality Monitoring Report
Annexure -VIII	Weather Data Reports
Annexure -IX	Ambient Noise Monitoring Report
Annexure - X	Ground Water Test Report
Annexure -XI	Surface Water Test reports
Annexure -XII	Transportation Route Map
Annexure -XIII	NABL accreditation certificate of Laboratory
Annexure -XIV	NABET Accreditation Certificate of EIA Consultant
Annexure -XIII	CER Undertaking



## **Executive Summary**

The proposed project is the riverbed sand mining of Ajay River located under Mouza- Malocha, Plot No.- 254(P),251(P),201(P) & 263(P), J.L. No.- 36, P.S: Burdwan, District- Purba Bardhaman, West Bengal of “West Bengal Mineral Development & Trading Corporation Limited”. The proposed project would have 9.15 hectares of land for five years. The area is in Survey of India Toposheet No. F45D10 (73M/10) and bounded by latitude 23°36'15.902"N to 23°36'13.755"N and longitude 87°38'52.154" E to 87°38'59.313" E. The area is non-forest land in nature. The area is predominantly flat with riverbed sand having elevation ranges from 86 m to 95m above mean sea level.

As per MoEF&CC, New Delhi Gazette dated 14<sup>th</sup> September 2006 and amended thereafter, the proposed mining project is categorized as category ‘B1’ project.

The mining plan has been prepared by Qualified Person Dr. N.B.Chanda and approved for five years by Chief Mining Officer, G.P. Branch, S.B. Unit, Asansol, Govt. of West Bengal.

The proposed activity is supposed to collect approximately 9,27,810.00 Cu.m of sand for a total of five years. The extraction of sand will be restricted within the central 3/4thwidth of the river and will be carried out through an open cast manual method. The proposed activity does not require any drilling and blasting in mining activities.

The lease area comes under ‘waterbody LULC type as per Land use Landcover Classification of Purba Bardhaman district of West Bengal, and the surrounding land use type is a mixture of agricultural land with settlement.


There is no permanent influx of the population anticipated, as the workers will be hired locally from nearby villages. Unemployment is very pervasive in the study area. A total manpower of 90 nos will be involved with the project, with 2 nos. of technical personnel (manager/supervisor), 26 nos of skilled and 60 nos. of non-skilled labours. It is expected that a large part of the investment in this project will be direct/ indirect role on local population. Hence there will be an overall improvement of the socio-economic status of the people of surrounding areas.

A total water requirement of 10 KLD will be envisaged with the proposed project, with 2 KLD allocated for drinking purposes, 4 KLD allocated for maintenance of green belt, and 4 KLD for dust suppression.

2 nos. of excavator of capacity 1.5 cum, 35-40 nos. of tipper truck of capacity 10 cum and 2 nos. of water sprinkler truck of capacity 10 cum will be deployed for the proposed activity.

The total cost of the project is approx., 9.829 crores for five years, one year would be approx., 1.966 crores and there is a budgetary provision that 5% (0.098 crore peryear) of the project cost will be allocated for the Environmental Management Plan (EMP) and 2% (0.039 crore per year) of the





**DRAFT EIA REPORT FOR “AUSGRAM-II SAND MINE (MIN\_EBUR\_24)”**  
**MINE AREA:** 9.15 Ha, **J.L. NO.:** 36, **PLOT NO.:** 254(P),251(P),201(P) & 263(P)  
**MOUZA:** Malocha, **P.S.:** Burdwan, **BLOCK:** Ausgram-II, **DISTRICT:** Purba Bardhaman

project cost will be allocated for Corporate Environmental Responsibility (CER) and health and hygiene (H&H) for causes of poor people of nearby villages. Health and Hygiene will be allocated for a health check-up once in six-months. Extra budgetary provisions will be allocated to lady workers. The Total expenditure of welfare scheme i.e., EMP + CRP & H&H = 7% (0.13762 crore per year).

# CHAPTER – 1

## 1.1 INTRODUCTION

The mining industry in India is a major economic activity which contributes significantly to the economy of India. The Mining and quarrying sector contributes around 2.5% of the Gross Domestic Product (GDP). The mining sector under index of Industrial Production (IIP) witnessed a growth of 1.7 percent Year on Year basis. Indian economy is on the aspirational path of becoming a \$5 trillion GDP economy by 2024-25. The Mining Industry is going to make a sizable contribution to the envisaged GDP and wealth creation. India, being a developing economy, is dependent on the growth of energy sector to achieve the desired economic growth. The economic reforms in the past, has propelled Indian mining industry into a new and competitive environment.

Unless mining of the minerals is properly regulated, they can show adverse consequences on environment and socio-economic components of the society. It also disturbs the Air, soil, water and ecological parameters. On the other hand, it develops the economic standard of the region. Issues of Technology for zero waste or low waste mining, relief & rehabilitation, mine closure which otherwise leads to land degradation are important issues which require continuous attention. In order to mitigate the impact of mineral mining on the environment, a scientific assessment is very important for framing sustainable development strategies. Therefore, the implementation of scientific mining principles through EIA & EMP plays a vital role in sustainable economic growth of our country.

## 1.2. Purpose of the Report

The Environmental Impact Assessment has been prepared to access the present scenario of the study area for the proposed mining activity. Based on the assessment an environment management plan (EMP) has been prepared, which helps in minimizing the adverse effects of the mining on the surrounding environment.

The draft EIA report is being prepared to comply with the Term of reference (TOR) received from MoEF&CC under EIA notification of MoEF dated 1<sup>st</sup> November and its amendments for seeking environmental clearance for sand mining in Ajay riverbed over an area of 9.15 Ha. in Mouza- Malocha, P.S.: Burdwan of Purba Bardhaman District of West Bengal. The project proponent has submitted application for prior Environmental Clearance (EC) and West Bengal State Expert Appraisal Committee has considered the same during the 73<sup>rd</sup> meeting held on 23.03.2023, subsequent to the discussions held on 25.04.2023, State Environmental Impact Assessment Authority (SEIAA) has issued the Terms of Reference (ToR) for conducting the Environmental

Impacts Assessment (EIA) study and to prepare EIA report for conducting the Public hearing as part of Environment Clearances Process. This Environmental Impact Assessment (EIA) report is prepared to comply with the Terms of Reference (TOR) received from SEIAA under EIA notification of the MoEF dated 14-9-2006, and its amendments of MoEF&CC, Govt. of India, for seeking Environmental Clearance (EC) for sand mining in the applied mining lease area measuring 9.15 Ha falling under category "BI".

### **1.3. Identification of the Project Proponent**

The proposed mine lease was granted to “**West Bengal Mineral Development & Trading Corporation Limited**” on 2<sup>nd</sup> May 2023. The mining plan for the Mine lease (ML) area has been approved by Chief Mining Officer, Dte of Mines & Minerals, G. P. Branch, S.B. Unit, Asansol, vide letter no 233/CMO/XVI/EBUR (552) dated 10<sup>th</sup> July, 2023. Attached as **Annexure-I**

- **Project proponent**

**“West Bengal Mineral Development & Trading Corporation Limited”**

WBIIDC Building, 3rd Floor, DJ-Block, DJ-10, Sector- II,

Bidhanagar (Salt Lake City),

Kolkata: 700091

### **1.4. Brief Description of Nature, Size, and Location of the project:**

- **Nature of the project:**

The Open Cast Mining method is proposed in the lease area.

- **Size of the project:**

As per the approved mining plan vide letter no 233/CMO/XVI/EBUR (552) dated 10<sup>th</sup> July, 2023, riverbed sand mining will be undertaken over an area of 9.15 Ha. for production of 9,27,810.00 Cu. M of sand for a contract period of Concession of 5 (five) years.

- **Anticipated Life of Project and Cost of the Project:**

The period of concession of the mine lease is 5 years based on the level of exploration and reserve established. The cost of mining lease, mining equipment, environmental protection, and socioeconomic development for the present mine lease area is about Rs 9.829 Crores (For Five Year).

- **Location of the project:**


The proposed Malocha sand mine unit comes under Mouza- Malocha, JL No.: 36, Plot No.: 254(P),251(P),201(P) & 263(P) P.S.- Burdwan, of Purba Bardhaman district of West Bengal.

Geographically the ML area extends from latitude 23°36'15.902"N to 23°36'13.755"N and longitude 87°38'52.154" E to 87°38'59.313" E. The highest elevation of the river sand bed is 95 m AMSL, and the lowest elevation of the lease area is 86 m AMSL. The proposed area falls in SOI top sheet No. F45D10(73 M/10). The study area map is shown in figure 1-1. The study area of the proposed project comprises 10 Km radius around the mining lease boundary. The map showing the core zone (Mine lease area) and Buffer zone (10 km radius from the lease boundary) is shown in Figure1-2.

The Mine Lease area is approx. 45.90 Km of aerial distance from the district headquarters at Purba Bardhaman. The proposed ML area can be approached by its own conveyance from NH 19, which is 21.19 Km away from the ML area on the Southern bank of Ajay River.


**Table 1-1: Geographical Co-ordinates of the Mine lease area.**

POINT No.	LATITUDE	LONGITUDE
1	23° 36' 15.902" N	87° 38' 52.154" E
2	23° 36' 16.831" N	87° 38' 52.243" E
3	23° 36' 18.877" N	87° 39' 17.521" E
4	23° 36' 15.973" N	87° 39' 19.306" E
5	23° 36' 12.582" N	87° 39' 08.933" E
6	23° 36' 12.638" N	87° 39' 04.989" E
7	23° 36' 13.755" N	87° 38' 59.313" E




**Figure 1-1: Malocha sand mining unit (MIN\_EBUR\_24)**





**Fig no 1.2 –Map showing core zone and buffer zone of the lease area**



**Fig no 1.3 –Map showing core zone and buffer zone of the lease area along with eco-sensitive zones**






**DRAFT EIA REPORT FOR “AUSGRAM-II SAND MINE (MIN\_EBUR\_24)”**  
**MINE AREA: 9.15 Ha, J.L. NO.: 36, PLOT NO.: 254(P),251(P),201(P) & 263(P)**  
**MOUZA: Malocha, P.S.: Burdwan, BLOCK: Ausgram-II, DISTRICT: Purba Bardhaman**

**Table 1.2: Salient Features of the Project Site**

1.	Project Name	Malocha Sand Mine					
2	Location of the Project	Mouza- Malocha Plot No.- 254(P),251(P),201(P) & 263(P)/J.L. No.- 36, P.S: Burdwan, District- Purba Bardhaman, West Bengal					
3	Mine Lease Area	9.15Ha					
4	Latitude & Longitude	LATITUDE			LONGITUDE		
		23° 36' 15.902" N			87° 38' 52.154" E		
		23° 36' 16.831" N			87° 38' 52.243" E		
		23° 36' 18.877" N			87° 39' 17.521" E		
		23° 36' 15.973" N			87° 39' 19.306" E		
		23° 36' 12.582" N			87° 39' 08.933" E		
		23° 36' 12.638" N			87° 39' 04.989" E		
23° 36' 13.755" N			87° 38' 59.313" E				
5	Toposheet Number	73M/10					
6	Type of Land	Riverbed					
7	Elevation	Highest Elevation:95 m AMSL, Lowest Elevation: 86 m AMSL					
8	Project Cost	9.829 crores (5 year)					
9	Manpower & No. of Working days	90 personnel for 200 Days/Year.					
10	Water Demand & Source	10 KLD, Source: Deep tube wells will be installed at site for drinking water with necessary treatment plant.					
11	Mineable Reserves	9,27,810 Cu. M					
12	Targeted Production	1,85,562 Cu. M annually					
13	Production Capacity	Years	Production Area (Ha)	Thickness (m)	Replenishment Rate (%)	Volume (m³)	
		1 <sup>st</sup>	7.93	3.00	100	2.37,900.00	
		2 <sup>nd</sup>	7.93	2.175	72.50	1,72,477.50	
		3 <sup>rd</sup>	7.93	2.175	72.50	1,72,477.50	
		4 <sup>th</sup>	7.93	2.175	72.50	1,72,477.50	
		5 <sup>th</sup>	7.93	2.175	72.50	1,72,477.50	
		Average Mineable Reserve (Cu.M)					9,27,810.00
		Total Mineable Reserve (C.Ft)					3.276 Cr
14	Type of Mining	Opencast Method					
15	Seismic Zone	Seismic Zone-III (As per 1893:2002)					
16	End Use of Product	For construction of Buildings and Roads					
17	Nearest Town	Bolpur City is Located at 7.8 km NE direction.					
18	Nearest Airport	Durgapur Airport is 35 KM SW Direction.					
19	Nearest railway Station	Bhedia Railway station is 6.2 kms SE direction.					
20	Nearest Highway	State Highway 2B is about 5.5 Kms along the Eastern direction from the lease area.					
21	Neares Sanctuary /National Park /Eco-Sensitive Zone/Elephant Corridor/Conservation Reserve,	Ramnabagan Wildlife sanctuary 10 km SW of lease area					
22	Nearest reserve forest (with name and its distance from the proposed project site)	No part of the proposed lease area falls under forest.					
23	Local geology of the area	The applied lease is Riverbed.					



## 1.5. Scope of the Study

The scope of the study includes a detailed characterization of the environment in an area of 10 Km radius of the Mine Lease Area for various environmental parameters like Ambient Air, Water, Noise, and Land, Biological and Socio-economic aspects.

## 1.6. Compliance for Terms of References (TOR)

The project proposal was submitted to State Level Environment Impact Assessment Authority of West Bengal for its appraisal. Based on which, SEAC meeting held on 30<sup>th</sup> July 2022 for Terms of Reference (TOR). Based on the data provided, TOR of proposed Sand mining project has been issued by SEIAA, West Bengal vide File no SEIAA.3069/2022/TOR/788 dated 23<sup>rd</sup> August 2022 (**Refer Annexure - 4**). The compliance of TOR is described below in Table 1.2.

**Table 1.3: TOR Compliance**

S. No	TOR	Compliance
1.	Year-wise production details since 1994 should be given, clearly stating the highest production achieved in any one year prior to 1994. It may also be categorically informed whether there had been any increase in production after the EIA Notification 1994 came into force, w.r.t. the highest production achieved prior to 1994.	This is a new Mining Project.
2.	A copy of the document in support of the fact that the Proponent is the rightful lessee of the mine should be given.	Copy of document in support of the fact that the Proponent is the rightful lessee of the mine ( <b>LOI</b> ) is enclosed with draft EIA report as <b>Annexure-III</b> .
3.	All documents including approved mine plan, EIA and Public Hearing should be compatible with one another in terms of the mine lease area, production levels, waste generation and its management, mining technology etc. and should be in the name of the lessee.	All documents including mine plan, draft EIA are compatible with one another in terms of mine area, production levels, waste generation and its management if any, mining technology etc. All documents are in the name of the lessee and the same for final EIA and Public Hearing
4.	All corner coordinates of the mine lease area, superimposed on a High-Resolution Imagery/ toposheet, topographic sheet, geomorphology and geology of the area should be provided. Such an Imagery of the proposed area should clearly show the land use and other ecological features of the study area (core and buffer zone).	All corner coordinates of the mine lease area, are superimposed on a High-Resolution Imagery/ toposheet, topographic sheet, geomorphology and geology of the area are provided in figure no.1.1 and 1.2 The land use and other ecological features of the study area (core and buffer zone) are shown in figure 1.3.



S. No	TOR	Compliance
<b>5.</b>	Information should be provided in Survey of India Toposheet in 1:50,000 scale indicating geological map of the area, geomorphology of landforms of the area, existing minerals and mining history of the area, important water bodies, streams and rivers and soil characteristics.	The topographic map of the study area is presented in Annexure –V (Original Toposheet with super impose project site).
<b>6.</b>	Details about the land proposed for mining activities should be given with information as to whether mining conforms to the land use policy of the State; land diversion for mining should have approval from State land use board or the concerned authority.	The Letter of Intent was issued by Government of West Bengal and is enclosed in <b>Annexure-III</b>
<b>7.</b>	It should be clearly stated whether the proponent Company has a well laid down Environment Policy approved by its Board of Directors? If so, it may be spelt out in the EIA Report with description of the prescribed operating process/procedures to bring into focus any infringement/deviation/violation of the environmental or forest norms/ conditions? The hierarchical system or administrative order of the Company to deal with the environmental issues and for ensuring compliance with the EC conditions may also be given. The system of reporting of non-compliances / violations of environmental norms to the Board of Directors of the Company and/or shareholders or stakeholders at large, may also be detailed in the EIA Report.	Lessee is an individual owner of the mine lease however a well laid down Environment policy to take care of any infringement /deviation/ violation of the environmental or forest norms/ conditions applicable for the mine lease is proposed in the EIA report in Chapter 10

S. No	TOR	Compliance
8.	Issues relating to Mine Safety, including subsidence study in case of underground mining and slope study in case of open cast mining, blasting study etc. should be detailed. The proposed safeguard measures in each case should also be provided.	Method of mining for the sand mine is open cast semi-mechanized method (No drilling and blasting involved) discussed in Chapter 7, with this EIA report. (Refer Annexure IV: Approved Mining Plan).
9.	The study area will comprise of 10 km zone around the mine lease from lease periphery and the data contained in the EIA such as waste generation etc. should be for the life of the mine / lease period.	The study area of the proposed project comprises of a 10 km radius around the mining Lease boundary. Map showing study area (10km radius from the lease boundary) is given in chapter-3 of EIA Report. EIA contains the data regarding proposed production for the life of mine and the same has been incorporated in Chapter-2.
10.	The study area will comprise of 10 km zone around the mine lease from lease periphery and the data contained in the EIA such as waste generation etc. should be for the life of the mine / lease period.	The proposed mine lease area is riverbank land. The study area comprises of RF, agricultural land, waterbodies, human settlements, and other ecological features involved. LU&LC Statistics presented.
11	Details of the land for any Over Burden Dumps outside the mine lease, such as extent of land area, distance from mine lease, its land use, R&R issues, if any, should be given.	Not applicable, as there is no overburden in the proposed Sand mining activity. No R&R involved.
12	A Certificate from the Competent Authority in the State Forest Department should be provided, confirming the involvement of forest land, if any, in the project area. In the event of any contrary claim by the Project Proponent regarding the status of forests,	The proposed mine lease area is riverbank land. There is no forest/tree clearance involved in the proposed project. However, Letter of Int for mining lease area was issued by






S. No	TOR	Compliance
	the site may be inspected by the State Forest Department along with the Regional Office of the Ministry to ascertain the status of forests, based on which, the Certificate in this regard as mentioned above be issued. In all such cases, it would be desirable for representative of the State Forest Department to assist the Expert Appraisal Committees.	Govt. of West Bengal, Dept. of Industry, Commerce & Tender Price, Mines Branch, vide letter no. 261 – ICE – 12011(99)\27\2022- MINES SEC- Dept. of ICE dated 20.04.2023 <b>(Annexure-III)</b>
13	Status of forestry clearance for the broken up area and virgin forestland involved in the Project including deposition of net present value (NPV) and compensatory afforestation (CA) should be indicated. A copy of the forestry clearance should also be furnished.	The proposed mine lease area is river bank land. There is no forest/tree clearance involved in the proposed project. However, Letter of Intent for mining lease area was issued by Govt. of West Bengal, Dept. of Industry, Commerce & Tender Price, Mines Branch, vide letter no. 261 – ICE – 12011(99)\27\2022- MINES SEC- Dept. of ICE dated 20.04.2023 <b>(Annexure-III)</b>
14.	Details of the land for any Over Burden Dumps outside the mine lease, such as extent of land area, distance from mine lease, its land use, R&R issues, if any, should be given.	Not applicable The area does not come under tribal area, hence, “Scheduled Tribes and other Traditional Forest Dwellers (Recognition of Forest Rights) Act, 2006” is not applicable.
15.	The vegetation in the RF / PF areas in the study area, with necessary details, should be given.	No Reserve Forest is falling within 10 km radius of the proposed mining activity. Ajodhya hill and Forest reserve is situated 62 km WSW direction of the forest. Please refer to figure 1.3.



S. No	TOR	Compliance
16.	A study shall be got done to ascertain the impact of the Mining Project on wildlife of the study area and details furnished. Impact of the project on the wildlife in the surrounding and any other protected area and accordingly, detailed mitigative measures required, should be worked out with cost implications and submitted.	In this proposed mining activity, there is no impact on wildlife. Biological Study for the project has been conducted. Impact and Mitigation measures are incorporated in Chapter - 4.
17.	Location of National Parks, Sanctuaries, Biosphere Reserves, Wildlife Corridors, Ramsar site, Tiger/ Elephant Reserves/(existing as well as proposed), if any, within 10 km of the mine lease should be clearly indicated, supported by a location map duly authenticated by Chief Wildlife Warden. Necessary clearance, as may be applicable to such projects due to proximity of the ecologically sensitive areas as mentioned above, should be obtained from the Standing Committee of National Board of Wildlife and copy furnished.	There are no National parks, Sanctuaries, Biosphere Reserves, Wildlife Corridors, Tiger / Elephant Reserves (existing as well as proposed) in the core area. A map of west Bengal creating with existing NP (National Park) and (WLS) (Wildlife Life Sanctuaries) is provided in (Refer figure 1.3).
18.	A detailed biological study of the study area [core zone and buffer zone (10 km radius of the periphery of the mine lease)] shall be carried out. Details of flora and fauna, endangered, endemic and RET Species duly authenticated, separately for core and buffer zone should be furnished based on such primary field survey, clearly indicating the Schedule of the fauna present. In case of any scheduled-I fauna found in the study area, the necessary plan along with budgetary provisions for their conservation should be prepared in consultation with State Forest and Wildlife Department and details furnished. Necessary allocation of funds for implementing the	There is no schedule-I fauna present in the study area. A detailed biological study is discussed under Chapter-3



S. No	TOR	Compliance
	same should be made as part of the project cost.	
19.	Proximity to Areas declared as 'Critically Polluted' or the Project areas likely to come under the 'Aravali Range', (attracting court restrictions for mining operations), should also be indicated and where so required, clearance certifications from the prescribed Authorities, such as the SPCB or State Mining Department should be secured and furnished to the effect that the proposed mining activities could be considered.	Not Applicable. The proposed project does not fall within 10 Km radius of any “ <b>Critically Polluted</b> ” area and The project area does not fall in “Aravali hill” ranges.
20.	Similarly, for coastal Projects, A CRZ map duly authenticated by one of the authorized agencies demarcating LTL, HTL, CRZ area, location of the mine lease w.r.t CRZ, coastal features such as mangroves, if any, should be furnished. (Note: The Mining Projects falling under CRZ would also need to obtain approval of the concerned Coastal Zone Management authority)	Not Applicable, as the proposed project does not fall within CRZ area.
21.	R&R Plan/compensation details for the Project Affected People (PAP) should be furnished. While preparing the R&R Plan, the relevant State/National Rehabilitation & Resettlement Policy should be kept in view. In respect of SCs /STs and other weaker sections of the society in the study area, a need based sample survey, family-wise, should be undertaken to assess their requirements, and action programmer prepared and submitted accordingly, integrating the sectoral programmer of line departments of the State Government. It may be clearly brought out whether the village(s) located in the mine lease area will be shifted or not. The issues relating to shifting of village(s) including their R&R	There will be no resettlement or rehabilitation involved in the project area, hence compensation details are not applicable.



S. No	TOR	Compliance
	and socio-economic aspect should be discussed in the Report	
22.	One season (non-monsoon) [i.e. March-May (Summer Season); October-December (post monsoonseason) ; December-February (winter season)] primary baseline data on ambient air quality as per CPCB Notification of 2009, water quality, noise level, soil and flora and fauna shall be collected and the AAQ and other data so compiled presented date-wise in the EIA and EMP Report. Site-specific meteorological data should also be collected. The location of the monitoring stations should be such as to represent whole of the study area and justified keeping in view the pre-dominant downwind direction and location of sensitive receptors. There should be at least one monitoring station within 500 m of the mine lease in the pre-dominant downwind direction. The mineralogical composition of PM10, particularly for free silica, should be given.	One season data of ambient air quality, water quality, noise level, meteorology, soil and flora and fauna has been collected from March' 2023 to May'2023 Details are given in Chapter 3
23.	Air quality modelling should be carried out for prediction of the impact of the project on the air quality of the area. It should also take into account the impact of movement of vehicles for transportation of minerals. The details of the model used, and input parameters used for modelling should be provided. The air quality contours may be shown on a location map clearly indicating the location of the site, location of sensitive receptors, if any, and the habitation. The wind roses showing pre- dominant wind direction may also be indicated on the map	The detailed Air Quality modelling will be incorporated in Final EIA report



S. No	TOR	Compliance
24.	The water requirement for the Project, its availability and source should be furnished. A detailed water balance should also be provided. Fresh water requirement for the Project should be indicated.	The total water requirement will be 10 KLD which will be sourced from locality. The water required for domestic and drinking purposes will be 2 KLD which will be Ground water sourced from nearby localities whose permission would be taken from local governmental bodies at the time of CTO. Other 8 KLD's would be required for the purposes of dust suppression and plantation programmer Which would be sourced from near Ajay River.
25.	Necessary clearance from the Competent Authority for drawl of requisite quantity of water for the Project should be provided.	Necessary clearance from the Competent Authority for drawl of requisite quantity of water for the Project would be obtained at the time of CTO.
26.	Description of water conservation measures proposed to be adopted in the Project should be given. Details of rainwater harvesting proposed in the Project, if any, should be provided.	Water requirements will be met from the deep tube wells installed at the site. But later on, when the mine sump will be developed and water will get accumulated in the sumps, then ground water will be drawn only for drinking & sanitation purpose and rest of the requirement will be fulfilled from water accumulated in the mine sump, thereby conserving the natural water resources
27.	Impact of the Project on the water quality, both surface and groundwater, should be assessed and necessary safeguard measures, if any required,	Mining will be done as per the approved Mine Plan and applicable Rules & Regulation, so that there is no



S. No	TOR	Compliance
	should be provided.	<p>damage to ground water recharge potential due to sandmining.</p> <ul style="list-style-type: none"> <li>➤ There will be no change in surface water quality as rivers are seasonal.</li> <li>➤ Ground water quality will not be affected due to mining activities as it is restricted to 3.00 m depth.</li> <li>➤ Mining will not be allowed below the water table.</li> <li>➤ Regular monitoring of water samples will be done as precautionary measures.</li> </ul>
28.	Based on actual monitored data, it may clearly be shown whether working will intersect groundwater. Necessary data and documentation in this regard may be provided. In case the working will intersect groundwater table, a detailed Hydro Geological Study should be undertaken, and Report furnished. The Report inter-alia shall include details of the aquifers present and impact of mining activities on these aquifers. Necessary permission from Central Ground Water Authority for working below ground water and for pumping of ground water should also be obtained and copy furnished.	The proposed mining will be done well above the ground water table. Hence no adverse impact on ground water table. Please refer to Hydro Geological map and data furnished in chapter 2, Figure No.- 2.11
29.	Details of any stream, seasonal or otherwise, passing through the lease area and modification / diversion proposed, if any, and the impact of the same on the hydrology should be brought out.	The proposed mine lease area itself is in the riverbed. But there is no diversion of the any stream. Hence there is no impact on the water course.
30.	Information on site elevation, working depth, groundwater table etc. Should be provided both in	The site is at an elevation of (highest 86 - lowest 95) m AMSL. The slicing





S. No	TOR	Compliance
	AMSL and bgl. A schematic diagram may also be provided for the same.	of the sand will be done up to 3mts only. No obstruction of the water table.
31.	A time bound Progressive Greenbelt Development Plan shall be prepared in a tabular form (indicating the linear and quantitative coverage, plant species and time frame) and submitted, keeping in mind, the same will have to be executed up front on commencement of the Project. Phase-wise plan of plantation and compensatory afforestation should be charted clearly indicating the area to be covered underplantation and the species to be planted. The details of plantation already done should be given. The plant species selected for green belt should have greater ecological value and should be of good utility value to the local population with emphasis on local and native species and the species which are tolerant to pollution.	Plantation programmer is given in Chapter- 10
32.	Impact on local transport infrastructure due to the Project should be indicated. Projected increase in truck traffic as a result of the Project in the present road network (including those outside the Project area) should be worked out, indicating whether it is capable of handling the incremental load. Arrangement for improving the infrastructure, if contemplated (including action to be taken by other agencies such as State Government) should be covered. Project Proponent shall conduct Impact of Transportation study as per Indian Road Congress Guidelines.	<p>There is no major impact on local transport as 98 trips per day will be required for the transport of mined out material from proposed project. The LOS value from the proposed mine is excellent and very good for all villages. Traffic Management &amp; Mitigation Measures are included.</p> <ul style="list-style-type: none"> <li>➤ Haul roads will be sprinkled with water to keep the dust suppressed.</li> <li>➤ Proper route management of the traffic will be done for smooth ingress and egress of traffic.</li> <li>➤ Supervisors will be appointed to</li> </ul>



S. No	TOR	Compliance
		<p>regulate the traffic at the project sites.</p> <ul style="list-style-type: none"> <li>➤ Speed breakers will be constructed in accident prone areas to calm the traffic and its speed.</li> <li>➤ Signposts will be erected at the sensitive and precarious places to caution or provide information to road users.</li> </ul>
33.	Details of the onsite shelter and facilities to be provided to the mine workers should be included in the EIA Report	<p>Onsite shelter and facilities will be provided to the mine workers as per Approved Mining Plan &amp; as per Mines Rules.</p> <ul style="list-style-type: none"> <li>➤ Following are the infrastructural facilities which will be provided to the workers:</li> <li>➤ First aid facilities will be provided.</li> </ul>
34.	Conceptual post mining land use and Reclamation and Restoration of mined out areas (with plans and with adequate number of sections) should be given in the EIA report	<p>The proposed mine is in the riverbed, the reclamation of the mined-out areas will be gradually filled up with sand carried out by water, during monsoon. Hence rehabilitation of the mined-out area is not applicable.</p>
35.	Occupational Health impacts of the Project should be anticipated, and the proposed preventive measures spelt out in detail. Details of pre-placement medical examination and periodical medical examination schedules should be incorporated in the EMP. The project specific occupational health mitigation measures with required facilities proposed in the mining area may be detailed.	<p>All safety measures prescribed under mining laws will be followed strictly. All workers will be medically examined in pre placement phase. Periodical medical examination as per Mines Rule 1955- should be done. The persons working in dusty environment should be examined every year as per the DGMS circular No. 01 of 21.01.2010. Medical</p>

S. No	TOR	Compliance
		examination will be as per the medical fitness prescribed under Form P and PI of the Mines Rule 1955, amended by Mines (amendment) Rules, 1989. The details of Occupational health impact of project are described under Chapter 10.
36.	Public health implications of the Project and related activities for the population in the impact zone should be systematically evaluated and the proposed remedial measures should be detailed along with budgetary allocations.	The workers' health check-up will be done in every six month. Medical camp will be organized in impact zone under CSR activity.
37.	Measures of socio-economic significance and influence to the local community proposed to be provided by the Project Proponent should be indicated. As far as possible, quantitative dimensions may be given with time frames for implementation.	Measures of socio-economic influence to the local community have been furnished and described under Chapter 10.
38.	Detailed environmental management plan (EMP) to mitigate the environmental impacts which, should inter-alia include the impacts of change of land use, loss of agricultural and grazing land, if any, occupational health impacts besides other impacts specific to the proposed Project.	Environmental Management Plan is address in Chapter 10.
39.	Public Hearing points raised and commitment of the Project Proponent on the same along with time bound Action Plan with budgetary provisions to implement the same should be provided and also incorporated in the final EIA/EMP Report of the Project.	Will incorporate after public hearing.

S. No	TOR	Compliance
40.	Details of litigation pending against the project, if any, with direction /order passed by any Court of Law against the Project should be given.	There is no litigation against the applicant and the lease area in any court of law to the best of our knowledge.
41.	The cost of the Project (capital cost and recurring cost) as well as the cost towards implementation of EMP should be clearly spelt out.	Initial Project Cost- 1.966 crores Cost for Environmental Protection Measures Capital Cost-Rs 0.098 crores per annum.
42.	A Disaster management Plan shall be prepared and included in the EIA/EMP Report.	Disaster management Plan have been furnished.
43.	Benefits of the Project if the Project is implemented should be spelt out. The benefits of the Project shall clearly indicate environmental, social, economic, employment potential, etc.	<p>The project proponent has proposed to provide financial assistance of 2% of project cost for the development of social infrastructure of the area. Following measure will be taken to improve the social infrastructure of the study area:</p> <ul style="list-style-type: none"> <li>➤ Preventive medical care and educational facilities for rural population shall be promoted.</li> <li>➤ Priority will be given to local people for employment.</li> <li>➤ Indirect Employment through contractual services shall be provided.</li> <li>➤ Extending general benefit by way of development work in the villages through respective Gram Panchayat.</li> <li>➤ Supplementing Govt, efforts in health monitoring camps, social</li> </ul>

S. No	TOR	Compliance
		welfare and various awareness programmes among the rural population. Assisting social forestry programmed.
41.	<p>Besides the above, the below mentioned general points are also to be followed:-</p> <ol style="list-style-type: none"> <li>Executive Summary of the EIA/EMP Report</li> <li>All documents to be properly referenced with index and continuous page numbering.</li> <li>Where data are presented in the Report especially in Tables, the period in which the data were collected and the sources should be indicated.</li> <li>Project Proponent shall enclose all the analysis/testing reports of water, air, soil, noise etc. using the MoEF&amp;CC/NABL accredited laboratories. All the original analysis/testing reports should be available during appraisal of the Project.</li> <li>Where the documents provided are in a language other than English, an English translation should be provided.</li> <li>The Questionnaire for environmental appraisal of mining projects as devised earlier by the Ministry shall also be filled and submitted.</li> <li>While preparing the EIA report, the instructions for the Proponents and instructions for the Consultants issued by MoEF&amp;CC vide O.M. No. J-1 1013/41/2006- IA.II (I) dated 4th August, 2009, which are available on the website of this Ministry, should be followed.</li> <li>Changes, if any made in the basic scope and project parameters (as submitted in Form-I and</li> </ol>	<ol style="list-style-type: none"> <li>Executive summary has been incorporated.</li> <li>Documents have been numbered in continuation and properly referenced w.r.t. Table of Contents (Index),</li> <li>The data presented in the report especially in table, along with the period in which the data was collected and the source has been incorporated.</li> <li>Analysis/testing reports of water, air, soil, noise has been incorporated.</li> <li>Compliance made.</li> <li>The relevant questionnaire will be incorporated in the final EIA.</li> <li>All instruction mentioned in O.M. No. J- 11013/ 41/ 2006- IA.II (I) dated 4th August, 2009 are being complied with.</li> <li>There is no change made in the basic scope and project parameter.</li> <li>This is new project. Hence, not applicable.</li> <li>All Surface plan, Geological cross section plan, conceptual plan has been incorporated EIA Report.</li> </ol>





S. No	TOR	Compliance
	<p>the PFR for securing the TOR) should be brought to the attention of MoEF&amp;CC with reasons for such changes and permission should be sought, as the TOR may also have to be altered. Post Public Hearing changes in structure and content of the draft EIA/EMP (other than modifications arising out of the P.H. process) will entail conducting the PH again with the revised documentation.</p> <p>i) As per the circular no. J-1 1011/618/2010-IA.II (I) dated 30.5.2012, certified report of the status of compliance of the conditions stipulated in the environment clearance for the existing operations of the project, should be obtained from the Regional Office of Ministry of Environment, Forest and Climate Change, as may be applicable.</p> <p>j) The EIA report should also include (i) surface plan of the area indicating contours of main topographic features, drainage and mining area, (ii) geological maps and sections and (iii) actions of the mine pit and external dumps, if any, clearly showing the land features of the adjoining area.</p>	
<b>B. Additional Terms of Reference</b>		
<b>a)</b>	Means of access and egress between the embankment and sand quarry may be clearly earmarked. The project proponent must commit that no hard topping or paving of any haulage route within the river bed will be attempted.	<p>No hard topping or paving of any haulage route within the river bed will be attempted.</p> <p>Transportation route map is attached as Annexure XIII.</p>
<b>b)</b>	A plan on the management and handling of sand during the period of intermediate stockpiling should be submitted	The management and handling plan of sand has already been submitted in the mining plan.



S. No	TOR	Compliance
c)	A progressive green belt plan may be prepared. The project area being entirely on the riverbed, afforestation/vegetation should be attempted alongside the village roads or other public land. This may be done with prior approval of the local self-governing bodies. If no public land is available for the purpose the project proponent shall arrange for land with his personal means. To enhance success/survival rate the plantation shall be attempted during the first two years of the project life, and the plantation so done shall be taken care of during the rest of the project life. Species of the plant selected should be self-sustaining in that particular region.	The Project area being entirely on the riverbed, afforestation/vegetation would be done alongside the village roads or other public land with prior Approval from the Local Self-Governing bodies.
d)	A need-based EMP may be prepared in accordance with the MoEF&CC Office Memorandum vide F.No.22-65/2017.14.III dated 30.09.2020. Record of communications made in this regard with the identified/ intended beneficiaries (schools/ institutions etc) may also be uploaded.	CER undertaking is enclosed as Annexure XIV.
e)	A study report on base flow level measured at 5 points with date and supporting photographs may be submitted. It should be committed that mining will be done at least 1m above the base flow level. Accordingly, if required, the excavation plan may also be revised.	Refer Chapter-3.
f)	Management plan of haul road to the public road.	Refer Annexure XIII.

## **CHAPTER – 2:**

### **2.1 PROJECT DESCRIPTION**

This chapter gives a broad description of the project, location, type of ore deposits, quality of reserve, Mining Methodology, various site utilities and infrastructure, etc. The downstream use of minerals for value addition and its importance is also described.

### **2.2 Type of the Project:**

The project is proposed for the excavation of river sand from Ajay River. The proposed project is a new minor mineral mining project. It is an opencast manual method mining project to excavate sand from the riverbed.

### **2.3 Need of the project:**

River channels and their flood plains are important sources of construction grade aggregate materials like sand. The durability of river-borne coarser elastics and their sorting by fluvial action make them the most suitable raw materials/ingredients for building constructions. The market demand for the materials extracted from river is high throughout the country for construction of infrastructure projects.

Sand bars formed at various places hinder the flow of water and excess deposition can change the shape of the riverbed. Because of this, during monsoon season, the water may rise above the high flood level causing heavy and devastating floods. Such disasters may damage large tracts of land lying on both the banks of the river, especially agricultural lands. Hence, it is necessary to remove the materials so that the river gets channelized. Apart from this the project will also serve the following:

- ❖ Generate various employment opportunities especially to the local people hosting the mining project.
- ❖ Economic development of the state by contributing to state exchequer.

### **2.4 Description of Mining Lease Area:**

The proposed activity of River sand mining is located at Mouza- Malocha, Plot No.- 254(P),251(P),201(P) & 263(P), J.L. No.- 36, P.S: Burdwan, District- Purba Bardhaman, West Bengal, over an area of 9.15Ha. The lease area falls in Survey of India Toposheet (SOI) No 73 M/10. The life of mine was estimated to be 5 years.

## 2.5 Location Details and Connectivity:


**Table 2-1: Location Details and Connectivity**

Sl. No.	Permanent Features	Description of the Area & Distance from the Area (Aerial distance)		
1.	Project site Location	Malocha sand mine, Mouza–Malocha, Plot No.-254(P),251(P),201(P) & 263(P), J.L. No.-36, P.S: Burdwan, District-Purba Bardhaman,, West Bengal.		
2.	Site Coordinates (Middle Axis)	<b>POINT No.</b>	<b>LATITUDE</b>	<b>LONGITUDE</b>
		1	23° 36' 15.902" N	87° 38' 52.154" E
		2	23° 36' 16.831" N	87° 38' 52.243" E
		3	23° 36' 18.877" N	87° 39' 17.521" E
		4	23° 36' 15.973" N	87° 39' 19.306" E
		5	23° 36' 12.582" N	87° 39' 08.933" E
		6	23° 36' 12.638" N	87° 39' 04.989" E
		7	23° 36' 13.755" N	87° 38' 59.313" E
3.	Village/District/State	Mouza: Malocha District: Purba Bardhaman State: West Bengal		
4.	Maximum temperature	40°C		
5.	Minimum temperature	14°C		
6.	Annual rainfall (total)	>1400mm		
7.	Plant site elevation above MSL	Ground elevation level – 68 m AMSL		
8.	Present land use at the site	Govt land of 9.15 ha (Riverbed)		
9.	Nearest highway	State Highway 2B is about 5.5 Kms along the Eastern direction from the lease area.		
10.	Nearest Railway Station	Bhedia Railway station is 6.2 kms SE direction.		
11.	Nearest Airport	Durgapur Airport is 35 KM SW Direction.		
12.	Nearest major water bodies	On the bank of Ajay River		
13.	Nearest town/City	Bolpur City is Located at 7.8 km NE direction.		
14.	Nearest village	Sagar Putul: 0.60 km (N)		
15.	Nearest Dispensary and Govt. Hospital, Educational facility	Hospital/Dispensary: Supur Primary Health centre 3.66 Km (S); Santiniketan Sebaniketan 7.45 (SW); Visva – Bharati University: 6.62 km(E)		
16.	Nearest Religious/Worship Places	Maa Kali Mandir: 1.11 km (NNE) Manasa Mandir: 0.76 km (NNE)		
17.	Protected areas as per Wildlife Protection Act, 1972 (Tiger reserve, Elephant reserve, Biospheres, National parks, Wildlife sanctuaries, community reserves and conservation reserves)	None - Within 10 km of Project Site		
18.	Reserved / Protected Forests	None - Within 10 km of Project Site		
19.	Defence Installations	None Within 10 km of Project Site		

## 2.6 Geological profile of the area:

### 2.6.1 Topography of the Area:

Purba Bardhaman district is a flat alluvial plain area that can be divided into four prominent topographical regions. On the north, the Kanksa Ketugram Plain lies along with the Ajay, which joins the Bhagirathi. The Bardhaman Plain occupies the central area of the district, with the Ajay on the south and the south-east. On the southern part is the Khandaghosh Plain. The Bhagirathi flows along the eastern boundary of the district, and the Bhagirathi Basin occupies the eastern part of the district. The undulating laterite topography of Purba Bardhaman district extends up to the Ausgram area of this district. The gradient is westerly to the west and to the east, it is northerly towards Ajay and southerly towards Ajay below the latitude. The Ajay- Ajay inter-stream tract is made up of several stows consisting of vales and low convex spurs which run in almost all directions except north-east and thus lends a very complicated character to local relief.




**Fig 2-1: Physiographic map of Purba Bardhaman district**



## 2.7 Geology:

Archaean granite gneisses and migmatites of the Chotanagpur Gneissic Complex are exposed in a narrow east-west belt fringing the north-western part and constitute the oldest basement rocks. Over these, in a faulted, subsided semi-graben type structural trough, deposited the thick bedded sedimentary sequence of Gondwana Super Group comprising sandstone, shale, siltstone with prolific commercial coal seams. All these rocks are cut across by a number of high angle, transverse, gravity faults. Mostly the Lower Gondwana sequence is developed in this district, comprising the Talchir, Barakar, Barren Measure, Raniganj and Panchet Formations. Durgapur beds constitute the youngest unit above the Panchet Formation which is considered equivalent to Mahadeva Formation of Upper Gondwana developed elsewhere. The Gondwana sequence rocks are exposed in the western part of the district area. In parts of the central and in the broad, oval area of eastern part, laterite cover with red soil and Quaternary sequence of riverine sediments grouped under Sijua, Panskura and Diara formations are exposed. The Sijua formation is mainly clay with caliche concretions; Panskura formation constitute clay alternations with silt and sand at the bottom and Diara formation comprise bedded interfingering sand, silt and clay in the present-day shifting river channel courses. Geological succession of Bardhaman district is furnished below



**Figure 2-2: Geological map of Purba Bardhaman district.**

**Table 2-2: Geological succession of Bardhaman (Purba and Paschim)**

Lithology	Geologic Unit	Age	
Sand, Silt, Clay	Diara Formation	Quaternary	Upper Holocene to Recent
Clay Alternating with Silt and Sand	Paskura Formation	Middle to Upper Holocene	
Clay with Caliche Aoncretion	Sijua Formation	Upper Pleistocene to Middle Holocene	
Laterite	Laterite	Cainozoic	
Very Coarse Sandstone	Durgapur Bed	Gondwana Super Group	Jurassic
Red Shale, Sandstone	Panchet Formation	Triassic	
Fine Grained Sandstone, Siltstone with Coal Seams	Raniganj Formation	Permian	
Micaceous Shale, Sandstone	Barren Measure Formation	Permian	
Gritty Pebbly Sandstone with Coal Seams	Barakar Formation	Permian	
Sandstone, Conglomerate	Talchir Formation	Carboniferous Permian(?)	
Granite Gneiss and Migmatite	Chhotanagpur Granite Gneissic Complex	Achaean(?)-Proterozoic	

## 2.8 Ajay River:

Ajay River originates from Batpar from Chakai block of Jamui district in Bihar. It then enters Jharkhand near Devipur (a proposed industrial area of Deoghar) and flows through Jharkhand and enters West Bengal at Simjuri, near Chittaranjan. It first forms the border between Paschim Bardhaman district and Jharkhand and then between Paschim Bardhaman district and Birbhum district, and finally it enters Katwa subdivision of Purba Bardhaman district at Nareng village in Ketugram police station. It then joins the Bhagirathi River at Katwa Town. Total length of the Ajay is 288 kilometres (179 mi), out of which 152 kilometres (94 mi) are in West Bengal. The catchment area of Ajay River is 6,000 square kilometres (2,300 sq mi).

**Table 2.3: Drainage system with description of main rivers**

Sl.No.	Name of the River	Area drained (Sq.km)
1.	Ajay	22159459.9255

**Table 2.4m: Salient Features of important rivers and streams**

Sl.No.	Name of the River or Stream	Total Length in District (in Km)	Place of origin	Altitude at Origin
1	Ajay	90,463.61	Chakai block of Jamui, Bihar	980 ft

Geomorphological characteristic of a river is foremost factor for annual deposition of sedimentary load. The study includes following parameter:

### i) Place of Origin

Details of origin of rivers of Purba Bardhaman District are furnished in Table 2.

**Table 2-5: Place of Origin of important rivers and streams**


Sl.No.	Name of the River or Stream	Place of origin
1	Ajay	Chakai block of Jamui, Bihar

### ii) Catchment Area


The Purba Bardhaman district is mainly drained by the Ajay, Dwarakeswar, Hoogly and Damodar. These rivers and its tributary rivers form the main catchment area.

### iii) General profile of river stream


River profile has been studied along the cross-section lines which was chosen based on the drastic variation of the river widths, proximity of the operating sand ‘ghats’ and the position of the sand bars. Relative disposition of rivers in Purba Bardhaman district along with the distribution of the section lines are shown in Figure 2.4. River profile section and cross section views are presented in Figures 2.5 and 2.6.




**Figure 2-5: Profile section of Ajay River**



**Figure 2-6: Cross section view of Ajay River**



**Figure 2-4: Map showing the major rivers along which profile section drawn.**



**Figure 2-7: Drainage map of the Purba Bardhaman district**



**Table 2-6: Sediment Load comparison between Pre- and Post-monsoon periods for different rivers.**


River Name	Pre-Monsoon Sediment Load (MCum)	Post Monsoon Sediment Load (MCum)	Variance (MCum)	Variance (%)
Ajay	5.51	7.62	2.10	38.18

**Table 2.7: Replenishment rate of the district**

River Name	Location (Mauza)	Area	Surface RL	Thickness	Volume	After mining floor RL	Surface RL after Replenishment	Thickness Replenished	Volume Replenished	Difference in RL	Replenishment Rate
		m <sup>2</sup>	m	m	cum	m	m	m	cum	m	%
Ajay	Malcha	19800.00	43.00	2.90	57420.00	40.10	42.94	2.84	56271.60	0.06	98.00%
Ajay	Harinathpur	28700.00	42.00	2.95	84665.00	39.05	41.94	2.89	82802.37	0.06	97.80%
Ajay	Churpuni	39600.00	17.00	3.00	118800.00	14.00	16.93	2.93	115948.80	0.07	97.60%

## 2.9 Geomorphology:

Bardhaman district with its varied tectonic elements and riverine features, is a transitional zone between the Jharkhand plateau which constitutes a portion of peninsular shield in the west and Ganga-Brahmaputra alluvial plain in the north and east. In general, the Jharkhand plateau consists of the metasedimentary rocks of precambrian age, Gondwana sedimentary rocks, Rajmahal basalts and upper tertiary sediments. Laterite has developed on these older rocks as well as on early Quaternary sediments. Towards south, the alluvial plain merges with Ajay-kasain Subarnarekha deltaic plains. The western half of the district resembles a promontory jutting out from the hill ranges of Chotonagpur plateau and consists of barren, rocky and rolling country with a laterite soil rising into rocky hillocks, the highest being 227 m. These diversify the otherwise monotonous landscape and lend a special charm to the skyline around Asansol subdivision. The Ajay-barakar divide is a convex plateau, the average altitude being 150 m. The gradient is westerly to the west and to the east it is northerly towards Ajay and southerly towards Ajay below the latitude. The Ajay- Ajay inter-stream tract is made up of several stows consisting of vales and low convex spurs which run in almost all directions except north-east and thus lends a very complicated character to local relief.




**Figure 2.8: Geomorphological map of the Purba Bardhaman district**

## 2.10 Soil:

Different types of soil are encountered in different topographical biological and hydrological as well as geological condition within the Bardhaman district. In the west coarse gritty soil blended with rock fragments is formed from the weathering of pegmatites, quartz veins and conglomeratic sandstones, whereas sandy soil characteristic of granitic rocks and sandstones. This soil is of reddish colour, medium to coarse in texture, acidic in reaction, low in nitrogen, calcium, phosphate and other plant nutrients. Water holding capacity of this soil increases with depth as well as with the increase of clay portions. Towards the east alluvial soil attains an enormous thickness in the low level plains to the east. This alluvial soil is formed of alluvium brought down by the Ajay, Ajay, Bhagirathi and numerous other rivers. These soils are sandy, well drained and slightly acidic in nature. Depending upon the soil Bardhaman district is divided into three separated zones:-

- Gangetic soil, which is found along the Ganga River.
- Vindhyan soil, between Ajay and Ajay Rivers in the central and eastern parts.
- Red soils, occurring in the undulating and coal field areas in the western parts of the district.





**Figure 2-9: Soil pattern of the Purba Bardhaman district**

## 2.11 Drainage:

The river system in Bardhaman includes the Bhagirathi-Hooghly in the east, the Ajay and its tributaries in the north and the Dwarakeswar, the Ajay and its branches in the south-west. Besides, there are innumerable Khals and old river beds all over the area. On the north, the Kanksa Ketugram Plain lies along the Ajay, which joins the Bhagirathi. The Bardhaman Plain occupies the central area of the district, with the Ajay on the south and the south-east. The Bhagirathi flows along the eastern boundary of the district, and the Bhagirathi Basin occupies the eastern part of the district. The notable rivers and khals are Ajay, Bhagirathi, Barakar, Ajay, Dwarakeswar, Nonia, Singaram, Tamla, Kukua, Kunur, Tumuni, Khari, Banka, Chanda-kanki nala, Behula, Gangur, Brahmani, Khandesvari, Karulia nala, Dwaraka or Babla, Koiya nala, Kandarkahal, KanaAjay, Kananadi, Ghea, Kakinadi etc.


**Ajay River:** - Ajay River originates from Batpar from Chakai block of Jamui district in Bihar. It then enters Jharkhand near Devipur (a proposed industrial area of Deoghar) and flows through Jharkhand and enters West Bengal at Simjuri, near Chittaranjan. It first forms the border between Paschim Bardhaman district and Jharkhand and then between Paschim Bardhaman district and Purba Bardhaman district, and finally it enters Katwa subdivision of Purba Bardhaman district at Nareng village in Ketugram police station. It then joins the Bhagirathi River at Katwa Town. Total length of the Ajay is 288 kilometres (179 mi), out of

which 152 kilometres (94 mi) are in West Bengal. The catchment area of Ajay River is 6,000 square kilometres (2,300 sq mi).

**Damodar River:-** The city of Bardhaman is situated on the banks of the river Ajay and acts as an anchor for this town. The river is considered to be a holy and sacred river by the aborigines of the Chotanagpur Plateau. The river Ajay originates from the Sonajuria Falls of the Bijonsa Hill which is located in the district of Palampur in Bihar. The river joins Barakar at the town of Dishergarh in the Asansol subdivision of the Bardhaman district and then flows through the rest of the district of Bardhaman. It continues to flow through the districts of Hooghly and Howrah in West Bengal before finally joining the Bhagirathi River, which is the other name for the Ganges in Murshidabad. Bardhaman takes up the shape of a delta along with the branch rivers of the Ajay surrounding it, namely Balluka, Behula, Gangur, Banka and so on, some of which have almost become extinct at present. The civilization of ‘Rarh-Bangla’ has also developed with this river as its centre. A bridge has been constructed over the River Ajay at Sadarghat which is known as ‘Krishok Setu’ (as pronounced in Bangla).

**Hoogly River:** - Bhagirathi River, river in West Bengal state, northeastern India, forming the western boundary of the Ganges-Brahmaputra delta. A tributary of the Ganges (Ganga) River, it leaves that river just northeast of Jangipur, flows south, and joins the Jalangi at Nabadwip to form the Hoogly River after a total course of 120 miles (190 km). Until the 16th century, when the Ganges shifted eastward to the Padma, the Bhagirathi formed the original bed of the Ganges. The Bhagirathi River originally flowed down the west of Nabadwip in the past, forming a natural boundary between the districts of Purba Bardhaman and Nadia. With time it has shifted its course to where it is at present, cutting the city off from the rest of the Nadia district.

**Dwarakeswar River:** - Dwarakeswar River (also known as Dhalkisor) is a major river in the western part of the Indian state of West Bengal. The river originates near Madhabpur in Purulia district and enters Bankura district near Chhatna. It cuts across the district flowing past the district headquarters and enters the southeastern tip of East Bardhaman District. It then passes through Hooghly District. The Silai joins it near Ghatal and the two together are known as Rupnarayan River, which flows into the Hooghly River near Gadiara in Howrah District. Dwarakeswar River has much sedimentation from low water (any season). In rainy seasons it is filled up with water; then huge sedimentations are blocked the channel, even near Arambagh the channel basin reduced by garbage and anthropogenic (manmade).



**Figure 2-10: Drainage map of Study area**

## 2.12 Climate and Rainfall:

District Purba Bardhaman belongs to humid tropical monsoon climatic region. According to District Meteorological Department, there are very minor variation of temperature, rainfall and relative humidity in all over the district viz. north to south and west to east.

Purba Bardhaman district has a tropical climate – hot and humid. While the hottest month is May, the coldest is January. The monsoon season is from June to September, with an annual average rainfall of 1,400 mm, 75% of it falling in the monsoon months. Localised thunderstorms, called kalbaisakhi in Bengali, are a special feature from March until the monsoon sets in. The cold season starts from about the middle of November and continues till the end of February. March to May is dry summer intervened by tropical cyclones and storms. June to September is wet summer while October and November are autumn.


<https://purbabardhaman.nic.in/geography>

The average annual rainfall in the district is 1400mm. The variations in the annual rainfall within the district and from year to year are not large. The rainfall during the monsoon season – June to September – constitutes 75 percent of the annual rainfall; July and August are the rainiest months.

[https://hydro.imd.gov.in/hydrometweb/\(S\(c31xot2fu1lahs45tplr2vuh\)\)/DistrictRaifall.aspx](https://hydro.imd.gov.in/hydrometweb/(S(c31xot2fu1lahs45tplr2vuh))/DistrictRaifall.aspx)

**Table 2-8: Annual rainfall (in milimeter) recorded in the Purba Bardhaman District**

<b>The District Rainfall in mm (R/F) shown below are the arithmetic averages of Rainfall of Stations under the District</b>						
<b>YEAR</b>	<b>JAN</b>	<b>FEB</b>	<b>MAR</b>	<b>APR</b>	<b>MAY</b>	<b>JUN</b>
<b>2016</b>	13.5	29.3	15	0	120	182.5
<b>2017</b>	1.2	0	32.6	28.3	171.2	255.8
<b>2018</b>	0	0.1	15.1	82.6	43.5	158.1
<b>2019</b>	0	64	16.3	47.8	129.9	90.9
<b>2020</b>	26.6	1.1	64.6	65.8	212	298.4
<b>YEAR</b>	<b>JUL</b>	<b>AUG</b>	<b>SEPT</b>	<b>OCT</b>	<b>NOV</b>	<b>DEC</b>
<b>2016</b>	263.9	463.5	274.5	44.3	1.9	0
<b>2017</b>	464.1	252.9	178.2	260.1	14.5	9.1
<b>2018</b>	329.7	174.7	154.3	16	0	26.7
<b>2019</b>	195.8	233.1	215.8	191.7	16.8	11.1
<b>2020</b>	338.2	262.2	128.2	81	1.7	0



**Figure 2-11: Graphical representation of the District rainfall**

## 2.13 Temperature:

**Summer:** - Paschim Bardhaman district experiences dry and hot summer with maximum temperature of near about  $\approx 40^{\circ}\text{C}$  during summer. The district shows a fierce dry heat in the warmer months. The summers in Purba Bardhaman usually start from month of March and last till the middle of June

**Monsoon:** - The arrival of the month of June marks the onset of monsoon in Purba Bardhaman. The district receives a high average rainfall. June to September has shown maximum average rainfall with moderate temperature. The district received average rainfall of 1400 mm.

**Winter:** - Winters in Paschim Bardhaman are pleasant and enjoyable, with mercury dropping to about 14°C or below. The winter starts from December and last till the month of February.

**Table 2-9: Monthly mean temperature (in °C) distribution of the district**

Parameters	Jan	Feb	Mar	Apr	May	June	July	Aug	Sep	Oct	Nov	Dec
<b>Average Temperature(°C)</b>	17.0	20.5	25.0	30.0	29.5	29.5	28.0	28.0	27.0	25.5	21.0	18.0
<b>Minimum Temperature(°C)</b>	10.0	13.0	18.0	22.0	23.0	25.0	24.0	24.0	22.0	20.0	13.0	10.0
<b>Maximum Temperature(°C)</b>	24.0	28.0	32.0	38.0	36.0	34.0	32.0	32.0	32.0	31.0	29.0	26.0

## 2.14 Relative Humidity, Wind speed & Wind direction

The maximum and minimum relative humidity of the district during summer season varies from 75% to 85 % and 40% to 60% respectively. In wintertime district's humidity varies from maximum 80% to 90 % and minimum 30% to 55% ([District Disaster Management Plan, 2015-2016](#)).


## 2.15 Hydrogeology:

Hydrological condition at a particular point is guided by topography, geology, and rainfall of the region. Central Ground Water Board (CGWB) has carried out detail hydrogeological investigation of the district. Figure 2.12 represents hydrogeological map showing the hydrogeological scenario of the district.


As per the CGWB report, In a major part of the district, ground water in thick unconsolidated Quaternaries and Tertiaries deposited under fluvial environment, the sand and/or gravel in different proportions of this formation constitute the main aquifer and they occur down to 295 mbgl in the central and eastern part of the district. Deeper aquifers occur under semi-confined to confined condition. Groundwater in the western part of Upper- Palaeozoic- Mesozoic- Tertiary sequences of Gondwana Supergroup of sedimentaries occur under both unconfined and confined conditions down to 150.35 mbgl. Groundwater in the extreme northwestern small part of Salanpur Block occupied by the Archaean metamorphics occurs down to a depth of about 82 mbgl under both unconfined and confined conditions down to 150.35 mbgl. It mainly occurs under unconfined condition in the dug well zone and under semi confined to confined condition in the deeper horizons. In Bardhaman district, ground water occurs in semi-confined to confined aquifer conditions in the depth span of 12.00-38.00 mbgl, 31.00-55.00 mbgl and 70.00-88.00 mbgl.

(<http://wbwrid.gov.in/swid/mapimages/PURBA BARDHAMAN.pdf>).





**Figure 2-12: Hydrogeology map of Purba Bardhaman district.**



**Figure 2-13: Graphical representation of pre-monsoon and post-monsoon water level data of Purba Bardhaman**


## 2.16 Seismicity of the area:

The seismic hazard map of India was updated in 2000 (Figure 2-14) by the Bureau of Indian Standards (BIS). There are no major changes in the zones in West Bengal with the exception



of the merging of Zones I and II of the 1984 BIS map. Western sections of the northern districts of Jalpaiguri and Coochbehar lie in Zone V. The remaining parts of these two districts, along with the districts of Darjeeling, Uttar Dinajpur, Dakshin Dinajpur, Maldah, 24 North Parganas and 24 South Parganas lie in Zone IV. The rest of the state along with the city of Kolkata lies in Zone III.

**Purba Bardhaman** district is categorized under seismically active zone - III i.e., moderate seismic intensity zone. Bureau of Indian Standards, based on the past seismic history, grouped the country into four seismic zones, viz. Zone - II, Zone –III, Zone-IV and Zone-V. Of these, Zone V is the most seismically active region, while Zone II is the least.



**Figure 2-14: Earthquake zonation map of West Bengal highlighting the Purba Bardhaman district position.**

## 2.17 Available reserves and production:

### 2.17.1 Geological Reserve:

The total area for lease is 9.15 Ha. Sand is available in the middle portion of the riverbed as well as near the riverbank. It is permitted to remove sand only up to 3 m depths or up to groundwater level whichever is less. Now as per policy of the West Bengal state and West Bengal Minor Mineral and Concession Rules 2016 and approved DSR of Purba Bardhaman, the estimation of the reserves in term of volume has been drawn on the basis of the area under the lease multiplied by the average 2.88 m depths and the replenishment rate of the river is considered to be 75% annually.

**Table 2-10: Considerations for Resource & Reserve Calculation of the Lease Area**

Total Area (Ha)	Safety Zone (Ha)	Production Area (Ha)	Thickness (m)
9.15	1.22	7.93	3.00

**Table 2-11: Geological Reserve of the Lease Area**

Year	Total Area (Ha)	Thickness (m)	Replenishment Rate (%)	Geological Resource (m <sup>3</sup> )
<b>1<sup>st</sup></b>	9.15	3.00	100	2,74,500.00
<b>2<sup>nd</sup></b>	9.15	2.175	72.50	1,99,012.50
<b>3<sup>rd</sup></b>	9.15	2.175	72.50	1,99,012.50
<b>4<sup>th</sup></b>	9.15	2.175	72.50	1,99,012.50
<b>5<sup>th</sup></b>	9.15	2.175	72.50	1,99,012.50
<b>Total Geological Reserve (Cu. M.)</b>				<b>10,70,550.00</b>

As per the MoEF&CC Guidelines we have to consider a Safety Zone in order to move forward with our mining activities in the allotted lease area, considering an annual replenishment rate of 72.5%.as per stated in Section 3,6 above.

Now, after deduction of safety zone, the Total Mineable Reserve is = **2,37,900.00 m<sup>3</sup>**

**Table 2-12: Minable Reserve of the Sand Deposit**

Year	Total Area (Ha)	Thickness (m)	Replenishment Rate (%)	Mineable Reserve (m <sup>3</sup> )
<b>1<sup>st</sup></b>	7.93	3.00	100	2,37,900.00
<b>2<sup>nd</sup></b>	7.93	2.175	72.50	1,72,477.50
<b>3<sup>rd</sup></b>	7.93	2.175	72.50	1,72,477.50
<b>4<sup>th</sup></b>	7.93	2.175	72.50	1,72,477.50
<b>5<sup>th</sup></b>	7.93	2.175	72.50	1,72,477.50
<b>Total Mineable Reserve (Cu. M.)</b>				<b>9,27,810.00</b>
<b>Total Mineable Reserve (C. Ft.)</b>				<b>3.276 cr cft</b>



**Figure 2-15: Mining location in lease area are marked as red colour polygon.**

### **2.17.2 Mineable reserve of the minerals:**

Assuming the riverbed of the Mining Contract Area to be a level area, the reserve of sand available for extraction can be estimated as stated below: -

The mineable area= 9.15 Hectares = 22.61 acres

Maximum depth allowed for riverbed mining = 2.88

The void occurring due to the removal of sand from the riverbed is gradually filled up with sand carried by the river current. This process is rapid during the rainy season and hence replenishes the reserve of the mineral (sand) every year as there will be an accumulation of sand to a considerable extent during the rainy season.

For extraction of the sand under the opencast mining method, three numbers of benches, each of 1m in depth and 2.88M width, may be maintained as indicated in Figure 2-9 and Figure 2-10.

As per Issued LOI vide memo no. 261 – ICE – 12011(99) \27\2022- MINES SEC- Dept. of ICE dated 20.04.2023, a total of 9,27,810.00 Cu.M of Sand may be excavated for 5 Years.

Extraction/ collection work of river sand is usually carried out for eight months in a year. The work remains suspended for the rest four months of the year due to seasonal monsoon rainfall and other related problems.

Therefore, considering the number of working days in a month to be 25 days and 8 hours per day. So, the total working days in a year would be = (25 X 8) = 200 days

However, the Competent Authority may prescribe the quantity of sand to be extracted by the Mining Contract Holder as per the terms and conditions of the contract taking into account the



impact on the ecology and environment of the surrounding areas.

However, the quantity of n bn sand allotted for extraction under the Mining Contract will be within the mineable reserve of sand available per year as depicted above.

## 2.18 Production of sand:

The Mining Contract proposed to be granted to the applicant “**West Bengal Mineral Development & Trading Corporation Limited**” in the riverbed of Ajay River is for extraction of sand manually. Ajay River is a perennial river and hence, considerable amount of sand is transported by the flow of riverwater. The total quantity of the sand to be produced are 9,27,810.00 cum.

Sand will be lifted from the riverbed for all eight from June to September. Proposed production for (As per the DSR report of Purba Bardhaman):

**Table 2-13: Year-wise Production details**

Year	Total Area (Ha)	Thickness (m)	Replenishment Rate (%)	Mineable Reserve (m <sup>3</sup> )
1 <sup>st</sup>	7.93	3.00	100	2,37,900.00
2 <sup>nd</sup>	7.93	2.175	72.50	1,72,477.50
3 <sup>rd</sup>	7.93	2.175	72.50	1,72,477.50
4 <sup>th</sup>	7.93	2.175	72.50	1,72,477.50
5 <sup>th</sup>	7.93	2.175	72.50	1,72,477.50
<b>Total Mineable Reserve (Cu. M.)</b>				<b>9,27,810.00</b>
<b>Total Mineable Reserve (C. Ft.)</b>				<b>3.276 cr cft</b>

### 2.18.1 Per Day Production

Total Estimated production of minable reserve during the full lease period will be

$$= 9,27,810.00 \text{ m}^3.$$

The Maximum Production of Minor Mineral (Sand) during the full lease Period is

$$= 1,85,562.00 \text{ m}^3$$

Considering the number of working days in a month to be 25. Since the Mining activities will be on halt during the time of Monsoon (Period of 4 months), Therefore only 8 months of working on the Lease area will be possible.

So, the total working days in a year would be:  $(25 \times 8) = 200$  days.

So, the Average Extraction of Riverbed Sand deposits per day (i.e., 200 days) would be about:

$$= (2,37,900 / 200)$$

$$\cong 1,189.50 \text{ m}^3 / \text{Day}.$$

Considering the carrying capacity of the trucks/ dumpers to be deployed is of average 10 m<sup>3</sup> (20 Ton), the total no. of trips to be made by the dumpers/trucks would be about:

$$= (1,189.50 / 10) \text{ m}^3$$

**≅ 119 trips per day.**

Sand will be transported from the mine site to various government, semi-government, and private consumers mainly for civil construction and road construction purposes. The quantity of sand stated above is an estimated quantity that may be available for extraction considering the extent of the area of the Mining Contract Site. However, the competent authority shall decide and fix the quantity of sand to be lifted by the Mining Contract Holder as per terms and conditions of the Mining Contract with due emphasis on the impact on environment and ecology of the surrounding areas.

## **2.19 Working Depth**

Taking into consideration the geological parameters of the sand deposit and the geotechnical field observations, it is advised to work in a semi mechanized mode and the method is opencast with a bench system which is adapted to work on the deposit. As per West Bengal Minor Mineral Concession rule 2016, it is advised to keep the working depth of the Mining activities at 3m.

It is only a small-scale sand mining. The extraction of sand is being done using small scale excavators (0.9 ml) and manually with simple hand tools such as shovel pans and crowbars. This activity is followed by sorting pebbles manually or by a screening device. The year wise projection of working is marked on the Production and Development plan which is enclosed in the section as Plate No. – 5. Surface Plan of the proposed lease area is shown in Plate No. – 6 Year-wise Production and Development Plan and Geological Cross-section showing the year-wise bench disposition is enclosed as Plate No. - 7 and 8.

## **2.20 Year Wise Development**

No development work is required as the mining is for riverbed sand. Excavation of river sand will be done in combination of both manual method and transportation will be done by loading trucks of 20 Ton (10 m<sup>3</sup>) capacity. It has been proposed to collect approximately 1,85,562.00 m<sup>3</sup>/per year (average). The riverbed material will be replenished during the monsoon season every year.

## **2.21 Life of mine:**

Generally, the extraction / collection of riverbed sand deposits can be carried out for eight months only in a year. The work remains suspended for four months during the monsoon season for allowing the riverbed to replenish. During this period as the riverbed remains full with seasonal flood water and other related problems like lack of approach road, heavy vehicles may get destroy connecting roads etc. The ultimate land use of the mine lease area will not change. The life of mine will be up to lease period i.e., 5 years. Based on the reserves with the average established rate of production of 1,85,562.00 m<sup>3</sup> per annum, the anticipated life of the sand mine will be about 5 years.

## **2.22 Mining Method:**


### **2.22.1 Proposed Mining Method:**

Presently the said mine is working with the conventional open cast with bench system method with the semi mechanized mode of operation. Based on the mode and method so adopted and taking into the consideration of geological parameters of the sand body, the mining pit is designed such that the height of the bench is kept at about 3 meters maximum and maintains 34° pit slope. However, only 3.00 m benches have been considered for present mining.


- Mode of operation (mining) is a manual open cast supplemented with semi-mechanised operation.
- Extraction of sand will be done by both manual labours and small capacity machineries like excavators and tractors for excavation and transportation of the excavated sand.
- The extracted sand will be temporarily stored in the stacking area which then further will be transported to the desired location as per MDO.
- The bench height will be 1m, at final stage the slope of the bench will be maintaining 34° slope.
- Loading of excavated and sorted sand materials into tippers with the help of manual mode or by small capacity excavator.

**Source:** *Approved Mine Plan (SGP./MP/6-21/2023/31 dtd. 17<sup>th</sup> February 2023).*





**Figure 2-16: Model Scheme of Extraction of River Sand in Mining Contract Area.**




**Figure 2-17: Model Scheme of Extraction of River Sand in Mining Contract Area.**

## 2.23 Conceptual Plan of Mining:

Considering individual sand deposits and restricting the mining to top 3 m from the present ground surface, shall be done. A pole (wooden or metal) shall be fixed in the sand deposit at a suitable location, with datum levels - 0m to 3m painted on it to work as a guide in depth restriction. The river channel is free of water and the ground water table lies about 6-8 m below the dry channel of the river exposed. In general this condition prevails in almost all of the sand deposits on this river stretch.

The mineralized zone or the sand zone in particular of the river does not follow any specific trend, somewhat it occurs as lensoid body. The relative occurrence of ground surface with the sand zone thickness varies from place to place and depends upon factors such as stream/river flow characteristics, geometry of the river banks, sediment load, rate of water flow, rainfall and surface runoff characteristics etc.

The longitudinal section of the river channel is explained in the Figure 2-18. The longitudinal section exhibits the generic upstream to downstream flow of river along with the sand deposits contained with it. As seen in the illustration, the top surface of the sand deposit is undulating and gently dipping and the contours of sand deposit vary with the factors as enumerated in above paragraph.



**Figure 2-18: Conceptual Longitudinal Section of River Channel.**

## 2.24 Machinery Requirement:

This is a new mining contract. Following equipment's are proposed to be deployed for the desired production.

**Table 2-14: List of Machinery.**

Sl. No.	Name of Machinery	Capacity	Approximate Quantity (Nos./Day)
1.	Excavator	1.5 (Cu.M/hrs.)	3
2.	Tipper Truck	10 (Cu.M)	35-40
3.	Water Sprinkler Truck	10	2

**Table 2-15: Details of Manpower Deployed**

Sl. No.	Manpower	Numbers
1.	Manager/ Supervisors/ Technical Professionals	4
2.	Skilled labour	26
3.	Non-skilled labour	60
	<b>Total</b>	<b>90</b>

## **2.25 Transportation of Minerals:**

As per the official Kolkata Gazette No. 48-ICE/O/MIN/GES-MIS/17/2021 dated 31<sup>st</sup> January 2022 and The West Bengal Sand Rule 2016, the following are the rules for transportation, storage & sale of sand:

1. No person shall transport sand without being duly authorized by the State Government and carrying a valid internal permit or e-challan generated on the centralized portal.
2. No person shall store and/or sell sand and or carry out any other allied activities without being duly authorized by the State Government.
3. A person engaged in the transportation of sand shall register itself and every carrier used by it for transporting sand on the centralized portal, in such manner, as may be specified by the State Government in a notification published in the Official Gazette.
4. A person engaged in the storage of sand shall register itself and every such stockyard/depot used for storage of sand on the centralized portal, in such manner, as may be specified by the State Government in a notification published in the Official Gazette.
5. A person engaged in sale of sand shall register itself on the centralized portal, in such manner as may be specified by the State Government in a notification published in the Official Gazette.
6. The persons specified in sub-rule (3), (4) and (5) who are engaged in transportation and/or storage and/or sale of sand from before the commencement of these rules, shall register themselves on the centralized portal within sixty days from the commencement thereof.
7. Within such time as may be specified by the State Government in a notification published in the Official Gazette, such other persons engaged in any activity in connection with sand, if not already registered on the date of publication of such notification in the manner specified in such notification, shall register themselves with the State Government.
8. The time period, terms and conditions of the registration and fees shall be as specified by the State Government in a notification published in the Official Gazette.

### **2.25.1 Transport from Lease Area to the destination:**

ROM generated at the mining site will be loaded on tractors with the help of labours followed by transportation by Tipper Trucks.

### **2.25.2 Transport System:**

The transportation system is mainly surface transport' assuming the tipper trucks have 10 m<sup>3</sup> (20 Ton) capacities. Therefore, there will be traffic of 98 trips per day at the mining site.

### **2.25.3 Sand Transportation Means:**

Both own and hired trucks

### **2.25.4 Conveyor/ rail/ ropeway/ pipeline:**

Not Applicable

### **2.25.5 Main destination to which riverbed sand is transported (giving both side travel distance):**

The material generated at this Mining Lease Area is sand which is used as Road Metal/Building material, hence the distance of destination (both side travel) cannot be furnished, because it varies.

NH 19 is a 10 km national highway passes across the northern bank of Ajay River. The average distance from the project site to village Rd is approx. 0.31km. The village road has its outlet meeting the tar road on the nearby villages and from where the mineral is sent to various destinations.

### **2.25.6 Measures related to transportation:**

- Regular water spraying on haulage roads during mineral transportation by rotary type water sprinkler, which will cover whole width of the haulage road in one round.
- Avoid overloading of tippers & consequent spillage on the roads.
- Mineral carrying trucks will be effectively covered by tarpaulin to avoid escape of fines to atmosphere.
- Air quality shall be regularly monitored both in the core zone and the buffer zone.

### **2.26 Mine drainage:**

During the course of mining, the water table in the river shall not be intercepted. The mining shall be restricted to the top 2.88 m from the general ground level. Ground water shall not be

intercepted during the mining of sand. In view of it, dewatering of sand pits shall not be required or discharged elsewhere.

## **2.27 Stacking of mineral rejects and disposal of waste:**

The present sand mining locations do not have significant topsoil/clay layer to be preserved elsewhere during the mining operations. The sand deposits inherit gravel, pebbles with them being a part and parcel of river system. During the field visit and information gathered during discussions with concerned people, 10% of the geological reserves occurring in the sand ghats are provided for these inclusions and accordingly these have been considered during the minable sand reserves.

### **2.27.1 Disposal of Waste (Reject) materials Silt:**

The proposed project is the mining of sand from dry part of riverbed, all the excavated material will be saleable, and therefore no mines reject will be generated. Some amount of silt may generate will be used in haul road development.

### **2.27.2. The land was chosen for disposal of waste with the proposed justification:**

There shall be no waste materials generated during the course of sand mining. Therefore, disposal of solid waste resulting from the sand mine shall not be required.

## **2.28 Use of Mineral:**

Sand is used in almost any type of construction activity. Thus, as the focus of the government is on the improvement of basic infrastructure, both in rural & urban areas, there is a constant need for ensuring a regular supply of these construction raw materials inputs. The production of sand will benefit the state in the form of royalty. Apart from this project operation will provide employment directly & indirectly to the people residing in the vicinity, thus improving the Socio-economic status of the area.

There will be also indirect employment in transportation and handling.

## **2.29 Utilities and Proposed Site Facilities:**

### **a) Utilities:**

#### **1. Need for the project and importance in the country:**

West Bengal is a rich district in terms of sand and mineral deposits. The districts endowed minor mineral resources. The region, where the project is situated, people are mostly dependent on agriculture for livelihood. The developments of mining in the area will lead to infrastructure development, improvement of road communication and also provided direct and indirect employment opportunities.



## **2. Demand Supply Gap:**

The demand for sand is ever-growing with the growth of the infrastructure sector in our country. The mineral is used mainly in the construction activities like buildings, pillars etc. The requirement for minerals is always high in the nearby cities and towns. Therefore, sand has a good demand in the domestic market.

## **3. Import v/s Indigenous Production:**

Only in-situ reserves of sand aggregate occurring in the riverbed of Ajay covering an area of 9.15 ha shall be mined by opencast as indigenous production.

## **4. Domestic / Export Markets:**

Sand is one of the most important dimensional minerals under listed minor minerals. The domestic demand for sand is also increasing due to large scale development of housing complexes, hotels, hospitals, offices, etc. not only in West Bengal but also in other states.

## **5. Export Possibility:**

The entire quantity of production of sand shall be used for local construction and road-making purposes within the district of Purba Bardhaman and within the state of West Bengal. There is no possibility of exporting the minor mineral at present.

### **b) Proposed Site Facilities:**

#### **1. Water Requirement:**

The water will be required only for drinking purposes. It is projected that not more than 90 laborers will be required for the proposed project. The total water requirement will be 10 KLD which will be met by installation of tube well within the project site.

**Table 2-16: Water Requirement.**

<b>Sl. No.</b>	<b>Activity</b>	<b>Water Requirement (In KLD)</b>
<b>1.</b>	Drinking & Domestic	2
<b>2.</b>	Green Belt	4
<b>3.</b>	Dust	4
<b>Total</b>		<b>8</b>

#### **2. Power:**

The material will be excavated by a semi open cast method and loaded directly into tractors by the workers themselves. The operation will be done only from sun rise to sun set. So, there is no power requirement for the mining activity.

#### **3. Manpower:**

There is no permanent influx of the population anticipated, as the workers will be hired

locally from nearby villages. Unemployment is very pervasive in the study area. The project will provide employment to around 26 nos of skilled labours, and 60 nos. of non-skilled labours from local proximity and 4 nos of managers/supervisors/technical professionals in the project. It is expected that a large part of the investment in this project will be direct/ indirect role on local population. Hence there will be an overall improvement of the socio-economic status of the people of surrounding areas.

#### **4. Infrastructure and Site Facilities:**

Infrastructure facilities like site office, first aid station, rest shelter, potable drinking water facility etc. will be established within the mine area. The following infrastructure facilities will be made available for the workers:

#### **5. First Aid Facility:**

A first aid facility will be made available at site with proper equipment will be maintained as per Mines Act and Mine Rules at the mine site office. First aid -box with all necessary facilities will be maintained and provided.

#### **6. Temporary rest shelter:**

The temporary rest shelter with arrangement for drinking water, tea etc., will be provided for the workers working in the mine as they will come from nearby villages at day time only.

#### **7. Washroom:**

Washroom facilities will be provided to the laborers near the site.

#### **8. Land use:**

The land of the mine lease area is for Sand Mining & there will be no change in land use after operation. The final land use of the mine lease area will not change. Extracted minerals will be used in construction purposes and other uses, the workers will be hired locally & temporarily, no housing facility will be required. Land use distribution proposed for quarrying and its allied works and ultimate land use details are given;

**Table 2-17: Land use of project site before and after project activity.**

<b>Year</b>	<b>2009-10</b>	<b>2010-11</b>	<b>2011-12</b>	<b>2012-13</b>	<b>2013-14</b>
Reporting Area	698.76	698.76	698.76	698.76	698.76
Forest Area	21.16	21.16	21.16	21.16	21.16
Area under Nonagricultural use	208.53	211.56	211.92	213.77	214.19
Barren & unculturable land	1.37	0.86	0.65	0.57	0.44
Permanent pastures & other grazing land	0.22	0.26	0.33	0.15	0.06
Land under misc. tree groves not included in Net	1.42	1.99	0.87	0.83	0.98

area sown					
Culturable waste land	5.6	4.88	6.09	4.45	3.74
Fallow land other than Current fallow	1.37	1.24	1.46	1.25	1.09
Current fallow	4.98	4.35	4.31	3.7	3.31
Net area sown	454.11	452.46	451.97	452.88	453.79

### 2.30. Project Cost:

The total cost of the project is approx.,9.829 crores, one year would be approx., 1.966 crores and there is a budgetary provision that 5% (0.098 crore peryear) of the project cost will be allocated for the Environmental Management Plan (EMP) and 2% (0.039 crore per year) of the project cost will be allocated for Corporate Environmental Responsibility (CER) and health and hygiene (H&H) for causes of poor people of nearby villages. Health and Hygiene will be allocated for a health check-up once in six-months. Extra budgetary provisions will be allocated to lady workers. The Total expenditure of welfare scheme i.e., EMP + CRP & H&H = 7% (0.13762 crore per year).

## **CHAPTER – 3**

### **3.1. DESCRIPTION OF THE ENVIRONMENT**

#### **3.1.1 General**

Sand is a site-specific mineral that occurs mostly along the riverbed and sometimes off the riverbed. Mining activities invariably affect the current environmental status of the site. It has both adverse and beneficial effects. To maintain the environmental commensuration with the mining operation, it is essential to undertake studies on the existing environmental scenario and assess the impact on different environmental components.

#### **3.2 Study area and Sampling Site**

The study area is divided into core and buffer zone in view of scientific study. The core zone is the lease area of the mining site and from the boundary of the lease area up to 10 km radius is called buffer zone (Figure: 1-2). The study of the proposed project was undertaken for assessing the base line status of Environmental Parameters like Land, Air, Water (both ground and surface), Soil, Noise and Biological (both flora and fauna) and socio-economic status.

Baseline data has been collected out during the Summer Season (March to May, 2023) by M/s N.D. International Kolkata [NABL Accredited Lab, Certificate No. TC: 5910] in accordance with the Guidelines for EIA issued by the Ministry of Environment Forests and Climate Change, Govt. of India and CPCB, New Delhi. Team of Experts visited the study area for Social & Biological Environment study. The following data, through field survey and other sources, has been collected by M/s Indian Mine Planners and Consultants, Kolkata, for preparing the EIA/EMP for the proposed mining area with related facilities.

- Physical environment (Air, Water, Soil and Noise) baseline data.
- Relevant meteorological data, for previous decades from Indian Meteorological Department (IMD) and primary data.
- Identification of water bodies, hills, roads etc. within 10 Km radius.
- Eco-sensitive places, sanctuaries, biosphere reserves within 10 Km radius.
- Religious places / historical monuments and tourist places within 10 Km radius.
- Study of present environmental protection and mitigation measures in nearby operating similar projects, if any.

**Table 3-1: Salient Features of Baseline Environmental Studies.**

Attribute	Parameter	Frequency of Monitoring
Micro - meteorological Studies	Wind Details like speed, direction, Temperature, Relative Humidity and Rainfall	3 months data has been collected to assess air Pollution impacts on the surrounding environment.
Ambient Air Quality	PM10 PM2.5 Sulphur Dioxide (SO <sub>2</sub> ) Oxides of Nitrogen (NO <sub>x</sub> )	3 months data has been collected to assess baseline Air Quality status of the area.
Noise Quality Data	Noise levels	1 middle month data has been collected to identify noise producing areas.
Water Quality, Soil Quality Data and Land Use pattern	Physical & Chemical parameters along with Measurement of heavy metals and land use parameters.	To establish baseline Water Quality, Soil Quality for future reference and Land Use Pattern in the area
Socio-Economic & Demographic Studies	Socio-Economic parameter	To know the present Socio-Economic status of the study area

### 3.3 Land Environment:

Since mining is essentially an excavation of mineral ore, the land environment is greatly affected by it, especially in the case of opencast mines. In contrast, underground mines have limited effect on the surface land.

### 3.4 Land Use Land Cover of the Study Area:

Land Use (LU) refers to man's activities and various uses which are carried out on land. Land Cover (LC) refers to natural vegetation, water bodies, rock / soil, artificial cover and others resulting due to land transformation. Although land use is generally inferred based on the cover, both the terms land use and land cover are closely related and interchangeable.

Information on the rate and kind of change in the use of land resources is essential to the proper planning, management and regulation of the use of such resources. Satellite imageries are potentially more amenable to digital processing because the remote sensor output can be obtained in digital format. Land use data are needed in the analysis of environmental processes and problems that must be understood if living conditions and standards are to be improved from or maintained at current levels. It is required to carry out the land use/land cover study for the project study area (10 km radius) to obtain the necessary environmental clearances from statutory authorities. The objective of the study is to carry out land use / land cover study for the proposed project. The LU/





LC study is carried out using the Satellite Imageries (IRS RS2 LISS III / IV Rabi and Khariff) in addition to Survey of India toposheets. Appropriate guidelines are followed while preparing the LU / LC map for the project study area.

### **1) Scope of the Work:**


- The LU/LC study shall be carried out for a study area of a 10 km radius, taking the site as the centre using the satellite imageries (IRS RS2 III / IV 5.8 m Resolution) for Rabi/ Kharif season.
- Procurement of latest satellite imagery (IRS RS2 III/IV 5.8m Resolution) based on availability) Rabi or Khariff seasons. Satellite imagery processing and interpretation of land use as per land use classification covering 10 km radius of proposed Project Site.
- Calculation of land use breakup w.r.t. each land use category covering 10 km of the proposed Project Site.
- Preparation and submission of reports, satellite imageries and maps.

### **2) Pre-Field Interpretation:**

- Collection of Survey of India Topographical maps on a 1:50,000 scale from Survey of India (SOI).
- Procurement of Satellite Imagery from the National Remote Sensing Centre (NRSC) site Geo Co-ordinates from the site centre taken 10 Km radius.
- Using ERDAS image processing software processed the raw satellite data.
- Using ArcGIS software, converting all base features from the toposheet and overlaying the same features on the satellite imagery.
- Using remote Sensing techniques, tone, colour, texture and shadow etc. draft land use map is prepared.
- Before site/ground truthing, randomly mark field data checked. With which fieldwork will be carried out.

### **3) Site/ground truthing:**

- Site visit - capture the Geo-Coordinates of Boundary Pillars and record them in a field notebook.
- Take traverses and observe the land use categories and map them on the field map on the draft map with field photographs.
- Observe each land use category like single crop/double crop, industrial area, settlements, forest lands, water bodies, wastelands, etc.
- The buffer zone area will randomly traverse for correlating mapping units.
- Collecting secondary data from the agricultural department and local people.




**Figure 3-1: Land Use Land Cover map of Purba Bhardhaman District**

**Table 3-2: Land utilization statistics of the district**


Year	2009-10	2010-11	2011-12	2012-13	2013-14
Reporting Area	698.76	698.76	698.76	698.76	698.76
Forest Area	21.16	21.16	21.16	21.16	21.16
Area under Nonagricultural use	208.53	211.56	211.92	213.77	214.19
Barren & unculturable land	1.37	0.86	0.65	0.57	0.44
Permanent pastures & other grazing land	0.22	0.26	0.33	0.15	0.06
Land under misc. tree groves not included in Net area sown	1.42	1.99	0.87	0.83	0.98
Culturable waste land	5.6	4.88	6.09	4.45	3.74
Fallow land other than Current fallow	1.37	1.24	1.46	1.25	1.09
Current fallow	4.98	4.35	4.31	3.7	3.31
Net area sown	454.11	452.46	451.97	452.88	453.79

**Table 3-3: Land use and Land cover data of buffer zone**

Land-use distribution	Area in sq km	Percentage (%)
Barren Land	23.41	7.08
Crop Land	178.93	54.13
Developed Area	58.05	19.59
Forest Land	64.75	17.56
Waterbody	5.38	1.63
<b>TOTAL</b>	<b>330.53</b>	<b>100</b>



**Figure 3-2: Pie chart showing Land use distribution of Buffer Zone Area**



**Figure 3-3: Land-use and Landcover of 10 km buffer zone of the project area**

### 3.5 Conclusion of land use and land cover analysis:

The major land use and land cover is Crop Land 54.13%, Forest Land area second highest by area 19.59%, Barren land 7.08 %, Settlement 17.56%, and water bodies cover 1.63%. This LULC data are compared with District land use land cover data presented in Figure 3-3.

### 3.6 Soil:

Soil, also commonly referred to as earth or dirt, is a mixture of organic matter, minerals, gases, liquids, and organisms that together support life. (Some scientific definitions distinguish dirt from the soil by restricting the former term to displaced soil.)

Soil consists of a solid phase of minerals and organic matter (the soil matrix), as well as a porous phase that holds gases (the soil atmosphere) and water (the soil solution). Accordingly, soil is a three-state system of solids, liquids, and gases. Soil is a product of several factors: the influence of climate, relief (elevation, orientation, and slope of terrain), organisms, and the soil's parent materials (original minerals) interacting over time. It continually undergoes development by way of numerous physical, chemical and biological processes, which include weathering with associated erosion. Given its complexity and strong internal connectedness, soil ecologists regard soil as an ecosystem.

To judge the soil properties of the area, soil was taken at 3 locations. The details of the location are given in Table 3-5. Soil samples were collected from surrounding agriculture fields and nearby area that are likely to be impacted from the project. Soil quality analysis done for parameters like texture, moisture, organic matter, conductivity, pH, bulk density, and NPK values. Soil parameter lab analysis results of the 3 locations are given in the table 3-4 and 3-5.

**Table 3-4: GPS Coordinate of Soil Sample collection location**


Sl. No.	Sampling Location	Location Code	Coordinates		Distance from Project Site	Direction from Project Site
			Latitude	Longitude		
1.	Malacha	S1	23°36'4.40"N	87°38'48.19"E	0.59 km	South
2.	Warishpur	S2	23°32'10.05"N	87°38'35.66"E	7.57 km	South
3.	Ilam Bazar Forest	S3	23°38'16.41"N	87°35'30.54"E	7.17 km	North- West

**Table 3-5: Soil parameters lab analysis results**

<b>A. Chemical Test Findings</b>						
Sl No.	Test Parameter	Test Method	Unit	Result		
				S1	S2	S3
1.	Electrical Conductivity (1:2.5 Aqueous Solution)	IS:14767: 2000 134	µs/cm	212	209	204
2.	Nitrogen	IS:14684 : 1999	%	0.12	0.98	0.09
3.	Moisture	IS:2720 (Part-2) : 1973	%	20.62	20.57	20.38
4.	Specific Gravity	NDI/CHEM/SOP/S-03	--	2.85	2.83	2.68
5.	Bulk Density	FAO Method-2007	gm/cm <sup>3</sup>	2.78	2.68	2.52
6.	Phosphorus as P	FAO : (Method) U.N.2007	mg/g	0.216	0.206	0.207
7.	Potassium as K	13.1 of FAO : 2007	mg/g	0.26	0.25	0.21
8.	Sodium Absorption Ratio	IS 11624:2019	-	1.35	1.23	1.23
9.	Permeability	NDI/CHEM/SOP/S-05	cm/h	15.18	15.11	13.56
10.	Calcium	The Fertilizer Control Order 1985	mg/g	0.88	0.87	0.83
<b>Texture of Soil</b>						



11.	Gravel	FAO Method-2007	%	Nil	Nil	Nil
12.	Sand	FAO Method-2007	%	32.56	36.57	30.56
13.	Silt	FAO Method-2007	%	17.34	18.24	18.72
14.	Clay	FAO Method-2007	%	51.10	45.19	50.72



**Figure 3-4: Soil Monitoring Locations**





**Figure 3-5: Soil sampling**

### **3.7 Conclusion of soil parameters analysis:**

The analysis of soil at three locations shows that the soil of the region is predominantly of clayey nature with a percentage of sand and silt and absence of gravel content.

### **3.8 Air Environment:**

#### **3.8.1 Climate:**

The climate of the area is characterized by a hot and dry summer from March to May, a south- west monsoon or rainy season from June to September, a pleasant post-monsoon or retreating monsoon from October to November and a cool winter from December to February. Therefore, climatologically, four seasons viz. summer (pre-monsoon), monsoon, post-monsoon and winter could be deciphered comprising the following months.

- Summer: March, April, May
- Monsoon: June, July, August and September
- Post Monsoon: October and November
- Winter: December, January and February

Air pollutants upon discharge to atmosphere pass through a number of mechanisms, which include

diffusion and transportation leading to dispersion. These mechanisms are governed by the local atmospheric conditions. All these result in the necessity to collect the meteorological parameters like ambient temperature, wind speed, wind direction, and other weather conditions (relative humidity, atmospheric pressure etc.), which will be ultimately used for the prediction of the ground level concentrations of the air pollutants through mathematical modelling.

For this purpose, a temporary auto weather station was installed to record micro meteorological data on wind speed, wind direction, ambient temperature, solar insolation and Relative humidity on hourly basis.

The primary data from the site was matched with secondary data of IMD nearby station for data proofing. A sophisticated on-site meteorological observatory was established near project site and operated continuously for three months' period (March 2022 to May 2022). The observatory was located about 10 m above the ground level and ensured to be free from any obstruction to wind. Besides, this location was found to be most suitable one being close to the project site. The wind rose diagram for the entire period is shown in Figure below.




**Figure 3-6: Ambient Air Quality Sampling Locations.**






**Figure 3-7: Onsite meteorological study**



**Figure 3-8: Wind rose diagram.**



**Figure 3-9: Wind Class Frequency Distribution.**

### 3.9 The wind rose Observations:

The predominant wind direction is from the east, with a speed of 3.60 to 5.70m/sec. Calm Percentage (37.5%) of wind direction is more than that the total time of both predominant directions.

### 3.10 Ambient Air Environment:

An assessment of the existing air quality is required to establish the reference level. To accomplish this, Ambient Air Quality Monitoring (AAQM) stations were set up within a 10 km radius of the proposed mining area. Data over the baseline status of ambient air quality was generated with following objectives:

- Qualitative analysis of air environment of the area.
- Representation of regional background levels.
- Influence of existing sources of pollution.

The significant contributors/sources of air pollution in the area are.

- Vehicular traffic
- Windblown Dust

### 3.11 Ambient Air Quality:

The ambient air quality monitoring was carried out at 4 locations. The location and description of AAQM stations is shown in Table 3-6 & Figure below. The parameters monitored during the study period were particulate Matters (PM<sub>10</sub>), particulate Matters (PM<sub>2.5</sub>), Sulphur dioxide (SO<sub>2</sub>) and Oxides of Nitrogen (NO<sub>2</sub>). The results of AAQM are depicted in Tables 3-7 to 3-12.

**Table 3-6: GPS Coordinates of Air Sample collection location**



S.N.	Location Name	Coordinates		Distance from Project Site	Direction from Project Site
		Latitude	Longitude		
1	Project site	23°36'15.11"N	87°39'6.95"E	-	-
2	Bengal Institute of Technology	23°38'31.98"N	87°37'40.75"E	4.86 km	South-east
3	Ramnagar High School	23°34'34.03"N	87°37'29.15"E	4.22 km	North-West
4	Kalyanpur FP School	23°34'35.07"N	87°44'18.25"E	9.30 km	West

**Table 3-7: Particulate Matter concentration at different site – PM<sub>10</sub>.**

Location	Minimum in(μg/m <sup>3</sup> )	Maximum in(μg/m <sup>3</sup> )	Average in(μg/m <sup>3</sup> )	98 <sup>th</sup> Percentile (μg/m <sup>3</sup> )
Project site	64	81	73.0	75
Bengal Institute of Technology	57	81	71.4	77
Ramnagar High School	60	81	72.5	75
Kalyanpur FP School	52	81	68.7	75

**Table 3-8: Particulate Matter concentration at different site – PM<sub>2.5</sub>**

Location	Minimum (μg/m <sup>3</sup> )	Maximum (μg/m <sup>3</sup> )	Average (μg/m <sup>3</sup> )	98 <sup>th</sup> Percentile (μg/m <sup>3</sup> )
Project site	40	58	49.5	55
Bengal Institute of Technology	41	56	49.2	54
Ramnagar High School	40	59	47.9	52
Kalyanpur FP School	41	59	49.1	55

**Table3-9: Sulphur dioxide (SO<sub>2</sub>) concentration at different site.**

Location	Minimum (μg/m <sup>3</sup> )	Maximum (μg/m <sup>3</sup> )	Average (μg/m <sup>3</sup> )	98 <sup>th</sup> Percentile (μg/m <sup>3</sup> )
Project site	11	26	17.7	22
Bengal Institute of Technology	11	22	18.0	20
Ramnagar High School	10	22	15.3	20
Kalyanpur FP School	11	25	17.0	21

**Table3-10: Nitrogen dioxide (NO<sub>2</sub>) concentration at different site.**

Location	Minimum (μg/m <sup>3</sup> )	Maximum (μg/m <sup>3</sup> )	Average (μg/m <sup>3</sup> )	98 <sup>th</sup> Percentile (μg/m <sup>3</sup> )
Project site	8	17	12.5	14
Bengal Institute of Technology	7	15	9.5	11
Ramnagar High School	7	15	11.0	12
Kalyanpur FP School	9	20	13.1	16

**Table3-11: Carbon Monoxide (CO)concentration at different site.**

Location	Minimum (μg/m <sup>3</sup> )	Maximum (μg/m <sup>3</sup> )	Average (μg/m <sup>3</sup> )	98 <sup>th</sup> Percentile (μg/m <sup>3</sup> )
----------	------------------------------	------------------------------	------------------------------	--



<b>Project site</b>	1	2	1.1	<1.0
<b>Bengal Institute of Technology</b>	1	2	1.3	<1.0
<b>Ramnagar High School</b>	1	2	1.4	<1.0
<b>Kalyanpur FP School</b>	1	1	1.0	<1.0

**Table3-12: Free Silica (Si) concentration at different site.**

<b>Location</b>	<b>Minimum (<math>\mu\text{g}/\text{m}^3</math>)</b>	<b>Maximum (<math>\mu\text{g}/\text{m}^3</math>)</b>	<b>Average (<math>\mu\text{g}/\text{m}^3</math>)</b>	<b>98<sup>th</sup> Percentile (<math>\mu\text{g}/\text{m}^3</math>)</b>
<b>Project site</b>	3.1	6.7	5.3	6.2
<b>Bengal Institute of Technology</b>	3.1	6.7	5.4	6.4
<b>Ramnagar High School</b>	3.1	6.8	5.4	6.3
<b>Kalyanpur FP School</b>	4.5	7.1	5.4	6.1

## **Baseline Scenario:**

### **a) Suspended Particulate Matter (PM<sub>10</sub>):**

Suspended particulate matter in general terms is the particulate matter in suspension in ambient air. It includes dust, smoke etc. In general, some of the important sources of suspended particulate matter are mines. The following sources of suspended particulate matter in the study area are identified:

- Emission due to vehicular movement
- Dust generation from the ground or other mining operations

The minimum and maximum level of PM<sub>10</sub> recorded within the study area was in the range of 52 $\mu\text{g}/\text{m}^3$  to 81 $\mu\text{g}/\text{m}^3$ , with a consolidated 98<sup>th</sup> percentile range between 75  $\mu\text{g}/\text{m}^3$  to 77  $\mu\text{g}/\text{m}^3$ . The 24-hourly average value of PM<sub>10</sub> is 73.0  $\mu\text{g}/\text{m}^3$ , which is within the permissible limit as per National Ambient Air Quality Standards (NAAQS) of 100  $\mu\text{g}/\text{m}^3$ , for PM<sub>10</sub> in industrial, residential, rural and other area.

### **b) Particulate Matter (PM<sub>2.5</sub>):**

Fine particulate matter (PM<sub>2.5</sub>) is generated due to all types of fuel combustion and some industrial processes. In general, some of the important sources of particulate matter are mines.

The following are the sources for particulate matter (PM<sub>2.5</sub>)

- Emission due to vehicular movement
- Dust generation from the ground or other mining operations

(PM<sub>2.5</sub>) recorded within the study area is in the range of 40 $\mu\text{g}/\text{m}^3$  to 59 $\mu\text{g}/\text{m}^3$  and 98 percentile range between 52  $\mu\text{g}/\text{m}^3$  to 55  $\mu\text{g}/\text{m}^3$ . The 24-hourly average value of PM<sub>2.5</sub> is 49.5 $\mu\text{g}/\text{m}^3$  which is within the permissible limit as per National Ambient Air Quality Standards (NAAQS) of 60 $\mu\text{g}/\text{m}^3$ , for PM<sub>2.5</sub> in industrial, residential, rural and other area.

**c) Sulphur Dioxide (SO<sub>2</sub>):**

Sulphur dioxide gas is an inorganic gaseous pollutant. Sulphur dioxide emissions are expected to be emitted wherever combustion of any fuel containing Sulphur takes place. The Sulphur in the fuel will combine with oxygen to form Sulphur dioxide. The following sources of Sulphur dioxide in the study area are identified:

- Emissions from domestic/consumption of fuel (coal, diesel, etc.)
- Emissions from machinery equipment's used for mining activity and local residents Sulphur dioxide in the atmosphere is significant because of its toxicity, Sulphur dioxide is capable of producing illness and lung injury. Further it can combine with water (moisture) in the air to form toxic acid aerosols that can corrode metal surfaces, fabrics and leaves of plants. Sulphur dioxide is an irritant to the eyes and respiratory system. Excessive exposure to Sulphur dioxide can cause bronchial asthma and other breathing related diseases as it affects the lungs.

The minimum and maximum levels of SO<sub>2</sub> recorded within the study area were in the range of 10 µg/m<sup>3</sup> to 26 µg/m<sup>3</sup>, and the 98<sup>th</sup> percentile was recorded between 20 µg/m<sup>3</sup> to 22 µg/m<sup>3</sup>. The 24-hourly average values of SO<sub>2</sub> is 18 µg/m<sup>3</sup>, which is within the permissible limit as per National Ambient Air Quality Standards (NAAQS) of 80 µg/m<sup>3</sup>, for SO<sub>2</sub> in industrial, residential, rural and other area.

**d) Oxides of Nitrogen (NO<sub>2</sub>):**

The essential sources of nitrogen oxides are utilities and auto exhaust due to vehicular movement in the mine lease area. The following sources of oxides of Nitrogen in the study area are identified.

- Emissions from field burning of coal
- Emissions from vehicular movements in the study area

Oxides of Nitrogen in the presence of sunlight will undergo reactions with several organic compounds to produce all the effects associated with photochemical smog. NO<sub>x</sub> has the inherent ability to produce deleterious effects by themselves, like toxicity. It causes asphyxiation when its concentration is significant enough to reduce the normal oxygen supply from the air.

The minimum and maximum levels of NO<sub>x</sub> recorded within the study area were in the range of 7 µg/m<sup>3</sup> to 20 µg/m<sup>3</sup>, with the 98<sup>th</sup> percentile range between 11 µg/m<sup>3</sup> to 16 µg/m<sup>3</sup>. The 24-hourly average values of NO<sub>x</sub> is 13.1 µg/m<sup>3</sup>, which is within the permissible limit as per National Ambient Air Quality Standards (NAAQS) of 80 µg/m<sup>3</sup>, for NO<sub>x</sub> in industrial, residential, rural and other area.

**e) Carbon Monoxide (CO):**

Carbon monoxide (CO) is an odorless, colorless gas formed by the incomplete combustion of fuels. Exposure to CO gas, results in displacement of oxygen in human bodies eventually leading to CO poisoning. The minimum and maximum levels of CO recorded within the study area were in the range of  $1\text{mg/m}^3$  to  $2\text{mg/m}^3$ , with the 98<sup>th</sup> percentile  $<1.0\text{mg/m}^3$ . The hourly average values of CO is  $1.4\text{ mg/m}^3$ , which is well within the permissible limit as per National Ambient Air Quality Standards (NAAQS) of  $4\mu\text{g/m}^3$ , for CO in industrial, residential, rural and other area.

#### **f) Free Silica (Si)**

The minimum and maximum levels of free silica recorded within the study area were in the range of  $3.1\text{ }\mu\text{g/m}^3$  to  $6.8\text{ }\mu\text{g/m}^3$ , with 98<sup>th</sup> percentile in the range of  $6.1$  to  $6.4\text{ }\mu\text{g/m}^3$ . The hourly average value of free silica is  $5.4\text{ }\mu\text{g/m}^3$ .

### **3.12 Conclusion of ambient air quality:**

The analysis of ambient air quality data for three months consequently indicates quite well ambient air conditions at the site as well as around the site upstream as well as downstream. Particulate matter  $\text{PM}_{10}$  is within the limits prescribed.  $\text{SO}_2$  and  $\text{NO}_2$  are well below the limits prescribed. Hence the overall scenario of the study area for ambient air quality is good.



**Figure 3-10: Ambient Air Sampling**

### **3.13 Ambient Noise Environment:**

A noise survey has been conducted in the study area covering residential transportation, commercial and calm zones. The main objective of noise monitoring in the study area is to establish the baseline noise level, which is needed for assessing the impact of total noise, which is expected to be generated in the proposed project activities. Noise is measured in terms of the loudness of the sound. A sound is a form of energy that propagates through an elastic medium at a speed that is determined by the properties of that medium. Since loudness of sound is




important to the effects of noise on people, the dependence of loudness upon frequency must be taken into account in environmental noise assessments. Several methods have been developed by researchers using the frequency spectrum of sound to arrive at the loudness index or the given sound. For measuring the intensity of the sound, "A sound level meter" is used, which gives the intensity of sound in terms of dB (A).


The basic step associated with impact assessment on the noise components of the environment involves the identification and evaluation of the present noise status in the general population. Therefore, noise level measurement was carried out at each ambient air quality station and the site. The objectives of Noise environment studies are.

- To assess the ambient noise level in the study area.
- To characterise the noise pollution area
- To predict the temporal changes in the ambient noise level of the area.

Noise pollution in the study area is associated with Industrial activities, Vehicular traffic. To judge the ambient noise level of the area, noise levels were recorded at 4 locations in dB (A). The details of the location are given in Table 3-13. Monitoring results of the Noise level recorded at 4 locations are given in the table below.



**Figure 3-11: Ambient Noise Monitoring Locations**



**Figure 3-12: Ambient Noise Monitoring at site**

**Table 3-13: Monitoring results of the Noise level in and around project site.**

Location	Noise Level dB(A)Leq					
	DAY TIME			NIGHT TIME		
	Max	Min	Average	Max	Min	Average
Project site	45.1	36.8	41.23	42.6	38.2	39.775
Nabagram	48.8	37.6	42.5	43.2	34.7	37.37
Mithapur	52.3	41	45.76	43.2	38.1	38.26
Garoma	48.5	36.8	43.0	42.6	36.4	39.02

Note:

- 1) Daytime is from 6.00 am to 10.00 pm and Night time is from 10.00 pm to 6.00 am.
- 2) Silence zone is defined as area up to 100 meters around premises of hospitals, educational institutions and courts. Use of vehicle horns, loud speakers and bursting of crackers are banned in these zones.

### **3.13.1 Conclusion of ambient noise level studies:**


Noise monitoring reveals that the maximum & minimum noise levels at day time were recorded between as 36.8 dB(A) & 52.3 dB(A) respectively. The maximum & minimum noise levels at night time were found to be 34.7 dB(A) & 43.2 dB(A) respectively.

The noise level recorded at project site (Station N1) both during day and night time is well within the permissible limit as per “The Noise Pollution (Regulation & Control) Rules, 2000.

The noise level recorded at residential zones (Station N3 and N4) both during day and night time is well within the permissible limit for residential zone as per “The Noise Pollution (Regulation & Control) Rules, 2000.



The noise level recorded at industrial zones (Station N2) both during day and night time is well within the permissible limit for industrial zone as per “The Noise Pollution (Regulation & Control) Rules, 2000.



**Figure 3-13: Bar Diagram showing day and nighttime noise level in the monitoring locations**

### 3.14 Water Environment:

Surface water and groundwater samples were collected from different sources within the study area and some important physical and chemical parameters were considered for depicting the baseline status of the study area.


#### 3.14.1 Water Quality Assessment:

Selected water quality parameters for water resource of the study area have been used for describing the water environment and assessing the impacts. About 3 Nos Sampling location are presented in Table 3-16. ground water samples and 3 nos (Table 3-17). surface water samples were collected in the study area to assess the water quality. Water samples are drawn from the hand pumps being used by the villagers for domestic needs.

To evaluate the physico-chemical characteristics of the water resources existing in the study area, water samples of ground water sources were collected during the pre-monsoon season and characterized for physico-chemical parameters. There samples were taken as grab sample and were analyzed for various parameters and compared with standards IS: 10500 and IS 2296: Class C specifications.

**Table 3-14: GPS Coordinates of Ground water Sample collection location.**

Sl. No.	Sampling Location	Coordinates		Distance from Project Site	Direction from Project Site
		Latitude	Longitude		
1.	Chandanpur	23°37'53.30"N	87°39'52.48"E	3.23 km	North
2.	Gopalpur gram	23°35'5.48"N	87°38'16.20"E	2.43 km	East
3.	Berenda	23°33'12.70"N	87°41'50.43"E	7.27 km	South



**Figure 3-14: Groundwater Quality sampling locations**

The physico-chemical characteristics of surface water samples presented in Table below.

**Table 3-15: Analysis results of ground water**

A. Microbiological Test Findings								
Sl.No	Parameter	Test Method	Unit	Results			Norm as per IS 10500:2012	
				GW-1	GW-2	GW-3		
1.	Total Coliform/100 ml at 37° for 24 hrs	IS 1622	Cfu	<1 (DL:1)	<1 (DL:1)	<1 (DL:1)	Not Detectable	
2.	E. coli/100ml at 44.5° for 24hrs	IS 1622	Cfu	Absent	Absent	Absent	Not Detectable	
B. Organoleptic and physical parameters								
Sl.No	Parameter	Test Method	Unit	Results			Norm as per IS 10500:2012	
				GW-1	GW-2	GW-3	AI (Max)	PL (Max)
3.	pH at 25°C	APHA, 23 <sup>rd</sup> Edition, 4500 H <sup>+</sup> B	-	7.3	6.8	7.0	6.5-8.5	No relaxation
4.	Total Dissolved Solids	APHA, 23 <sup>rd</sup> Edition,2540-C	mg/l	144	140	118	500	2000
C. General Parameters concerning substances undesirable								
5.	Chloride (as Cl)	APHA, 23 <sup>rd</sup> Edition,4500, Cl-B	mg/l	18.7	18.8	19.2	250	1000
6.	Fluoride (as F)	APHA, 23 <sup>rd</sup> Edition,4500, F-C	mg/l	<0.1 (DL:0.1)	<0.1 (DL:0.1)	<0.1(DL:0.1)	1	1.5
7.	Iron (as Fe)	APHA, 23 <sup>rd</sup> Edition,3500, Fe-B	mg/l	0.26	0.24	0.28	0.3	No relaxation
8.	Nitrate (as NO3)	APHA, 23 <sup>rd</sup> Edition,4500, NO3-B	mg/l	1.43	1.11	0.94	45	No relaxation
9.	Sulphate (as SO4)	APHA, 23 <sup>rd</sup> Edition,4500, SO4-B	mg/l	24.65	22.6	18.33	200	400
10.	Sulphide (as H2S)	APHA, 23 <sup>rd</sup>	mg/l	<0.05(DL:	<0.05(DL:O	<0.05(D	0.05	No

		Edition,4500, S2-B		O.OS)	.OS)	L:O.OS)		relaxation
11.	Total Hardness (as CaCO <sub>3</sub> )	APHA, 23 <sup>rd</sup> Edition, 2340 C	mg/l	71	66	55	200	600
12.	Arsenic (as As)	APHA, 23 <sup>rd</sup> Edition,3113 B	mg/l	<0.002 (DL:0.002)	<0.002 (DL:0.002)	<0.002 (DL:0.002)	0.01	0.05
13.	Chromium (as Cr)	APHA, 23 <sup>rd</sup> Edition,3111 D	mg/l	<0.01 (DL:0.01)	<0.01 (DL:0.01)	<0.01 (DL:0.01)	0.05	No relaxation
14.	Total Suspended Solids	APHA, 23 <sup>rd</sup> Edition, 2540 D	mg/l	10	14	9	100mg/l(max)	

### Observation & Analysis of Ground Water Quality:

Groundwater samples collected from three locations within a 10 km radius of the proposed site showed all parameters well within the drinking water standards specified in IS 10500 and IS 2296: Class C. Therefore, it can be concluded that, all sites of water are suitable for drinking purposes.




**Figure 3-15: Ground Water Sampling**

**Table 3-16: GPS Coordinates of Surface water Sample collection location.**

Sl. No.	Sampling Location	Coordinates		Distance from Project Site	Direction from Project Site
		Latitude	Longitude		
1.	Upstream Of the River (SW1)	23°36'34.67"N	87°38'1.26"E	1.85 km	West
2.	Downstream Of the River (SW2)	23°37'7.59"N	87°40'3.97"E	2.33 km	East
3.	Boro shiv Pukur	23°32'44.19"N	87°39'4.93"E	6.41 Km	North-East





**Figure 3-16: Surface water Quality Monitoring Locations**

The physico-chemical characteristics of Surface water samples are presented in the Table below.

**Table 3-17: Analysis results of surface water**

C. Microbiological Test Findings								
Sl.No	Parameter	Test Method	Unit	Results			Norm as per IS 10500:2012	
				SW-1	SW-2	SW-3		
1.	Total Coliform/100 ml at 37° for 24 hrs	IS 1622	Cfu	<1(DL:1)	<1(DL:1)	<1(DL:1)	Not Detectable	
2.	E. coli/100ml at 44.5° for 24hrs	IS 1622	Cfu	Absent	Absent	Absent	Not Detectable	
D. B. Organoleptic and physical parameters								
Sl.No	Parameter	Test Method	Unit	Results			Norm as per IS 10500:2012	
				SW-1	SW-2	SW-3	AI (Max)	PL (Max)
3.	pH at 25°C	APHA, 23 <sup>rd</sup> Edition, 4500 H <sup>+</sup> B	-	6.9	7.2	7.5	6.5-8.5	No relaxation
4.	Total Dissolved Solids	APHA, 23 <sup>rd</sup> Edition,2540-C	mg/l	98	119	98	500	2000
C. General Parameters concerning substances undesirable								
5.	Chloride (as Cl)	APHA, 23 <sup>rd</sup> Edition,4500, Cl-B	mg/l	23.81	24.88	24.51	250	1000
6.	Fluoride (as F)	APHA, 23 <sup>rd</sup> Edition,4500, F-C	mg/l	<0.1 (DL:0.1)	<0.1 (DL:0.1)	<0.1(DL:0.1)	1	1.5
7.	Iron (as Fe)	APHA, 23 <sup>rd</sup> Edition,3500, Fe-B	mg/l	0.26	0.20	0.28	0.3	No relaxation
8.	Nitrate (as NO3)	APHA, 23 <sup>rd</sup> Edition,4500, NO3-B	mg/l	0.92	0.82	0.34	45	No relaxation
9.	Sulphate (as SO4)	APHA, 23 <sup>rd</sup> Edition,4500, SO4-B	mg/l	22.6	24.7	25.3	200	400
10.	Sulphide (as H2S)	APHA, 23 <sup>rd</sup> Edition,4500, S2-B	mg/l	<0.05 (DL:0.05)	<0.05 (DL:0.05)	<0.05 (DL:0.05)	0.05	No relaxation
11.	Total Hardness (as CaCO3)	APHA, 23 <sup>rd</sup> Edition, 2340 C	mg/l	52	49	44	200	600
12.	Arsenic (as As)	APHA, 23 <sup>rd</sup> Edition,3113 B	mg/l	<0.002 (DL:0.002)	<0.002 (DL:0.002)	<0.002 (DL:0.002)	0.01	0.05

13.	Chromium (as Cr)	APHA, 23 <sup>rd</sup> Edition, 3111 D	mg/l	<0.01 (DL:0.01)	<0.01 (DL:0.01)	<0.01 (DL:0.01)	0.05	No relaxation
14.	Total Suspended Solids	APHA, 23 <sup>rd</sup> Edition, 2540 D	mg/l	8	10	9	100mg/l(max)	
15.	Biochemical Oxygen Demand at 27°C for 3 days	IS 3025 (Part- 44) 1993	mg/l	3.0	2.9	2.7	30 mg/l(max)	
16.	Chemical Oxygen Demand	APHA, 23 <sup>rd</sup> Edition, 5220 B	mg/l	19	17	23	250 mg/l(max)	

### 3.15 Observation & Analysis of Surface Water Quality:

Surface water samples collected from three locations within 10 km radius of the proposed site showed all parameters analyzed are well within the drinking water standards specified by CPCB



**Figure 3-17: Surface Water Sampling.**

### 3.16 Biological Environment:

Biological environment is an essential component that constitutes the total environment of the study area. The study area has a diverse ecological structure and therefore needs a thorough study of all its components.

EIA is essentially a planning tool for preventing environmental problems due to change of any landscape. As per EIA notification, 2006 the study area for biological environment is taken within 5km radius of Sand Mine (MIN\_EBUR\_24) in Ausgram-II block of Purba Bardhaman district, West Bengal.

Study on biological environment has three components in it.

- Existing species diversity and ecological structure of the study area,
- Possible impacts of mining on biological environment, and
- Mitigation measures.

### 3.17 Existing species diversity and ecological structure of the study area

MIN\_EBUR\_24 proposed sand mine lease area being 9.15 hectare on the river Ajay River of Purba



Bardhaman district, falling under Mouzas – Malocha, JL No. – 36, Plot No – 254(P),251(P),201(P) & 263(P) coming under P.S: Burdwan of Purba Bardhaman district of West Bengal.

## A. Methodology for the Study

Ecological study was done collecting baseline data to understand the present status of ecological settings of the area. This data also helped us in designing the pollution mitigation plan biologically in such a way that the harmful impacts of the proposed sand West Bengal mine on the vegetation and fauna are avoided or minimised. Different types of habitats with varied vegetation covers are encountered in different ecological condition of the study area. This area is having agricultural lands with very dense human habitation, two reserved forests with some remnants of natural forest, plantation of various exotic species, waterbodies, and degraded lands etc. Random quadrats were laid to study the floral components in the study area in the following manner. The quadrat sizes laid were as follows –

- (a) 10m x 10m in agricultural lands
- (b) 10m X 10m in the plantation areas

Aquatic flora was studied in line transects along the aquatic bodies to study aquatic flora. Each studied location for vegetation study was marked with a GPS (etrax 10) and coordinates (latitude and longitude) were noted with site characteristics.

## B. Present Land-use pattern of the study area

The land use pattern of this vast landscape has been framed from the Satellite Imagery and Toposheet and duly authenticated. Ground truth was also done in different location marking it with GPS coordinates. The land use / land cover pattern of the study area may be classified into following categories: (i) Crop Land (ii) Open areas without scrubs (iii) Settlements and (iv) Water bodies.

The study area is mostly covered with rainfed crops and is under paddy cultivation. A small area is irrigated by ground water for Boro paddy cultivation. A good amount area is also used for cultivation of vegetables etc. The species of herbs, shrubs and trees found in the sampled plots of study area are depicted in the table below.

**Table 3-18: List of Tree Species found within 5 km radius of the mining lease area.**

Sl. No.	Scientific Name	Local name	Family
1.	<i>Citrus maxima</i>	Batabilebo	Rutaceae
2.	<i>Dalbergia sisso</i>	Sisso	Fabaceae
3.	<i>Azadirachta indica</i>	Neem	Meliaceae
13	<i>Mangifera indica</i>	Mango	Anacardiaceae

11	<i>Ficus bengalensis</i>	Banyan	Moraceae
6.	<i>Artocarpus heterophyllus</i>	Kathal	Moraceae
7.	<i>Alstoniascholaris</i>	Chatim	Apocynaceae
8.	<i>Anthocephalus chinensis</i>	Kadam	Rubiaceae
9.	<i>Aegle marmelos</i>	Bel	Rutaceae

**Table 3-19: List of Shrub Species found within 5 km radius of the mining lease area.**

Sl. No.	Scientific Name	Local Name	Family
1.	<i>Dioscorea bulbifera</i>	Khamalu	Dioscoreaceae
2.	<i>Dioscorea floribunda</i>	Panalu	Dioscoreaceae
3.	<i>Tephrosia purpurea</i>		Papilionaceae
4.	<i>Vitex negundo</i>	Began	Vitaceae
5.	<i>Hibiscus rosa-sinensis</i>	Joba	Malvaceae
6.	<i>Clerodendron infortunatum</i>	Ghentu	Verbenaceae
7.	<i>Croton bonplandianum</i>	Chuchhuri	Euphorbiaceae

**Table 3-20: List of herb species found within 5 km radius of the mining lease area.**

Sl. No.	Scientific Name	Family
1.	<i>Cyperus iria</i>	Cyperaceae
2.	<i>Cyperus kyllinga</i>	Cyperaceae
3.	<i>Cyperus rotundus</i>	Cyperaceae
4.	<i>Dactylocteniumaegypticum</i>	Poaceae
5.	<i>Desmodiumtriflorum</i>	Papilionaceae
6.	<i>Desmodiumvolubilis</i>	Papilionaceae0
7.	<i>Digitariasanguinalis</i>	Poaceae
8.	<i>Eclipta alba</i>	Asteraceae
9.	<i>Eragrostistenella</i>	Poaceae
10.	<i>Euphorbia hirta</i>	Euphorbiaceae
11.	<i>Euphorbia microphylla</i>	Euphorbiaceae
12.	<i>Evolvulusalsenoides</i>	Convolvulaceae
13.	<i>Evolvulusnummularius</i>	Convolvulaceae
14.	<i>Fimbristylis japonicum</i>	Cyperaceae



a) *Digitosia* Sp



b) *Dioscorea* Sp





c) *Ocimum* Sp



d) *Clerodendron* Sp



e) *Aegle marmelos* (Bel)



f) *Albizia lebbek* (Shirish)



g) *Alstonia scholaris* (Chatim)



h) *Anthocephalus chinensis* (Kadam)

**Figure 3-18: Ecology and Biodiversity study around the project site**

**Aquatic flora (Both Angiosperms and Pteridophytes)**

1. *Azolla pinnata* (Salviniaceae)
2. *Cynodon dactylon* (Poaceae)
3. *Digitaria longiflora* (Poaceae)
4. *Eclipta alba* (Asteraceae)
5. *Hydrodictyon reticulatum* (Hydrodictyaceae),



**Table 3-21: List of Faunal Species Found within 5 km radius of the mining lease area.**

<b>Phylum: Annelida</b>		
<b>SL.No</b>	<b>Local Name</b>	<b>Scientific Name</b>
1	Kecho	<i>Pheretimaposthuma</i>
<b>Phylum: Arthropoda</b>		
1	Prajapati	<i>Papilio</i> sp
2	Moth	<i>Galleria</i> sp
3	Moumachi	<i>Apissp</i>
4	Jonaki	<i>Lampyrinoctiluca</i>
5	Arsola	<i>Periplanetaamericana</i>
6	Vimrul	<i>Vespa orientalis</i>
7	Lalpipra	<i>Oecophyllasmaragdina</i>
8	Kakrabicha	<i>Buthussp</i>
9	Tetulbicha	<i>Scolopendrasp</i>
<b>Phylum: Mollusca</b>		
1	Sthalsamuk	<i>Acatinafulica</i>
2	Jalsamuk	<i>Pilaglobosa</i>
3	Gugli	<i>Bellamyabengalensis</i>
<b>Fresh water fishes</b>		
1	Mrigelmach	<i>Cirrhinusmrigala</i>
2	Bata mach	<i>Labeobata</i>
3	Kalbose	<i>Labeocalbasu</i>
4	Silver carp	<i>Hypophthalmichthysmolitrix</i>
5	Grass carp	<i>Ctenopharyngodonidella</i>
6	Cyprinuscaurio	<i>Cyprinuscaurio</i>
7	Chang mach	<i>Channagachua</i>
8	Sholmach	<i>Channastrata</i>
9	Koi mach	<i>Anabasatestudineus</i>
10	Phaloimach	<i>Notopterusnotopterus</i>
11	Tilapia	<i>Oreochromismossambicus</i>
12	Pabdamach	<i>Ompokpabda</i>
13	Phutimach	<i>Puntiusticto</i>
<b>Class: Amphibia</b>		
1	Kuno bang	<i>Duttaphrynusmelanostictus</i>
<b>Class: Reptilia</b>		
1	Loudaga	<i>Ahaetullanasutas</i>
2	Jaldhora	<i>Xenochrophispiscator</i>
3	Matiali sap	<i>Elachistodonwestermanni</i>
4	Jamna sap	<i>Ptyasmucosus</i>
<b>Class: Aves</b>		
1	Charaipakhi	<i>Passer domesticus</i>
2	Tuntuni	<i>Orthotomussp</i>
3	Satbhaya	<i>Turdoideseaudatus</i>
4	Doyel	<i>Copsychussaularis</i>
5	Bulbul	<i>Pycnonotussp</i>
6	Kak	<i>Corvussplendens</i>
7	Shalik	<i>Acridotherestrictis</i>
8	Phinge	<i>Dicrurousadsimilis</i>
9	Kajalpakhi	<i>Laniuscristatus</i>

10	Kat thokra	<i>Dinopiumbenga</i>
<b>Class: Mammalia</b>		
1	Katbirali	<i>Funambuluspennantii</i>
2	Neul	<i>Herpestesedwardsii</i>
3	Mechobiral	<i>Prionailurusviverrinus</i>
4	Katas	<i>Felischaus</i>
5	Khaksial	<i>Vulpesbengalensis</i>
6	Honuman	<i>Semnopithecus entellus</i>

### 3.18 Socio Economic Environment:

Socio – Economic has been recognized as an important component of environment. It focuses primarily on the social and economic effects that are likely to occur as a result of the construction and operation of the proposed mining activities in the area. It includes various factors, viz. demographic structure, availability of basic amenities such as housing, education, health and medical services, occupation, water supply, sanitation, communication and power supply, prevailing diseases in the region as well as features such as places of tourist attraction and monuments of archaeological importance. The study of these parameters helps in identifying predicting and evaluating the likely impacts due to project.

### 3.19 Objectives:

Objectives of Socioeconomic study as follows:

- To study the demographic structure and facilities available in the study area.
- To identify and assess the impact on socio-economic status of the study area.
- To identify all potential significant adverse and beneficial social impacts of the Project.
- To recommend the mitigation measures to reduce the adverse impact of the project.
- To verify compliance with the environmental regulations and industry’s standards.
- To recommend cost effective measures to be implemented to mitigate the expected impact.

### 3.20 Data Collection:

**Primary Data Collection:** Primary data means original data that has been collected specially for the purpose. The data collected from the field under the control and supervision of an investigator. This type of data is generally afresh and collected for the first time. It is useful for current studies as well as for future studies. While collecting primary data collection in study area following methods are uses.

1. Observation Method
2. Focussed group discussion (FGD)
3. Surveys and questionnaires

**Secondary Data Collection:** Secondary data is usually the “Data gathered and recorded by someone else prior to and for a purpose other than the current project”. Secondary data are collected from




different offices or Govt. websites like Census offices (India Census 2011), Statistical department, Health offices, Land and Revenue department, Zilla Parishad and Non-Governmental org


Baseline data for the socio-economic and cultural environment plays an important role in conducting EIA studies. Any development activity will bring about changes to socio-economic pattern. Data on the demographic pattern, population characteristics, employment, land use pattern, transport and recreation facilities were collected from Revenue offices and other Govt, agencies. Test check survey was also conducted in some of the villages. All the above said environmental parameters will be used for identification, prediction and evaluation of significant impacts. The Socio-Economic details of the study area are gathered through:

- Identification of villages falling from the study area map.
- Collection of the demographic pattern of villages falling in the area through 2011 census data.
- Occupational structure of villages falling in the study area through NIC 2011 census data.
- Details of the amenities available in villages falling in the study area through NIC 2011 census data.

situated in Purba Bardhaman division is district of West Bengal with administrative headquarter located at Purba Bardhaman city. As per the 2011 Census of India data, recast after bifurcation of Bardhaman district in 2017, Purba Bardhaman district had a total population of 4,835,532. There were 2,469,310 (51%) males and 2,366,222 (49%) females. Population below 6 years was 509,855. As per the 2011 census data, recast after bifurcation of Bardhaman district in 2017, the total number of literates in Purba Bardhaman district was 3,232,452 (74.73% of the population over 6 years) out of which males numbered 1,781,090 (80.60% of the male population over 6 years) and females numbered 1,453,362 (68.66% of the female population over 6 years). As per the 2011 census data, recast after bifurcation of Bardhaman district, Hindus numbered 3,566,068 and formed 73.75% of the population in Purba Bardhaman district. Muslims numbered 1,251,737 and formed 25.89% of the population. Christians numbered 8,582 and formed 0.18% of the population. Others numbered 9,145 and formed 0.19% of the population. Scheduled Castes and Scheduled Tribes made up 1,487,151 and 327,501 which is 30.75% and 6.77% of the population respectively. According to the 2011 census, 92.86% of the population in what is now Purba Bardhaman district spoke Bengali, 5.03% Santali and 1.66% Hindi as their first language.



**Figure 3-19: Pie Diagram showing distribution of male and female population of the district**



**Figure 3-20: Pie Diagram showing distribution of male and female literacy rate of the district**



**Pubar Anchalik High Madrasha**



**Senkapur Primary School**

**Figure 3-21: School near the project site**

Socioeconomic survey has been conducted at 2 nos. of school near the project site. **Pubar Anchalik High Madrasha** is located at an aerial distance of 1.81 km south-east of the project site. **Senkapur Primary School** is located at an aerial distance of 2.05 km, South-east of the project site.



**Supur Primary Health center**



**Santiniketan Sebaniketan**

**Figure 3-22: Hospitals near the project site**

Socioeconomic survey has been conducted at Supur Primary Health centre located at an aerial distance of 3.66 km South of the project site and Santiniketan Sebaniketan Hospital located at an aerial distance of 7.45 km, South-west of the project site.

**Table 3-22: Nearest Communication & Infrastructure from the project site**

Sl No.	Amenities	Description	Distance from Project site	Direction from the project site
1.	Airport	Kazi Nazrul Islam Airport	60 km	North-West
2.	Railway	Bhedia railway station	6.2 km	South - East
3.	Bus stand	-	-	-
4.	Police station	Khandaghosh Police station	4.46 km	South-east
5.	Fire Station	Bolpur Fire Brigade Station	18.71 km	East
6.	Hospital	Supur Primary Health center Santiniketan Sebaniketan	3.66 Km 7.45 km	South South-west
7.	Post-Office	Nrisinghapur Post Office	2.92 km	North-East
8.	College	Visva – Bharati University	6.62 km	north
9.	Roads	State Highway-2B National highway-19	5.5 km 16.2 km	South North-East
10.	Infrastructure	Aban Setu	5.12 km	West

## CHAPTER – 4

### 4.1. Anticipated Environmental Impacts and Mitigation Measures:

Any human activity in any environment produces impact, modifying it to a status which is considered adverse or beneficial according to the damage or improvement it brings about in the physical, biological and socio-economic status of the baseline environment. Depending on the nature of activities and existing status, the impacts are assessed for their importance. On the basis of the impact analysis, the mitigating action and future monitoring requirements are focused on the Environmental Management Plan for countering or minimising adverse impacts. The magnitude and significance of the environmental pollution caused by mining depend on the method of mining, scale and concentration of mining activity.

The following parameters are of significance in the EIA and are being discussed in detail:

- Land Environment.
- Water Environment.
- Air Environment.
- Noise Environment.
- Biological Environment.
- Socio-Economic Environment.

### 4.2. Land Environment:

River mining does not involve generation of any overburden/ waste. Thus, no waste dump sites are needed for the proposed activity. The main aspects likely to feature on the land environment are excavation, loading and transportation activities which will not pose any impact to the surrounding land environment.

- **On Agriculture Field:**

Since dry sand mining will be carried out in the riverbed, no impacts on surrounding agricultural lands are envisaged.

**Table 4-1: Anticipated Impacts on Land Environment**

Anticipated Impacts	Mitigation measures
Obstruction in river flow/ course. <ul style="list-style-type: none"> <li>➤ Erosion of channel bed and banks.</li> <li>➤ Increased in Channel Slope</li> <li>➤ Change in channel morphology.</li> <li>➤ Impact on stream's physical characteristics such as channel geometry, bed elevation in stream roughness of the bed, flow velocity, discharge capacity, sediment transportation</li> </ul>	Mining of minerals will be started from so that water flow / course will not be obstructed. The slicing of the mineral will be done at 3.00 m. <ul style="list-style-type: none"> <li>➤ Mining is to be done leaving safety barrier 7.5 m or offset on both sides and maximum barrier should be on concave side of river preferably the flow channel (excavation void created) should be kept straight so as to help avoid erosion as side cutting or</li> </ul>

<p>capacity etc.</p> <ul style="list-style-type: none"> <li>➤ Impact on ecological equilibrium of riverine regime.</li> </ul>	<p>collapsing.</p> <ul style="list-style-type: none"> <li>➤ Safety zone or buffer area will be created from the riverbanks to minimize the instability &amp; erosion and to increase the stability of structures. These safety zones will not be mined out.</li> <li>➤ Quantities will be strictly limited so that sand accumulation rates are sufficient to avoid extended impacts on channel morphology.</li> <li>➤ Mining will be carried out as per approved Mine Plan in scientific and systematic way.</li> <li>➤ Sand mining will be restricted down to 3.00 m depth or the groundwater level whichever less is. Therefore, the mining will not intersect the ground water table.</li> <li>➤ Loss of habitat is minimized because the riverbed mining will be carried only in dry bed which will not disturb the riverine ecosystem.</li> <li>➤ The mine working will remain confined to riverbed only and in no case, mining will disturb any surface area outside the riverbed which may affect topography or drainage.</li> <li>➤ The mining from riverbed will not have impact on natural drainage of surrounding areas as the excavated sand from riverbed is filled with first heavy flow in river during monsoon season.</li> </ul>
---	---

### 4.3. Water Environment:

Planned sand mining: To address the issue of loss of aquatic species, it is suggested that sand mining may be done in different streams so that the water stream on another side of the river is allowed to flow in its natural course.

**Table 4-2: Anticipated Impacts on Water Environment**

Anticipated Impacts	Mitigation measures
River water flow pattern might be changed due to riverbed mining. Mining activities will increase riverbed depth, which may result in increase of flow velocity.	<ul style="list-style-type: none"> <li>➤ No diversion is proposed. There will not be any adverse impact on flow pattern, surface hydrology and ground water regime.</li> <li>➤ Mining activities will be restricted to 3.00 m depth, which will not cause much change in the flow pattern of the river.</li> <li>➤ An offset of 7.5 m will be left from both sides of river, which will minimize the chances of bank failure</li> </ul>



Change in surface water quality and ground water quality.	<ul style="list-style-type: none"> <li>➤ There will be no change in surface water quality other than monsoon season as the river channel remains almost dry during the rest period of time.</li> <li>➤ Ground water quality will not be affected due to mining activities as it is restricted to 3.00 m depth and the mining will not be allowed below the water table.</li> <li>➤ Regular monitoring of water samples will be done as precautionary measures</li> </ul>
Impact on ground water recharge potential as the thickness of the natural filter materials (sediments) is reduced causing less infiltration	➤ Mining will be done as per approved Mine Plan and applicable Rules and Regulation, so that there is no damage on ground water recharge potential due to sand mining.
Wastewater discharge	Portable Bio-toilets will be used; hence no sewage / liquid effluent will be generated and ground or surface water contamination is also not expected due to percolation.

#### 4.4. Air Environment:

Anticipated Impacts on Air Environment:

- The major sources of air pollution from the proposed mining project is dust generation due to extraction, loading and haulage of sand and wind driven erosion of exposed material.
- Exhaust emissions from vehicles and equipment deployed during the operation phase are also likely to increase the levels of SO<sub>2</sub>, NO<sub>x</sub>, PM, CO and un-burnt hydrocarbons.
- The dust generation will affect the health of the workers as well as the nearby habitation/local population.

**Table 4-3: Anticipated Impacts on Air Environment.**

Anticipated Impacts	Mitigation measures
<ul style="list-style-type: none"> <li>➤ Dust from excavation and mining.</li> <li>➤ Loading, unloading and screening. Vehicular movement on the haul roads</li> </ul>	<ul style="list-style-type: none"> <li>➤ Water sprinkling will be done on the haul roads twice in a day.</li> <li>➤ Plantation will be carried out on approach roads.</li> <li>➤ Planning transportation routes of mined material so as to reach the nearest paved roads by shortest route. (minimize transportation over unpaved road);</li> <li>➤ Dust mask provided to the workers engaged at dust generation points like excavations loading and unloading points.</li> <li>➤ Speed limit will be enforced to reduce airborne fugitive dust from vehicular</li> </ul>

	<p>traffic.</p> <ul style="list-style-type: none"> <li>➤ Deploying PUC certified vehicles to reduce their noise emission.</li> <li>➤ Spillage from the trucks will be prevented by covering tarpaulin over the trucks.</li> </ul>
--	---

The Biological mitigation of air pollution can be done by plantation of indigenous species. In this case, on the eastern bank of the river Mayuraksi there is a vast stretch of plain land which is not being used for any other purpose. It is, therefore, suggested that the project proponent should take up plantation activity, in consecutive years, as per the suggestion given below. No exotic and quick growing species will be planted as quick-growing species may invite invasive plant species which exist in the forest fringe area of the locality other than the indigenous ones. Plantation of indigenous species may invite associated species of the region like grasses, herbs and shrubs to grow out of their own. A species-mix plantation is also suggested for maintaining high species diversity of the area.

#### 4.5. Noise Environment:

Since the mining operations are non-mechanized, there will not be any noise and vibrations related impacts. However, only noise-generating activities are due to truck movement carrying sand from the mining lease area. The noise sources shall not generate sound levels above 90 dB (A). With the resultant value being less than the ambient noise levels, there is no likelihood of excess addition of noise from the mine operation to the surrounding background noise level. As derived above and due to the fact that there are human settlements within 200m, no impact of noise on habitation is likely. The same is brought out by the noise measurements, which indicate that the noise levels in the vicinity are within limits.

**Table 4-4: Anticipated Impacts on Noise Environment.**

Anticipated Impacts	Mitigation measures
<ul style="list-style-type: none"> <li>➤ Noise Impact due to mining activities</li> <li>➤ Noise impact due to vehicular movement</li> <li>➤ Auditory Impact</li> </ul>	<ul style="list-style-type: none"> <li>➤ The noise levels from all these sources are periodical and restricted to particular operation.</li> <li>➤ The noise measurement data indicated that present noise levels in the study area is well within the permissible limits of National Ambient Noise Quality Standards.</li> <li>➤ Periodical monitoring of noise will be done.</li> <li>➤ No other equipment except the transportation vehicles will be allowed. Noise generated by this equipment will be intermittent in nature and will not cause much adverse impact.</li> </ul>

	<ul style="list-style-type: none"> <li>➤ Proper maintenance of all equipment/ machines will be carried out which help in reducing noise during operations.</li> <li>➤ Plantation will be taken up along the approach roads and vicinity of river bank which will minimize propagation of noise and also arrest dust by acting as barrier on the pathway between source and receptor.</li> <li>➤ Ear muffs will be provided while working with mining equipment. Regular health check-up facility for labours will be conducted for avoiding any kind of health implications arising due to noise related activities.</li> </ul>
--	---

#### **4.6. Biological Environment:**

There will be no major adverse impact of the mining activity on the biological environment. Minor impacts of sand mining activity on the physical environment will mostly be confined to air pollution due to the excavation and transport of the products. Some impacts may be caused due to the increased load of air-borne particulate matter. The source of suspended particulate matter (SPM) of different sizes will be mostly the stacks of sand. Trucks carrying sand may also add to SPM in the air due to vehicular pollution.

Another negative impact that can affect the aquatic species composition of Mayuraksi River, particularly in the area from where sand will be mined, is the decline in species richness of both aquatic fauna and flora. The dependence of some people on fishing may be affected to some extent due to mining. During mining operations, aquatic flora may be eliminated locally.

As aquatic fauna like fish etc., is primarily dependent on aquatic flora, there will likely be a negative impact on fish availability in this particular locality. As per the Approved mining plan, the project activity is only done on the identified sand deposited area. There are no diversion and excavation activities done in the river water flowing channel. Therefore above mentioned impact will be negligible by the current project. Noise pollution will have a harmful impact on the wild fauna, provided sand transport is allowed during the night. But in this case, heavy mining equipment and explosives will not be used. Moreover, human habitation and forest are far from the place of mining. This impact will be minimal and will not need any mitigation measure. It is suggested that transport in heavy vehicles during the night should be avoided. To address the possible adverse impacts on the biological environment due to the mining of sand, the some mitigation measures are suggested. Ecological management of possible pollution can be done at the source. The northern bank of the river adjacent to the project site has an open barren land where afforestation for mitigating air and noise pollution will be done.

## 4.7. Socio -Economic Environment:

**Table 4-5: Anticipated Impacts on Socio-economic Environment.**

Aspect	Anticipated Impacts	Mitigation measures
Habitation	No loss of Habitation	<ul style="list-style-type: none"> <li>➤ The nearest habitation is beyond 0.67 Km.</li> <li>➤ All necessary measures are being adopted to avoid disturbance in livelihood to Locality.</li> </ul>
Employment	<ul style="list-style-type: none"> <li>➤ Direct employment to 2 persons.</li> <li>➤ Indirect employment to about 90 persons.</li> <li>➤ Improved incomeexpenditure.</li> <li>➤ Improved microinvestments - savingspatterns</li> </ul>	<ul style="list-style-type: none"> <li>➤ Local people will be employed.</li> <li>➤ Training will be provided to non-workers and unskilled workers.</li> <li>➤ Awareness program to motivate people for savings and investment.</li> </ul>
Health Implications	<ul style="list-style-type: none"> <li>➤ No health-related problems were reported during the primary survey.</li> <li>➤ No significant health implications likely to arise to the workers due to mining activities.</li> </ul>	<ul style="list-style-type: none"> <li>➤ Regular health camps will be organized for the local people.</li> <li>➤ Adequate number of medical facilities are situated in the area.</li> </ul>
Health impacts on mental, physical, and social well-being.	The proposed project will not impact the mental, physical and social well-being.It will improve the well-being of the people in and around the surrounding area.	<ul style="list-style-type: none"> <li>➤ Expectations in fair pay, employee care, social responsibility commitments etc. will be timely met. Grievance redressal mechanism will be made to overview and manage complaints arising from the study area.</li> </ul>
Loss / gain of selfesteem	A rise in self-esteem due to increase rate of economic growth in the region. Higher degree of self-satisfaction and contentment	<ul style="list-style-type: none"> <li>➤ Immigration in search of employment will be controlled.</li> </ul>
Loss/ gain of culture and religion	The proposed project will follow universal respect for,and observance and protection of, human rights andfundamental freedoms for all	<ul style="list-style-type: none"> <li>➤ The proposed project will promote neither selective,nor relative, but universal respect through contribution in various festivities, equal observance and protection among employees and societies at large in all CSR activities.</li> </ul>

The proposed project is a riverbed sand mine and is providing to their employees all basic facilities.	The mine will promote girl child education, women empowerment, scholarship to encourage the students and will provide donation to build toilet for sanitation facility. Community development will be designed and programmed by engaging with the Panchayats and local authorities.	➤ The mine will give a boost to local population. Monetary gains, education, health, sanitation, waterconservation, plantation and improvement in general environment will lead to positive growth.
--	--	---

## 4.8. Corporate Environment Responsibility:

**Table 4-6: Anticipated Impacts on Corporate Environment Responsibility.**

Aspect	Anticipated Impacts	Mitigation measures
The proposed riverbed sand mine project will be providing all basic facilities to their employees	<ul style="list-style-type: none"> <li>➤ The mine will promote girl child education, women empowerment, scholarship to encourage the students and will provide donation to build toilet for sanitation purpose.</li> <li>➤ Community development will be designed and programmed by engaging with the Panchayats and local authorities.</li> </ul>	➤ The mine will give boost to local population. Monetary gains, education, health, sanitation, water conservation, plantation and improvement in general environment will lead to positive growth.

## 4.9. Green Belt Development Plan:

Avenue plantation shall be done of suitable indigenous species during the planning period in open and free government land with permission from the competent Authority. Plantation will also be undertaken along the approach road during the plan period. Suggested species to be planted are listed in Plantation Programme section 10.10.



## **CHAPTER – 5**

### **5.1. Analysis of Alternatives (Technology & Site):**

#### **5.1.1. Analysis of Alternative Site:**

No alternative sites have been analyzed, since the project is site specific, and sand is available in the proposed site.

#### **5.1.2. Analysis of Alternatives Technology:**

The mine will be operated by an opencast manual method of mining. No other alternative technologies can be used because of the nature and occurrence of the deposit, cost of operation and PMV, capacity of the mine and specification laid by the consumer industry. Project Proponent of the proposed mine is using eco-friendly measures to minimize the impact of mining on the surrounding environment.

## **CHAPTER – 6**

### **6.1. ENVIRONMENTAL MANAGEMENT PROGRAM**

#### **6.1.1. Introduction**

Regular monitoring of the various environmental parameters is necessary to evaluate the effectiveness of the management programme so that the necessary corrective measures can be taken in case there are some drawbacks in the proposed programme. Since environmental quality parameters at work zone and surrounding area are important for maintaining sound operating practices of the project in conformity with environmental regulations, the post project monitoring work forms part of Environmental Monitoring Program.

#### **6.2. Environmental Monitoring and Reporting Procedure:**

Post Monitoring of various environmental parameters will be carried out on regular basis to ascertain the following:

- Status of Pollution within the mine site and in its vicinity.
- Generate data for predictive or corrective purpose in respect of pollution.
- Examine the efficiency of pollution control system adopted at site.
- To assess environmental impacts.

Monitoring will be carried out at site as per the norms of CPCB. Environmental Monitoring Programme will be conducted for various environmental components as per conditions stipulated in Environmental Clearance Letter issued by MoEF&CC and consent to operate issued by SPCB. Six monthly compliance reports will be submitted to MoEF&CC, the regional office on 1st of June and 1st of December. Quarterly compliance Report for conditions stipulated in Consent to Operate will be submitted to SPCB on regular basis.

#### **6.3. Environmental Management Cell:**

In order to maintain the environmental quality within the stipulated standard, regular monitoring of various environmental components is necessary which will be complied as per condition for this an Environmental Management team be constituted.

The core responsibilities of the Environmental Monitoring Cell will be:

- The organization and interpretation of the environmental monitoring data to establish a record of change associated with the implementation of a project or the operation of an organization.
- The process of verification that all or selected parameters measured by Environmental Monitoring Program are in compliance with regulatory requirements, internal policies and standards, and established environmental quality performance limits.
- The assessment of the effectiveness of the environmental management system, practices and

procedures.

- The environmental monitoring and audit work will be carried out by qualified personnel.
- A summary of non-compliance of the environmental quality performance limits.
- To implement and monitor the control and protective measures based on the EMP.
- To coordinate the environment related activities to the top management within as well as with outside concerned agencies.
- To provide of health checkup of workers and the people living in nearby villages.
- To develop greenbelt in the nearby villages, schools, Govt, offices and transportation routes.

## **6.4. Environmental Monitoring Schedule:**

All the environmental parameters viz. air, water, noise, soil will be monitored regularly in order to detect any changes from the baseline status. Monitoring program will be followed till the mining operations continue as per the CPCB and SPCB guideline.

## **6.5. Methodology Adopted:**

Post project monitoring will be carried out as per conditions stipulated in environmental clearance letter and consent issued by SPCB as well as according to CPCB guidelines. The project site is considered as core zone and the area lying within 10km radius from the mine site is considered as buffer zone, where some impacts may be observed on physical and biological environment. In the buffer zone, slight impact may be observed and that too is occasional. The manual sand mining project particularly have low footprint on buffer zone.

## **6.6. Detailed budget & procurement schedules:**

The monitoring of the environment parameters will be outsourced and carried out by the lab of SPCB or a lab approved by MoEF/NABL.

## **6.7. Conclusion:**

Post Environmental monitoring is an essential step in the EIA process. This justifies the predicted impacts, the efficiency of mitigation measures and the shortcomings of prediction methods, measures and even regulations are to be verified, and EIA practice improved. Environmental indicators could contribute to designing and evaluating monitoring programs, thus improving the establishment of the cause-effect relationship and the reporting and communication of environmental data.

The Environmental Monitoring Cell will coordinate all monitoring programmes at the site and data thus generated will be furnished as per statutory requirements. The frequency of reporting will be on half yearly basis to the SPCB and to SEIAA. The Environmental audit reports will be prepared for the entire year of operations and will be regularly submitted to regulatory authorities.

## **CHAPTER – 7**

### **7.1. ADDITIONAL STUDIES**

The draft EIA as per the EIA notification dated 14/09/2006 and subsequent amendments is being submitted to SPCB for conducting a public hearing for the proposed mining within the ML area located in Malocha Mouza of Purba Bardhaman district of West Bengal. The report will be updated after conducting the public hearing by SPCB with the concerns/suggestion of people and stake holders who would attend the public hearing.

### **7.2. Risk Analysis:**

Risk analysis is the systematic study of uncertainties and risks encountered in various areas. Risk analysis is to identify the risks involved in mining operations at various phases. Potential locations and activities around the proposed site are identified and probable risks are estimated on a person, business and Govt, establishment.

### **7.3. Risk Prioritization Based on Hazards of Mining:**

Sand mining will be by open cast method. Mining will be only within the river site located in Malocha Mouza of Purba Bardhaman district of West Bengal. The lease area is 9.15 Ha. There is no land degradation due to mining activities as mining is done only on riverbed surface. There will be no overburden (OB) or waste generation as the sand is exposed in the riverbed. There will be neither any stacking of soil nor the creation of OB dumps. So, no dumping area, well as stockpiling area, is required. Therefore, there is no chance of failure of dumps and no slope failure due to OB dump and stockpiling. However, there are various factors which can create unsafe working conditions/ hazards in the mining of minerals. The following types of hazards are identified during sand mining operations.

- 1) Accidents during Sand/ Mineral loading, transportation and dumping.
- 2) Accident due to vehicular movement
- 3) Inundation/ Flooding
- 4) Quicksand Condition / Bench Slope Failure.

### **7.4. Mitigation Measures:**

#### **7.4.1. Measures to prevent accidents during loading:**

The following activities will be done to minimize the risk are:

- The truck will be covered with tarpaulin and maintained to prevent any spillage.
- To avoid danger while reversing the trackless vehicles especially at the embankment and tipping points, all areas for reversing of Lorries should be made man free as far as possible.



- The vehicles must be maintained in good repairs and checked thoroughly at least once in a week.
- All transportation within the main working will be carried out directly under the supervision and control of the management.
- Opening of the side covers (pattas) should be done carefully and with warning to prevent injury to the loaders.
- Overloading should not be permitted and the maximum permissible speed limit should be ensured.
- The truck drivers should have proper driving license.
- A statutory provision of the fences, constant education, training etc. will go a long way in reducing the incidents of such accidents.

### **7.5. Measures to prevent incidents during Inundation/ Flooding:**

The following activities will be done to minimize the risk are:

- During monsoon months and heavy rains, the mining operations are ceased.
- There should be mechanism/ warning system of heavy rains and discharges from the upstream dams.
- Inundation of flooding is expected and beneficial for these mines as during this time only the mineral reserve gets replenished.

### **7.6. Precautionary Measure for Sudden Release of Water from Upstream**

The following activities will be done to minimize the risk are:

- The mining should be done only during the dry season and under strict supervision.
- Mining activities should be avoided during monsoon season.
- No go zones should be clearly marked and made aware to the mine workers.
- Deep water areas must be identified.

Exposure pathway (e.g., a means to get it in contact with someone), and determination of likely a receptor (someone receiving the stuff that is migrating). Occupational hazard due to sand mining mainly comes under the physical hazards. Possible Physical hazards are as below mentioned.

### **7.7. Physical Hazards Due to Mining Operations:**

Following health related hazards were identified due to mining operations to the workers: -

- **Light:** The workers may be exposed to the risk of poor illumination or excessive brightness. The effects are eye strain, headache, eye pain and lachrymation, congestion around the cornea and eye fatigue.
- **Heat and Humidity:** The most common physical hazard is heat. The direct effects of heat exposure are burns, heat exhaustion, heat stroke and heat cramps; the indirect effects are

decreased efficiency, increased fatigue and enhanced accident rates. Heat and humidity are encountered in hot and humid condition when temperatures and air temperatures increase in summertime up to 38°C or above in the mining area.

- **Eye Irritation:** During the high windy days in summer the sand & dust could be the problems for eyes like itching and watering of eyes.
- **Respiratory Problems:** Large amounts of dust in air can be a health hazard, exacerbating respiratory disorders such as asthma and irritating the lungs and bronchial passages.
- **Noise Induced Hearing Loss:** Machinery is the main source of noise pollution at the mine site.

## 7.8. Management of Health Hazards:

**Table 7-1: Management of Health Hazards.**

Particulars	Control Measures
Heat & Light	<ul style="list-style-type: none"> <li>➤ The mine site will have adequate provision drinking water supply for labours to combat dehydration. Lightweight and loose-fitting clothes having light colors will give preference to wear.</li> <li>➤ Rigorous exercise and more physical activities will be avoided in hot weather.</li> </ul>
Noise	<ul style="list-style-type: none"> <li>➤ Noise exposure measurements will be taken to determine the exposure limits and identify the zones.</li> </ul>

## 7.9. Disaster Management Plan:

The following activities will be done to minimize the risk are:

- The shallow depth of activities in riverbed mining will not involve any high-risk accident due to side falls/collapse.
- The complete mining operation will be carried out under the Management and control of experienced and qualified Mines Manager.
- All the provisions of Mines Act 1952, MMR 1961 and Mines Rules 1955 and other laws applicable to mine will strictly be complied with.
- During monsoon season the mining activities will be closed.
- All persons in supervisory capacity will be provided with proper communication facilities.
- Proper coordination with Irrigation Department will be maintained so that at the time of releasing water, if any, from the dam suitable warning/ information is given in advance.
- Disaster Warning System" as developed will be strictly implemented.
- Security guards will be posted.
- Provision of rest shelters for mine workers with amenities like resting, drinking water, toilets facilities and site-specific anti-venom provisioning etc. will be provided by lessee.
- First - Aid facilities in the mining area.

## **7.10. Socio Economic Impact assessment:**

### **7.10.1. Social Impact Assessment:**

The proposed mine site has no negative impact on local socio- economic environment. The proposed project will generate direct and indirect employment and revenue to Govt, as well as fulfil the demand of construction and requirement of the local and regional market.

The project will provide following facilities to workers:

- Safe drinking water and water coolers shall be provided.
- Conveyance arrangements to hospitals or dispensaries from the proposed project site will be provided.
- PPE's (Helmets face masks, gloves, shoes etc.) will be provided to the workers as per safety norms.
- Urinal and lavatories, wash basins, bathrooms. One toilet facility per 50 workers shall be provided.

### **7.11. Assessment Resettlement and Rehabilitation:**

No settlements are present within the ML area, thus there is no need to conduct the Rehabilitation and resettlement study.

## **CHAPTER – 8**

### **8.1. PROJECT BENEFITS**

#### **8.1.1. General**

The demand of Sand has been rising in the state as a result of rising in construction activities and development. The sediment in the form of riverbed material (RBM) deposited is of critical importance in civil and other infrastructural activities. The proposed project aims to fulfill the supply of Sand demand. The proposed project lies on the riverbed of Ajay River. The quality of Sand is fine and appropriate for mega infrastructural activities. The mineral is used mainly in construction activities like buildings, roads and infrastructure etc. The requirement for minerals is always high in the nearby cities and towns. Therefore, there is always a good demand for minerals in the domestic market. The local region demand is increasing; hence newer areas for Sand reserves are approached. This will also generate much needed employment for the local people. The economy of the area will get a boost and there will be overall growth of the region in terms of education, health, training, transport, automobile, industry. The standard of living accordingly will also get an up-liftment on the positive side.

#### **8.2. Employment:**

The Socio-Economic Condition of the surrounding villages is poor as there is no significant source of the income. The occupational activities are agriculture, cattle rearing and employment in mines but on daily wages.

##### **➤ Direct Employment:**

During the operational phase, about 2 nos. of people will be employed directly. Considering that some of the skilled personnel to be employed for the project will be from outside the area and unskilled/semiskilled personnel will be from within the study area, the project will add to the wellbeing of the area. In addition to the workforce the indirect employment will also be generated for local persons. It will help in bringing prosperity to the area.

##### **➤ Indirect Employment**

The project will also provide some 90 people indirect employment to the people of nearby area of mine site. It will also provide some need-based opportunities to the local public. The project will provide following indirect employment to the local people:

- The sand available will provide agency employment in the value chain analysis, for place utility and retail.
- Transportation and warehousing in the region required to transfer the mineral will eventually be needed and therefore trucks and jobs in logistical activities will come up.

- Local contractors & villagers will be involved in the extraction of sand which will improve their economic status.

### **8.3. Improvements in Physical Infrastructure:**

The proposed project will enhance the socio-economic activities in the adjoining areas. This will result in following benefits:

- Improvements in physical infrastructure.
- Improvements in social Infrastructure.
- Increase in employment potential.
- Contribution to the exchequer.
- Prevention of illegal mining which will help in sustaining the river and its aesthetic value.
- Post-mining enhancement of green cover.

### **8.4. Improvements in Social Infrastructure:**

There will be some obvious changes in various environmental parameters due to mining activity. Increase socio-economic activities, creation of new employment opportunities. There will be positive impact in socio-economic areas due to increased economic activities, creation of new employment opportunities. The mine will contribute to the Exchequer of State and Central Government as per norms.

### **8.5. Plantation:**

The lease area is in the riverbed and devoid of any vegetation. Mining activities will not cause any harm to riparian vegetation cover as the working will not extend beyond the safety zone left as per approved mining plan. Plantation will be carried along the village roads through which sand will be transported and the areas allocated by the Panchayat / State authorities.

Plantation has been proposed on both sides of the roads as greenbelt to provide cover against dust dissemination. Plantation will be done near the mine area and available free government land within the study area to mitigate the ill-effects of mining and to improve the environment of its surrounding area. This will increase the consciousness in workers and nearby villagers for greenery. Suggested species to be planted are listed in Plantation Programmer section 10.8.

### **8.6. Other Benefits:**

The other tangible benefits include metrics and improvements of demonstrating process, system cost savings, compliant inspections, customer audits, faster product approvals, manufacturing throughput, less rejected material, reduced non-conformance issues, more efficient continuous improvement and project implementation. Intangible benefits include improved staff morale, quick, more accurate and transparent decision making, increased staff accountability and an enhanced culture of quality throughout the organization.





## **CHAPTER – 9**

### **9.1. ENVIRONMENTAL COST BENEFIT ANALYSIS**

The environmental cost benefit analysis is not recommended for this project during scoping stage.

## **CHAPTER – 10**

### **10.1. ENVIRONMENTAL MANAGEMENT PLAN**

#### **10.1.1. Introduction**

The Environment Management Plan (EMP) is required to ensure sustainable development in the study area. This section covers the proposed measures required for meeting the prevailing statutory requirements for protecting environment by suitable environmental management practices in connection with the proposed mining and related activities in the area.

The Environmental Management Plan (EMP) has been designed within the framework of various Indian legislative and regulatory requirements on environmental and socio-economic aspects so as to attain sustainable development.

### **10.2. Air Quality Management:**

#### **10.2.1. Impacts on Air Quality:**

The impacts envisaged due to mining activity are evaluated based on various factors like production capacity, vehicles involved, transportation of sand to the stocking yard etc. The emission inventory of the pollutants is as follows:

The main air pollutant would be dust or particulate matter generated by handling and transportation of sand. But the impact of mining operations on air quality is negligible as excavation involved only scooping of sand deposits from the riverbed. There will be negligible generation of dust due to the proposed mining activities because activities are restricted to only scooping sand from dry riverbed manually. The impact of mining operations on air quality is negligible in and around the excavation zone as there is no utilization of machinery.

Dust may be emitted in air due to mineral transportation vehicles. However, this will be temporary and insignificant as there will be only about approximately 119 trips per day of 20 Cu.m capacity Trucks/ Tractors involved in sand transport.

#### **10.2.2. Controlling Dust Levels:**

The environmental control measures proposed to control the fugitive dust includes:

- Haul road will be maintained regularly. Water tankers with spraying arrangement will be used for regular water sprinkling on the haul roads to ensure effective dust suppression.
- Speed limits will be prescribed for transport vehicle Regular maintenance of transport vehicles.

- Ore carrying trucks will be effectively covered by tarpaulin to avoid escape of fines to the ambient air.
- Dumpers will not be overloaded to prevent spillage on the road.
- Plantation / green belt development along approach/ transportation roads; and controlling of SO<sub>2</sub> & NO<sub>x</sub> Levels. The source of SO<sub>2</sub> & NO<sub>x</sub> would be due to vehicular emissions. This can be controlled by:
  - a) Periodic maintenance of the trucks/dumpers used in transport of sand will be done as per manual and/or at regular interval to reduce smoke emissions.
  - b) Ambient air quality monitoring will be carried out as per CPCB norms except monsoon season.

### **10.3. Noise Pollution Control:**

Noise will be produced at the mine due to the movement of transport vehicles only. This will be temporary and insignificant as the noise generated by the mining activity is dissipated within a small zone around the mine.

As the mining process involves only extraction of sand from the riverbed manually, there is no major noise generation. In the mine, no machinery will be used. Major noise sources are transportation vehicles. The noise produced due to vehicle will not be continuous throughout the day.

### **10.4. Water Requirement and Supply:**

About 10 KLD water will be required in the mine for dust suppression, plantation and drinking purposes. Water will be supplied by authorized water transported through tankers from nearby villages.

### **10.5. Water Quality Management:**

#### **10.5.1. Impacts on water quality:**

There is no wastewater generation in the sand mine. The only water contaminant is rainwater run-off during the monsoon season. Mining will be carried out in dry riverbed and it will remain above the ground water table. There will be no impact due to the proposed mining on the water environment and the water flow pattern does not disturb the turbidity and velocity. The impact on the aquatic flora & fauna due to the proposed opencast excavation is insignificant as it involves only scooping of sand from the dry river bed which will not disturb the aquatic life present in the river.

In order to ensure that the project activities shall not affect the water environment, the following measures will be taken up:

### **10.6. Water pollution control measures:**

In order to ensure that the project activities shall not affect the water environment, the following measures will be taken up:

- Mining will be closed during the monsoon season and at the time of floods. This will help in replenishment of sand in the riverbed.
- Sand will be collected in slices up to depth of 3.00 m or above the ground water level.
- Mining will be restricted minimum 7.5m away (inward) from riverbank to minimize effect of river bank erosion and to avoid consequent channel migration.
- River stream will not be diverted to form in active channels.
- Ground water levels will be monitored regularly in and around sand mining project.
- Mining will be started from north western side and advanced towards eastern side across the river uniformly. In order to maintain safety and stability of river banks, a minimum distance of 7.5 m is left as safety zone.
- Mining at the concave side of the river channel will be avoided to prevent bank erosion.
- Meandering segment of river will be selected for mining in such a way to avoid natural eroding banks and to promote mining on naturally building meander components.
- Water Quality Monitoring for the ground waters, river water and other surface waters shall be carried out seasonally to ensure that the water quality is not affected by the project activities.

### **10.7. Waste Management:**

No waste or overburden is generated hence waste management is not required.

### **10.8. Land Environment:**

#### **➤ Impacts on Land environment:**

The proposed project involves mining of sand from dry bed of the river. The sand excavation activities will form small pits in the river bed temporarily. These pits are filled back naturally by the sediments brought by the river during monsoon. Thus, no reclamation is required as there will not be any change in the land use pattern.

➤ **Land environment control measures:**

- 1) Mining in 9.15 ha will be carried out leaving 7.5m as undisturbed as safety barrier around the mine pits.
- 2) The annual production will be less than replenishment rate of the river.
- 3) Mining will be restricted minimum 3.00 m away (inward) from river bank to minimize effect of river bank erosion and to avoid consequent channel migration
- 4) Mining at the concave side of the river channel will be avoided to prevent bank erosion. Plantation will be carried out along the banks of the river to control erosion of banks.
- 5) Slopes of the mine pits will be maintained below 35°.

## **10.9. Biological Environment:**

No RET (Rare, Endanger and Threatened) species has been spotted within the study area. There will be no loss of forest resources like medicinal plants, endangered & rare species during the mining operation. As no deforestation is involved since excavation is done on the deposited sand of a river. The mining will be carried out in dry bed without disturbing the aquatic species and will not disturb the aquatic life in the river. Since there will be no pollution of the river water due to the proposed mining activity the aquatic biodiversity will not be affected. There will be no habitat fragmentation or blocking of migratory corridors due to the proposed mining activity.

## **10.10. Plantation Programme:**

As the mine lease area is located within the riverbed, it is not suitable for plantation and green belt development, no plantation is proposed in haul roads of the lease area. However, plantation of local species of trees plantation will be carried out along the banks of the river near the mine lease area to form a green belt which will help in reducing the erosion of the river banks and also to act as a dust and noise arresting screen. Plantation will also be carried out along the mineral transportation roads in the nearby villages. About 1200 saplings per annum will be planted in during plan period. Also plantation will be carried out in the available free government areas within the study area. Species suggested for mixed plantation of species like:

- a) *Acacia sp. (Akashmoni, Sonajhuri)*
- b) *Adina Cordifolia (Haldu, Karam)*
- c) *Aegle marmelos (Bael tree)*
- d) *Albizzia Lebbeck (Kalasirish, Kalsish)*



- e) *Anthocephalus cadamba (Kadam)*
- f) *Azadirachta indica (Neem, Nim)*
- g) *Bombax ceiba (Simul, semal)*
- h) *Casuarina equisetifolia (Jhau)*
- i) *Diospyros Melanoxylon (Kend, Tendu)*

### **10.11. Socio-Economic Environment:**

The project activities shall not have any adverse impacts on any of the common property resources of the village communities, as the mine lease area is not being used for any purpose by any section of the society in this region. There is no Resettlement & Rehabilitation involvement in this project. There is no land acquisition in this project. The project is expected to yield a positive impact on the socio-economic environment. It will help for improving direct and secondary employment opportunities for the local people.

### **10.12. Employment Potential:**

Besides the direct and indirect employment of approx. 140 persons, the company will provide vocational skill training to the unemployment youth of the neighboring villages through outside agencies. Local villagers residing in the nearby villages shall be employed as semiskilled workers.

### **10.13. Occupational Health & Safety Measures:**

There is no environmental pollution due to the proposed mining as it is proposed to be a manual scooping of sand on the banks of Ajay River. Hence there will be no major occupational health hazards. Periodic Medical Examination shall be conducted to the workers, wherein a detailed examination and health survey including routine tests shall be conducted and records shall be maintained.

- Employee will be adequately trained and educated for involvement and commitment to the implementation of health and safety guidelines.
- Monitoring the effects of mining activities on safety and health and conducting regular performance reviews through periodical health check-ups.
- Provision of all necessary resources for safety and health of employees and contractors engaged in mining.
- Setting of safety and health objectives based on comprehensive strategic plans and measure performance against these plans.

- Implementing safety and health management system and assessing the effectiveness through periodic audits.
- Organizing regular health check-up of the employee.

#### **10.14. Site Services:**

Temporary office shed, Rest shelters, water supply and first aid facilities will be provided at site. Mostly local people will be employed in the mine.

#### **10.15. Safety Provision:**

All provisions in safety rules and regulation will be maintained by providing required safety equipment to the employees. The lessee will provide safety shoes, safety helmets to all the employees. The safety precautions will be followed as per the provisions of Mines Rules and standards.

#### **10.16. Environmental Monitoring Programme:**

Environmental monitoring will be carried out regularly for ensuring the compliance of environmental standards and conditions stipulated by various regulatory agencies. The services of a recognized laboratory will be hired for monitoring work. Compliance with the conditions will be submitted to the regulatory agencies periodically.

#### **10.17. Budget for Environmental Protection:**

It is necessary to include the environmental cost as a part of the budgetary cost component. For this, a sum of Rs. 9.80 lakhs /annum approx., is allocated for environmental protection activities. This will include the cost of water sprinkling, plantation, environmental monitoring,

**Table 10-1: Proposed Budget for Environmental Monitoring/Protection.**

Sl.No	Particulars	Amount per annum (INR)
1	Dust suppression	214,500
2	Plantation and its protection	382,750
3	Environmental Monitoring	382,750
<b>Total in INR per annum</b>		<b>980,000</b>

#### **10.18. Corporate Environmental Responsibility and Health and hygiene:**

As per the MoEF&CC OM No. 22-65/ 2017-IA II(M) dated 01.05.2018, it has been recommended that 2% of the project cost will be accorded for Corporate Environmental responsibility and 2% for Health and Hygiene.

**Table 10-2: Proposed Budget for Environmental Monitoring/Protection.**

Sl.No	Particulars	Amount per annum (INR)
1	Personal Protective Equipment	50,600
2	Social Welfare Measures	169,700
3	Health and Hygiene	169,700
<b>Total in INR per annum</b>		<b>390,000</b>

### 10.19. Environment Policy:

we recognize the significance of preserving the environment while undertaking our sand mining project. As a responsible entity, we are committed to ensuring that our operations have minimal adverse impacts on the environment and local communities. This policy outlines our approach to environmental conservation and sustainable sand mining practices:

- i. Compliance with Regulations:** We will adhere to all relevant national and local environmental laws, regulations, and guidelines pertaining to sand mining in West Bengal. Our operations will be conducted in full compliance with the stipulated permits and licenses.
- ii. Environmental Impact Assessment (EIA):** Before commencing any mining activities, we will conduct a comprehensive Environmental Impact Assessment (EIA). This assessment will identify potential environmental risks and help develop appropriate mitigation measures.
- iii. Biodiversity Conservation:** We will take measures to protect and conserve the local biodiversity in the mining area. Special attention will be given to endangered and sensitive species, and their habitats will be preserved to the greatest extent possible.
- iv. Water Management:** Water resources in the vicinity of the mining site will be managed responsibly. We will implement water recycling and conservation techniques to minimize water consumption and prevent contamination.
- v. Dust Control and Air Quality:** To mitigate dust emissions, we will implement effective dust control measures throughout the mining process. Regular air quality monitoring will be conducted to ensure compliance with acceptable standards.
- vi. Rehabilitation and Restoration:** Upon the completion of mining activities, we will rehabilitate and restore the mined-out areas. The land will be reclaimed and revegetated to its original ecological condition or transformed into an ecologically viable alternative.
- vii. Community Engagement:** We will engage in open and transparent communication with the local communities. Their concerns, needs, and suggestions will be considered in our decision-making processes.
- viii. Health and Safety:** Employee safety and health will be our top priority. Adequate safety measures will be implemented to prevent accidents and occupational health hazards.

- ix. Resource Optimization:** We will adopt sustainable practices to optimize the use of natural resources. This includes responsible extraction techniques and efficient use of energy during the mining process.
- x. Monitoring and Reporting:** We will establish a robust monitoring system to continuously assess the environmental impacts of our mining activities. Regular reports will be generated and shared with relevant authorities and stakeholders.
- xi. Continuous Improvement:** We are committed to continuous improvement in our environmental performance. Feedback from stakeholders, scientific advancements, and lessons learned from previous projects will be used to enhance our practices.
- xii. Emergency Response Plan:** We will develop and implement an Emergency Response Plan to address any environmental accidents or unforeseen incidents promptly and effectively.

This environmental policy will serve as a guiding document for our sand mining project. By integrating sustainable practices into our operations, we aim to safeguard the environment and contribute positively to the well-being of local communities and ecosystems. Our commitment to environmental protection aligns with our vision of creating a greener and more sustainable future.

## **10.20. Organization Manpower:**

### **10.20.1. Organisational Setup:**

Environmental monitoring and reporting will be designed to provide a close watch on the surrounding natural environment and provide early warnings of any adverse changes that may be related to some dimension of the mining and allied operations.

#### **➤ Man Power:**

Environmental Management & Monitoring Division (EMMD) will be manned by adequate staff. Services of retired forest officials may be taken for the effective implementation of plantation schemes. For the development and maintenance of jobs like drainage, settling tanks etc., assistance from the project civil engineering department may be taken. Manpower recommended is included in the Table below.

**Figure 10-3: Manpower requirement for environmental management & monitoring.**

<b>Sl.No</b>	<b>Description</b>	<b>Nos.</b>
<b>1</b>	Manager, (Pollution Control)/ horticultural Supervisor	<b>2</b>
<b>2</b>	Field assistant	<b>26</b>
<b>3</b>	Labourers	<b>60</b>
<b>Total</b>		<b>90</b>

## CHAPTER – 11

### 11.1. Summary and Conclusion:

The mining industry in India is a major economic activity which contributes significantly to the economy of India. Unless the mining of the minerals is properly regulated, they can have adverse consequences on the environment and socio-economic components of the society. It also disturbs the Air, soil, water and ecological parameters. On the other hand, it develops the economic standard of the region. Issues of Technology for zero waste or low waste mining, relief & rehabilitation, mine closure which otherwise leads to land degradation, are important issues which require continuous attention. In order to mitigate the impact of mineral mining on the environment, a scientific assessment is very important for framing sustainable development strategies. Therefore, the implementation of scientific mining principles through EIA & EMP plays a vital role in sustainable economic growth of our country.

The Environmental Impact Assessment has been prepared to assess the present scenario of the study area for the proposed mining activity. Based on the assessment an environment management plan (EMP) has been prepared, which helps in minimizing the adverse effects of the mining on the surrounding Environment.

The draft Environment Impact Assessment report is being prepared to comply with the Term of reference (TOR) received from MoEF&CC under EIA notification of MoEF dated 14 September and its amendments for seeking environmental clearance for sand mining in Ajay Riverbed over an area of 9.15 Ha. In Malocha mouza of Purba Bardhaman district of West Bengal. The project proponent has submitted application for prior Environmental Clearance (EC) and State Expert Appraisal Committee has considered the same during 73<sup>rd</sup> meeting held on 23.03.2023, subsequent to the discussions held on 25.04.2023, State Environmental Impact Assessment Authority (SEIAA) has issued the Terms of Reference (ToR) for conducting the Environmental Impacts Assessment (EIA) study and to prepare EIA report for conducting the Public hearing as part of Environment Clearances Process.

This Environmental Impact Assessment (EIA) report is prepared to comply with the Terms of Reference (TOR) received from SEIAA under EIA notification of the MoEF dated 14-9-2006 and its amendments of MoEF&CC, Govt. of India, for seeking Environmental Clearance (EC) for sand mining in the applied mining lease area measuring 9.15 Ha falling under category "B1".

The proposed Malocha sand mine unit comes under Mouza- Malocha, JL No.: 36, Plot No.: 254(P),251(P),201(P) & 263(P) P.S.- Burdwan of Purba Bardhaman district of West Bengal. Geographically the ML area extends from latitude 23°36'15.902"N to 23°36'13.755"N and



longitude 87°38'52.154" E to 87°38'59.313" E. The highest elevation of the river sand bed is 95 m AMSL, and the lowest elevation of the lease area is 86 m AMSL. The proposed area falls in SOI top sheet No.73 M/9. The study area map is shown in figure 1-1. The study area of the proposed project comprises 10 Km radius around the mining lease boundary. The map showing the core zone (Mine lease area) and Buffer zone (10 km radius from the lease boundary) is shown in Figure 1-2.

The Mine Lease area is approx. 45.90 Km of aerial distance from the district headquarters at Purba Bardhaman. The proposed ML area can be approached by its own conveyance from NH 19, which is 21.19 Km away from the ML area on the Southern bank of Ajay River.

The proposed mine lease has been granted to “**West Bengal Mineral Development & Trading Corporation Limited**” on 17<sup>th</sup> February 2023. The mining plan for the Mine lease (ML) area has been approved by Chief Mining Officer, Dte of Mines & Minerals, G. P. Branch, S.B. Unit, Asansol, vide letter no 233/CMO/XVI/EBUR (552) dated 10<sup>th</sup> July, 2023. The Open Cast Mining method is proposed in the lease area. As per approved mining plan vide letter no 233/CMO/XVI/EBUR (552) dated 10<sup>th</sup> July, 2023, river bed sand mining will be undertaken over an area of 9.15 Ha. for production of 9,27,810 Cu. M of sand for a contract period of Concession of 5 (five) years. The period of concession of the mine lease is 5 years based on the level of exploration and reserve established. The cost of mining lease, mining equipment, Environmental protection, Socio-economic development for the present mine lease area is about Rs 1.966 Crores (For Initial Years).

**Table 11-1: Salient Features of Baseline Environmental Studies.**

Attribute	Parameter	Frequency of Monitoring
Micro - meteorological Studies	Wind Details like speed, direction, Temperature, Relative Humidity and Rainfall	3 months data has been collected to assess air pollution impacts on the surrounding environment.
Ambient Air Quality	PM <sub>10</sub> PM <sub>2.5</sub> Sulphur Dioxide (SO <sub>2</sub> ) Oxides of Nitrogen (NO <sub>x</sub> )	3 months data has been collected to assess baseline Air Quality status of the area.
Noise Quality Data	Noise levels	1 middle month data has been collected to identify noise producing areas.
Water Quality, Soil Quality Data and Land Use pattern	Physical & Chemical parameters along with measurement of heavy metals and land use parameters.	To establish baseline Water Quality, Soil Quality for future reference and Land Use Pattern in the area

Socio-Economic & Demographic Studies	Socio-Economic parameter	To know the present Socio-Economic status of the study area
--------------------------------------	--------------------------	---

## 11.2. Environmental Monitoring Program:

Regular monitoring of the various environmental parameters is necessary to evaluate the effectiveness of the management programme so that the necessary corrective measures can be taken in case there are some drawbacks in the proposed programme. Since environmental quality parameters at work zone and surrounding area are important for maintaining sound operating practices of the project in conformity with environmental regulations, the post project monitoring work forms part of Environmental Monitoring Program. Post Monitoring of various environmental parameters will be carried out on regular basis to ascertain the following:

- Status of Pollution within the mine site and in its vicinity.
- Generate data for predictive or corrective purpose in respect of pollution.
- Examine the efficiency of pollution control system adopted at site.
- To assess environmental impacts.

Monitoring will be carried out at site as per the norms of CPCB. Environmental Monitoring Programme will be conducted for various environmental components as per conditions stipulated in Environmental Clearance Letter issued by MoEF&CC and consent to operate issued by SPCB. Six monthly compliance reports will be submitted to MoEF&CC, regional office on 1st of June and 1st of December. Quarterly compliance Report for conditions stipulated in Consent to Operate will be submitted to SPCB on regular basis.

Post Environmental monitoring is an essential step in the EIA process. This justifies the predicted impacts, the efficiency of mitigation measures and the shortcomings of prediction methods, measures and even regulations are to be verified and EIA practice improved. Environmental indicators could contribute to designing and evaluating monitoring programs, thus improving establishment of the cause effect relationship and the reporting and communication of environmental data.

The Environmental Monitoring Cell will co-ordinate all monitoring programmers at site and data thus generated will be furnished as per statutory requirements. The frequency of reporting will be on half yearly basis to the SPCB and to SEIAA. The Environmental audit reports will be prepared for the entire year of operations and will be regularly submitted to regulatory authorities.

## 11.3. Environment Management Plan:

- Mining activities will be confined to 3.00 m or ground water level whichever is less depth in the riverbed.

- The approach roads from the mining area to the tar road will be properly sprayed with water for dust suppression.
- Greenbelt and plantations will be proposed with collaborative assistance from local governing bodies. It will help in dust suppression and will also reduce the noise level.
- Plantation will improve the ecology and aesthetic beauty of the area.
- Measures will be taken to Limit the mining activities in the provided lease area by installing proper demarcated pillars and boundaries along the perimeter of the lease area.
- Prior to commencement of mining, a short awareness program will be conducted for labours to make them aware of way of working and various precautions to be taken while at work. Such programs will be repeated periodically.
- It will be ensured that noise produced due to vehicles movement while carrying sand is within the permissible noise level.
- No stacking of Riverbed Material will be done in the riverbed or mining lease area.

#### 11.4. Details of plantation

YEAR	NO. OF PLANTS	LIKELY SPECIES OF PLANTS
1 <sup>ST</sup> YEAR	240	a) <i>Acacia sp. (Akashmoni, Sonajhuri)</i>
2 <sup>ND</sup> YEAR	240	b) <i>Adina Cordifolia (Haldu, Karam)</i>
3 <sup>RD</sup> YEAR	240	c) <i>Aegle marmelos (Bael tree)</i>
4 <sup>TH</sup> YEAR	240	d) <i>Albizia Lebbec (Kalasirish, Kalsish)</i>
5 <sup>TH</sup> YEAR	240	e) <i>Anthocephalus cadamba (Kadam)</i>
Total	1200	f) <i>Azadirachta indica (Neem, Nim)</i>
		g) <i>Bombax ceiba (Simul, semal)</i>
		h) <i>Casuarina equisetifolia (Jhau)</i>
		i) <i>Diospyros Melanoxylon (Kend, Tendu).</i>

#### 11.5. Measures for air pollution and dust suppression

Control of Air Pollution Due to Dust, Exhaust Emissions or Fumes During Mining or Processing Operations for Minor Mineral & Related Activities and Containing the Same Within Permissible Limits Specified Under: -

- a) Roadside plantations will be done in order to prevent the spreading of dust.
- b) Water spraying will be done twice a day over the haul road & roads leading to adjoining state roads.
- c) Dust respirators will be provided to the operators of the mine worker.

- d) Preventive maintenance shall be carried out on equipment.
- e) Every workplace where the air-borne dust is generated is to be sampled and the concentration of the respirable dust will be determined regularly. If any measurement at any workplace and at source, the concentration in excess of measurements shall be carried on and a 6 monthly compliance report will be submitted to the appropriate authority respectively.
- f) Silencers will be fitted to the dumpers.

## **11.6. Measures related to transportation.**

- Regular water spraying on haulage roads during mineral transportation by water sprinklers of rotary type, which will cover the whole width of haulage road in one round.
- Avoid over loading of tippers & consequent spillage on the roads.
- Mineral carrying trucks will be effectively covered by tarpaulin to avoid escape of fines to atmosphere.
- Air quality shall be regularly monitored both in the core zone and the buffer zone.

## **11.7. Measures for controlling NOx level.**

The source of Nox is due to vehicular emission. This can be controlled by proper maintenance and servicing of the vehicles. Only PUC certified vehicles will be permitted.

## **11.8. Measures for noise pollution**

There is no drilling and blasting for mineral extraction. Noise pollution will only be due to loading and transporting equipment. Effective steps will be taken to keep the noise level well below the DGMS prescribed limit of 85 dBA. Noise control is achieved by the following:

- Proper care and maintenance of the equipment will be carried out.
- Personal protective equipment will be provided to the workers. Along the haul road plantation shall be done to act as an acoustic barrier.

## **11.9. Measures on water quality management**

There is little flow of water in the riverbed in the post-monsoon period. The area is having an average of 1400 mm rainfall in a year. During the rainy season, catchments water flows into the river. During the dry period, the Sand is excavated which gets replenished to some extent during this period. No mining activities will be carried out during the rainy season when there is water flowing in the working area.

## CHAPTER – 12

### 12.1. Disclosre of the consultant

This Draft EIA report is prepared on behalf of the proponents, West Bengal Mineral Development & Trading Corporation Limited by the environmental Consultant, “M/s. Indian Mine Planners and Consultants” (IMPCON). The head office of IMPCON is at Kolkata. Indian Mine Planners & Consultants (IMPCON) was established in 2007 with the prime objective of guiding for total mining solution in Mine Planning for the Mine Entrepreneurs of Government, Public Sectors and Private Sector bodies engaged in the field of mining of Coal, Metallic and non- Metallic deposits. The services are provided by the energetic and highly experienced mine planners and guided by the dynamic, pragmatic, qualified and experienced advisors in the field of mining with an aim to ensure safety, productivity, and sustainable mining with due regard to quality and environment. Currently, IMPCON is an ISO 9001:2015 Certified Company & a QCI – NABET accredited Environment Consultant Organization (ECO), Accredited Prospecting Agency (APA) & Mining Plan Preparation Agency (MPPA) from Jan-2021 and Accredited Exploration Agency (AEA) for Mineral sector.

IMPCON caters to the need of existing as well as new Mining Entrepreneurs for preparing the geological reports, mining feasibility reports, mining plan, detailed mine design, environment impacts assessment (EIA) reports etc. A group of advisors from various disciplines with over 40 years of experience from organizations like Geological Survey of India, Various subsidiaries of Coal India Limited (CIL) including Central Mine Planning & Design Institute Limited (CMPDIL), Steel Authority of India Limited (SAIL), Indian School of Mines etc. provide their valuable guidance.

IMPCON also delivers advisory services in all aspects of geological exploration, geo-technical services, hydrogeology, mine planning & detailed design, electrical installations and maintenance, possible improvement areas of mechanical performance of the high-capacity mining machineries, civil and infrastructural job planning, choice of equipment’s for mining, manpower, planning and finally total economics for project viability.



## 12.2. Eia team:

NAME	FUNCTUIONAL AREA
Dr. N. B. Chanda	Air Pollution Monitoring, Prevention and Control (AP)
	Water Pollution monitoring, prevention and control (WP)
	Geology (GEO)
Dr.A.S. Shannigrahi	Meteorology, Air Quality Modelling, and Prediction (AQ)
Mr. Gopal Chandra Das	Land Use and Land Cover (LU)
	Soil Conservation (SC)
Dr. Tapan Kumar Mishra	Ecology & Biodiversity (EB)
Mr. Sanjib Chattopadhyay	Solid Waste Management (SW)
	Hazardous Waste Management (HW)
Ms. Nidhi Singh Rathod	Socio – Economy (SE)
Mr. Debashish Ghosh	Hydrology, Ground Water and Water Conservation (HG)
Mr. Debashish Basu	Noise and Vibration (NV) & Hazards Management (RH)
Mr. Arpan Chakraborty	TEAM MEMBER (TM)
Mr. Sirshendu Hazra	TEAM MEMBER (TM)

## 12.3. Laboratory partner:

N.D. International is a multinational organisation located in India and Japan. Their laboratory is accredited by NABL, ISO 9001:2015 Certified and recognised by other governmental departments. The Details of their laboratory are:

Name of and address of the Laboratory	Scope of services	Accreditation status
ND International <b>Address:</b> 17, Jnan Goswami Sarani, 107b, Block-F, New Alipore, Kolkata, West Bengal, India	Monitoring and Analysis of: <ul style="list-style-type: none"> <li>• Ambient Air Quality</li> <li>• Noise Quality</li> <li>• Soil Quality</li> <li>• Ground Water Quality</li> </ul>	Accredited by NABL, Certificate No. <b>TC-5910</b> <b>Validity:</b> 06 <sup>th</sup> June 2024

## 12.4. Related all documents are attached as Annexures.



GOVERNMENT OF WEST BENGAL  
Office of the Chief Mining Officer  
COURT ROAD, ASANSOL-713304  
DISTT. PASCHIM BARDHAMAN

Tele Fax: 0341-2252407  
e-mail : [cmo.dmm-wb@nic.in](mailto:cmo.dmm-wb@nic.in)

Memo. No. 233/CMO/XVI/EBUR (552)

Dated: Asansol the 10<sup>th</sup> July, 2023

To,  
✓ The Chairman and Managing Director,  
West Bengal Mineral Development & Trading Corporation Limited,  
WBIDC Building, 3<sup>rd</sup> Floor, DJ-Block, DJ-10,  
Sector-II, Bidhannagar (Saltlake City),  
Kolkata – 700091

**Subject-** Approval of "Mining Plan" for mining of 'River-bed Sand' in respect of Sand Block, bearing I.D. MIN\_EBUR\_24, in Mouza Malocha, J.L. No. 36, under P.S. Burdwan, in the District of Purba Bardhaman, over an Area of 9.15 Hectares to be leased out to West Bengal Mineral Development & Trading Corporation Limited.

**Ref.-** IC&E Department's Order No. 04(1/351012/2022)-ICE-12011(99/27/2022-  
MINES SEC Dept. of ICE dated 03.01.2023  
Your QP's submission letter no. IMPCON/KOL/SAND/EBUR/2023-24/122,  
Dated 03/07/2023

Sir,

In terms of **Sub rule 2(b) under Rule 4** of the West Bengal Minor Minerals Concession Rules, 2016, I hereby approve the above mentioned **Mining Plan** for 'River-bed Sand' in Mouza Malocha, J.L. No. 36, Under P.S. Burdwan, in the District of Purba Bardhaman, over an Area of 9.15 Hectares subject to the following conditions:-

01. i) This **Mining Plan** is approved without prejudice in any other laws applicable to the Mine from time to time whether made by Central Govt., State Govt. or any other Government authority.
- ii) The **Mining Plan** is approved without prejudice to any order or direction from any court of competent jurisdiction.
02. It is also clarified that the approval of your aforesaid **Mining Plan** does not in any way imply the approval of the Government in terms of any other provisions of Mines & Minerals (Development & Regulation) Act, 1957, West Bengal Minor Minerals Concession Rules, 2016 and West Bengal Sand (Mining, Transportation, Storage and Sale) Rules, 2021, framed there-under and any other laws.
03. It is also clarified that this approval of **Mining Plan** under the West Bengal Minor Mineral Concession Rules, 2016 and West Bengal Sand (Mining, Transportation, Storage and Sale) Rules, 2021 is subject to the provision of Forest (Conservation) Act, 1980, Forest (Conservation) Rules, 1981 and other relevant statutes, orders and guidelines including those issued by Hon'ble Courts of Law (including National Green Tribunal) as may be applicable to the proposed lease area from time to time.

Contd....2/-



**STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY**

**Pranisampad Bhawan, 5<sup>th</sup> floor, LB 2, Sector-III, Salt Lake, Kolkata – 700 106**

**e-mail: [environmentwb@gmail.com](mailto:environmentwb@gmail.com)**

**Web Portal: [www.environmentwb.gov.in](http://www.environmentwb.gov.in)**

No. **2529** / EN / T – II – 1/ 518/ 2023

Date: **01** / **11** / 2023

To

M/s. West Bengal Mineral Development and Trading Corporation Limited.

13, Nellie Sengupta, sarani ,

2nd floor, Kol- 700087,

Sub: ToR for doing EIA for the proposed Ausgram - II Sand Mine (MIN\_EBUR\_24) over an area of 9.15 ha (22.61 Acres) on the Ajay River at Mouza - Malocha Plot No.254(P), 251(P), 201(P) & 263(P), J.L. No. 36 Block: Ausgram II, PS – Burdwan, District: Purba Bardhaman, West Bengal (proposal no SIA/WB/MIN/440218/2023)

Sir,

This is to inform you that SEIAA in its meeting on 16.10.2023 considered your online application (vide Proposal No. SIA/WB/MIN/440218/2023) as well as the recommendations of SEAC for issuance of ToR and agreed with the recommendation.

The ToR for conducting EIA study is attached herewith (annexure 1).

The ToR is valid for a period of 3(three) years from the date of issue. EIA/EMP is to be submitted before the expiry of the ToR for consideration of EC application.

Encl: Annexure 1



(Tripti Sah)

Member Secretary, SEIAA

No. **2529** / EN / T-II-1/518/2023

Date: **01** / **11** / 2023

Copy forwarded for the information to:

The Secretary, State Level Expert Appraisal Committee, 'Paribesh Bhavan', LA, Salt Lake Sector III, Kolkata- 700106




Member Secretary, SEIAA



Government of West Bengal  
Department of Industry, Commerce and Enterprises  
Mines Branch

- 4, Abanindranath Tagore Sarani (Camac Street), Kolkata-700016



No.261 -ICE-12011(99)/27/2022-MINES

Date:20.04.2023

From : The Deputy Secretary  
to the Government of West Bengal.

To : The Chairman and Managing Director  
West Bengal Mineral Development & Trading Corporation Ltd.,  
WBIDC Building, Sector-II, Bidhannagar,  
Kolkata-700091.

Sub : Provisional Grant Order for Sand Blocks auctioned by WBMDTCL, reg.

Ref : Your Memo No.MDTC/SAND/003/Part-6/948 dated 12.04.2023

Sir,

With reference to the above subject, I am directed to inform you that Provisional Grant Order is hereby accorded by this Department to the West Bengal Mineral Development and Trading Corporation Ltd. for the 47 nos. of sand blocks auctioned by the Corporation in 6<sup>th</sup> and 7<sup>th</sup> phase.

I am also directed to request you kindly to arrange for preparation of Mining Plans and obtain Environment Clearance from the competent authority as well as other statutory clearances as per norms in order to execute Mining Lease in due course.

Yours faithfully

Deputy Secretary

No.261/1(2)-ICE-12011(99)/27/2022-MINES

Date:20.04.2023

Copy forwarded to:

1. PA to Secretary, (Mines), Dept of I, C & E, with request to place it for kind appraisal of the authority
2. Chief Mining Officer, WB, for kind information and necessary action.

Deputy Secretary




87°38'30"E

87°39'0"E

87°39'30"E

Ausgram II Sand Mine (Sand Block: MIN\_EBUR\_24) Mouza  
Malocha JL No. 36 Plot No. 254(P),251(P),201(P) & 263(P)  
Block- Ausgram II, Dist.- Purba Bardhaman West Bengal.



### Legend

○ Lease area coordinates

□ Lease area

0 0.2 0.4 0.8 Kilometers

87°38'30"E

87°39'0"E

87°39'30"E

23°37'0"N

23°36'30"N

23°36'0"N

23°35'30"N



Approved vide Memo. No. 233/eko  
Dated 10/07/2023

**MINING PLAN INCLUDING MINE CLOSURE PLAN  
RIVER BED MINING FOR SAND  
AT AJAY RIVER**

As per West Bengal Minor Mineral Concession Rules 2016 &  
Sand Mining Rules, Govt. of WB 2021)

LESSEE:



**West Bengal Mineral Development  
& Trading Corporation Limited**

ADDRESS: 3<sup>rd</sup> Floor, DJ – 10, WBIIDC Building  
DJ Block, Sector – II, Salt Lake,  
Kolkata-700091, West Bengal



POTENTIAL ZONE CODE (as per DSR): BH\_BL\_AJ\_50\_51\_53

SAND BLOCK CODE: MIN\_EBUR\_24

MINERAL: Riverbed Sand


RIVER: Ajay River; P.S.: Burdwan

DISTRICT: Purba Bardhaman

APPROVED

*Joydeb Das*  
10/07/2023  
(Joydeb Das)  
Chief Mining Officer  
Govt. of West Bengal

QUAZA	PLOT NO.	J.L. NO.	RIVER	AREA
alocha	254(P), 251(P), 201(P) & 263(P)	36	Ajay	9.15 Ha (22.61 Acres)



**PREPARED BY:**

**Dr. N. B. Chanda**

**Qualified Person**


**M/S Indian Mine Planners & Consultants**





# Annexure V: Project Site Located on Toposheet

TOPOSHEET NO.- F45D10\_73M10



INDEX	
BLOCK BOUNDARY	

PLATE NO. - 2

AUSGRAM II SAND MINING LEASE (MIN_EBUR_24)	
MOKUA, MALOCHIA	
PS. AUSGRAM II DIST. - PURBA BARDHAMAN, STATE - WEST BENGAL	
(PLOT No. - 294/351/201/205) II, No. - 36	
AREA - 22.61 Acres (9.15 Ha)	
	<b>WBMDTCL</b>
TOPOGRAPHICAL PLAN	
SCALE: 1:50000	DATE: APRIL, 2023
PREPARED BY:	
M/S INDIAN MINE PLANNERS AND CONSULTANTS	


**N.D. INTERNATIONAL**

 GOVERNMENT REGISTERED  
 An ISO 9001:2015 Company Certificate : 20DQHH82

**TEST REPORT**


Format No.: NDI/FM/81

Date: 20.03.2023

Page -1 of 1

Certificate No. NL(M)/23-2410180

SAMPLE SUBMITTED BY

PARTY :

Name of Customer : Indian Mine Planners and Consultants  
 Address : GE-61, Rajdanga Main road, East Kolkata Township Project, E.M Bypass, Kol-107  
 Description of Sample : Soil  
 Collection Source : MIN\_EBUR\_24 (Ausgram-II) L1  
 Sampling Done by : Mr. A. Mondal & R. Mondal  
 Environmental Condition : Temperature: 42 C, Humidity: 67%  
 Sample Drawn on : 12.03.2023  
 Analysis Started on : 12.03.2023  
 Analysis Completed on : 20.03.2023

**A. CHEMICAL TEST FINDINGS:**

SL No.	Test Parameters	Test Method	Unit	Result
1	Electrical Conductivity (I: 2.5 Aqueous solution)	IS 14767 :2000 134	µs/cm	207
2	Nitrogen	IS 14684:1999	%	0.13
3	Moisture	IS 2720 (Par1-2) :1973	%	20.56
4	Specific Gravity	NDI/CHEM/SOP/S-03	-	2.81
5	Bulk Density	FAO Method: 2007	gm/cm <sup>3</sup>	2.91
6	Phosphorus as P	FAO: (METHOD)U. N 2007	Mg/g	0.243
7	Potassium as K	13.1 of FAO :2007	mg/g	0.28
8	Sodium Absorbion Ratio (SAR)	IS 11624:2019	-	1.23
9	Permeability	NDI/CHEM/SOP/S-05	cm/h	14.35
10	Calcium as Ca	Tbt Fertilizer Control Order 1985	mg/g	0.82
Texture of Soil				
11	Gravel	FAO Method: 2007	%	Nil
12	Sand	FAO Method: 2007	%	35.30
13	Slit	FAO Method: 2007	%	21.82
14	Clay	FAO Method:2007	%	42.88

...END OF TEST REPORT...



For N.D. International  
 L.P. De - CEO (Authorised Signatory)

- The test report shall not be reproduced, except in full, without written approval of the company.
- Results relate only to the parameters tested.
- The remaining sample after test will be retained for 15 days from the date of issue of certificate.

SKR

**N.D. INTERNATIONAL**

GOVERNMENT REGISTERED

An ISO 9001:2015 Company Certificate : 20DQHH82



**eiāci**  
 شركة الهندسة والبناء  
 Engineering International Agromedical Service  
 033-CB-QMS

**TEST REPORT**

Format No.:NDI/FM/81

Date: 20.03.2023

Page -1 of 1

Certificate No. NL(M)/23-2410180

SAMPLE SUBMITTED BY

PARTY :

Name of Customer : Indian Mine Planners and Consultants  
 Address : GE-61, Rajdanga Main road, East Kolkata Township Project,E.M Bypass,Kol-107  
 Description of Sample : Soil  
 Collection Source : MIN\_EBUR\_24 (Ausgram-II) L<sub>2</sub>  
 Sampling Done by : Mr. A. Mondal & R. Mondal  
 Environmental Condition : Temperature: 42 C, Humidity: 67%  
 Sample Drawn on : 12.03.2023  
 Analysis Started on : 12.03.2023  
 Analysis Completed on : 20.03.2023

**A. CHEMICAL TEST FINDINGS:**

SL No.	Test Parameters	Test Method	Unit	Result
1	Electrical Conductivity (I: 2.5 Aqueous solution)	IS 14767 :2000 134	µs/cm	221
2	Nitrogen	IS 14684:1999	%	0.17
3	Moisture	IS 2720 (Par1-2) :1973	%	20.82
4	Specific Gravity	NDI/CHEM/SOP/S-03	-	2.49
5	Bulk Density	FAO Method: 2007	gm/cm <sup>3</sup>	2.99
6	Phosphorus as P	FAO: (METHOD)U. N 2007	Mg/g	0.261
7	Potassium as K	13.1 of FAO :2007	mg/g	0.25
8	Sodium Absorbtion Ratio (SAR)	IS 11624:2019	-	1.29
9	Permeability	NDI/CHEM/SOP/S-05	cm/h	14.37
10	Calcium as Ca	Tbt Fertilizer Control Order 1985	mg/g	0.87
Texture of Soil				
11	Gravel	FAO Method: 2007	%	Nil
12	Sand	FAO Method: 2007	%	35.76
13	Slit	FAO Method: 2007	%	21.90
14	Clay	FAO Method:2007	%	42.34

...END OF TEST REPORT...



*[Signature]*  
 For N.D. International  
 K.P. De - CEO (Authorized Signatory)

- The test report shall not be reproduced, except in full, without written approval of the company.
- Results relate only to the parameters tested.
- The remaining sample after test will be retained for 15 days from the date of issue of certificate.


5/3/23



**N.D. INTERNATIONAL**

GOVERNMENT REGISTERED

An ISO 9001:2015 Company Certificate : 20DQHH82



**eiāci**  
 شركة الهندسة والبناء  
 Emirates International Engineering Co. LLC  
 033-CB-QMS

**TEST REPORT**

Certificate No. NL(M)/23-2410180

Format No.:NDI/FM/81

SAMPLE SUBMITTED BY

Date: 20.03.2023

PARTY :

Page -1 of 1

Name of Customer	: Indian Mine Planners and Consultants
Address	: GE-61, Rajdanga Main road, East Kolkata Township Project, E.M Bypass, Kol-107
Description of Sample	: Soil
Collection Source	: MIN_EBUR_24 (Ausgram-II) L <sub>3</sub>
Sampling Done by	: Mr. A. Mondal & R. Mondal
Environmental Condition	: Temperature: 42 C, Humidity: 67%
Sample Drawn on	: 12.03.2023
Analysis Started on	: 12.03.2023
Analysis Completed on	: 20.03.2023

**A. CHEMICAL TEST FINDINGS:**

SL No.	Test Parameters	Test Method	Unit	Result
1	Electrical Conductivity (I: 2.5 Aqueous solution)	IS 14767 :2000 134	µs/cm	211
2	Nitrogen	IS 14684:1999	%	0.16
3	Moisture	IS 2720 (Part-2) :1973	%	20.42
4	Specific Gravity	NDI/CHEM/SOP/S-03	-	2.77
5	Bulk Density	FAO Method: 2007	gm/cm <sup>3</sup>	2.53
6	Phosphorus as P	FAO: (METHOD)U. N 2007	Mg/g	0.286
7	Potassium as K	13.1 of FAO :2007	mg/g	0.21
8	Sodium Absorbtion Ratio (SAR)	IS 11624:2019	-	1.33
9	Permeability	NDI/CHEM/SOP/S-05	cm/h	14.72
10	Calcium as Ca	Tbt Fertilizer Control Order 1985	mg/g	0.92
Texture of Soil				
11	Gravel	FAO Method: 2007	%	Nil
12	Sand	FAO Method: 2007	%	32.72
13	Slit	FAO Method: 2007	%	22.47
14	Clay	FAO Method:2007	%	44.81

...END OF TEST REPORT...



*[Signature]*  
 For N.D. International  
 K.P. De - CEO (Authorized Signatory)

- 1 The test report shall not be reproduced, except in full, without written approval of the company.
- 2 Results relate only to the parameters tested.
- 3 The remaining sample after test will be retained for 15 days from the date of issue of certificate.

SKR





# N.D. INTERNATIONAL

## GOVERNMENT REGISTERED

### An ISO 9001:2015 Company Certificate : 20DQHH82



### TEST REPORT

SAMPLE DRAWN BY US:

Certificate No. NL(M)/23-2410180

Date: May, 2023

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants

Address : GE-61, Rajdanga Main road, East Kolkata Township Project, E.M Bypass, Kol-107

: Site Address: - MIN\_EBUR\_24 (Ausgram-II).

Description of Sample : Ambient Air

### TEST FINDINGS:

Sl. No.	Date of Monitoring	Collection Source : L-1					
		PM 10 (µg/m <sup>3</sup> )	PM 2.5 (µg/m <sup>3</sup> )	SO <sub>2</sub> (µg/m <sup>3</sup> )	NO <sub>x</sub> (µg/m <sup>3</sup> )	CO (ppm)	Si (µg/m <sup>3</sup> )
1	02-Mar-23	81	54	15	9	< 1.0	6.1
2	05-Mar-23	71	41	17	8	< 1.0	8.8
3	08-Mar-23	71	45	14	7	< 1.0	4.1
4	11-Mar-23	66	47	19	8	< 1.0	6.6
5	14-Mar-23	74	51	20	8	< 1.0	6.4
6	17-Mar-23	78	55	21	9	< 1.0	6.7
7	20-Mar-23	70	46	20	10	1	6A
8	23-Mar-23	81	51	21	10	< 1.0	5.8
9	26-Mar-23	70	44	22	9	< 1.0	4.6
10	29-Mar-23	74	56	19	9	< 1.0	6.2
11	01-Apr-23	81	54	15	9	< 1.0	6.1
12	04-Apr-23	71	41	17	8	< 1.0	9.4
13	07-Apr-23	71	45	14	7	< 1.0	4.1
14	10-Apr-23	66	48	19	8	< 1.0	6.6
15	13-Apr-23	70	47	14	10	1	6.1
16	16-Apr-23	74	50	15	8	1	5.1
17	19-Apr-23	78	47	18	9	1	4.4
18	22-Apr-23	70	35	22	10	1	4.8
19	25-Apr-23	81	51	26	10	1	6.4
20	28-Apr-23	69	46	20	9	< 1.0	8
21	01-May-23	64	47	21	11	1	9.5
22	04-May-23	74	48	14	10	< 1.0	9.1
23	07-May-23	81	54	15	14	1	6.6
24	10-May-23	71	58	11	12	1	6.2
25	13-May-23	71	52	21	12	< 1.0	6.1
26	16-May-23	66	58	14	11	1	9
27	19-May-23	69	54	11	14	2	8
28	22-May-23	74	52	13	11	< 1.0	6.6
29	25-May-23	78	46	14	17	2	8.6
30	28-May-23	70	47	16	14	1	5.8
MAX		81	58	26	17	2	9.5
MIN		64	41	11	7	1	4.1
Average		72.8	49.7	17.3	10	1.2	6.6

...END OF TEST REPORT...



For N.D. International  
G.P. De - CEO (Authorized Signatory)

- 1 The test report shall not be reproduced, except in full, without written approval of the company.
- 2 Results relate only to the parameter tested.
- 3 The remaining sample after test will be retained for 15 days from the date of issue of certificate.

NR



# N.D. INTERNATIONAL

GOVERNMENT REGISTERED

An ISO 9001:2015 Company Certificate : 200QHH82

## TEST REPORT



eiāci  
International Environmental Inspection Agency  
033-CB-QMS

SAMPLE DRAWN BY US:

Certificate No. NL(M)/23-2410180

Date: May ,2023

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants

Address : GE-61,Rajdanga Main road,East Kolkata Township Project,E.M Bypass,Kol-107

: Site Address: - MIN\_EBUR\_24 (Ausgram-II).

Description of Sample : Ambient Air

### TEST FINDINGS:

Sl. No.	Date of Monitoring	Collection Source : L-2					
		PM 10 (pg/m <sup>3</sup> )	PM 2.5 (pg/m <sup>3</sup> )	SO <sub>2</sub> (pg/m <sup>3</sup> )	NO <sub>x</sub> (pg/m <sup>3</sup> )	CO(ppm)	Si (pg/m <sup>3</sup> )
1	02-Mar-23	74	54	15	9	< 1.0	6.1
2	05-Mar-23	74	41	17	8	< 1.0	8.8
3	08-Mar-23	71	45	14	6	<1.0	4.1
4	11-Mar-23	70	47	19	8	< 1.0	6.6
5	14-Mar-23	61	51	20	8	< 1.0	6.4
6	17-Mar-23	69	55	21	9	< 1.0	6.7
7	20-Mar-23	72	46	20	10	1	6A
8	23-Mar-23	58	51	21	10	< 1.0	5.8
9	26-Mar-23	70	44	22	9	< 1.0	4.6
10	29-Mar-23	74	56	19	9	< 1.0	6.2
11	01-Apr-23	81	54	15	9	< 1.0	6.1
12	04-Apr-23	71	41	17	8	< 1.0	9.4
13	07-Apr-23	71	45	14	7	< 1.0	4.1
14	10-Apr-23	78	48	19	8	< 1.0	6.6
15	13-Apr-23	73	47	14	10	2	6.1
16	16-Apr-23	74	50	15	8	1	5.1
17	19-Apr-23	78	47	18	9	2	4.4
18	22-Apr-23	77	55	22	10	1	4.8
19	25-Apr-23	81	51	27	10	1	6.4
20	28-Apr-23	69	46	20	9	< 1.0	8
21	01-May-23	64	47	21	11	1	9.5
22	04-May-23	74	48	14	10	< 1.0	9.1
23	07-May-23	81	54	15	14	2	6.6
24	10-May-23	71	58	10	12	1	6.2
25	13-May-23	76	52	21	12	< 1.0	6.1
26	16-May-23	71	58	14	19	2	9
27	19-May-23	74	54	11	14	2	8
28	22-May-23	77	52	13	11	< 1.0	6.6
29	25-May-23	78	46	14	19	2	8.6
30	28-May-23	70	47	16	14	1	5.8
MAX		81	41	27	19	2	9.5
MIN		58	58	10	6	1	4.2
Average		72.73	49.44	17.27	10.43	1.2	6.8

...END OF TEST REPORT...



*[Signature]*  
For N.D. International  
G.P. De - CEO (Authorized Signatory)

- 1 The test report shall not be reproduced, except in full, without written approval of the company.
- 2 Results relate only to the parameters tested.
- 3 The remaining sample after test will be retained for 15 days from the date of issue of certificate.


SCR



# N.D. INTERNATIONAL

GOVERNMENT REGISTERED

An ISO 9001:2015 Company Certificate : 20DQHH82



**eiāci**  
 Environmental Inspection Agency  
 033-CB-QMS

## TEST REPORT

SAMPLE DRAWN BY US:

Certificate No. NL(M)/23-2410180

Date: May ,2023

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants

Address : GE-61,Rajdanga Main road,East Kolkata Township Project,E.M Bypass,Kol-107

: Site Address: - MIN\_EBUR\_24 (Ausgram-II).

Description of Sample : Ambient Air

## TEST FINDINGS:

Sl. No.	Date of Monitoring	Collection Source : L-3					
		PM 10 (µg/m <sup>3</sup> )	PM 2.5 (µg/m <sup>3</sup> )	SO <sub>2</sub> (µg/m <sup>3</sup> )	NO <sub>x</sub> (µg/m <sup>3</sup> )	CO(ppm)	Si (µg/m <sup>3</sup> )
1	02-Mar-23	81	51	15	9	< 1.0	6.1
2	05-Mar-23	73	41	17	8	< 1.0	8.8
3	08-Mar-23	74	45	14	5	<1.0	3.5
4	11-Mar-23	66	47	19	8	< 1.0	6.6
5	14-Mar-23	74	51	20	8	< 1.0	6.4
6	17-Mar-23	78	55	21	9	< 1.0	6.7
7	20-Mar-23	70	46	20	10	1	6A
8	23-Mar-23	81	51	21	10	< 1.0	5.8
9	26-Mar-23	70	44	22	9	< 1.0	4.6
10	29-Mar-23	74	56	19	7	< 1.0	6.2
11	01-Apr-23	81	54	15	9	< 1.0	6.1
12	04-Apr-23	71	41	17	8	< 1.0	9.4
13	07-Apr-23	71	45	14	7	< 1.0	4.1
14	10-Apr-23	66	48	19	8	< 1.0	6.6
15	13-Apr-23	70	47	14	10	1	6.1
16	16-Apr-23	74	50	15	8	1	5.1
17	19-Apr-23	78	47	18	9	1	4.4
18	22-Apr-23	70	55	22	10	1	4.8
19	25-Apr-23	81	51	26	10	1	6.4
20	28-Apr-23	69	46	20	9	< 1.0	8
21	01-May-23	54	47	21	11	1	9.5
22	04-May-23	74	48	14	10	< 1.0	9.1
23	07-May-23	81	54	15	14	1	6.6
24	10-May-23	71	58	11	12	1	6.2
25	13-May-23	71	52	21	12	< 1.0	6.1
26	16-May-23	66	56	14	11	1	9
27	19-May-23	69	54	11	14	2	8
28	22-May-23	74	52	13	11	< 1.0	6.6
29	25-May-23	78	46	14	17	2	8.6
30	28-May-23	70	47	16	14	1	5.8
MAX		81	51	26	17	2	9.5
MIN		56	41	11	5	1	3.5
Average		70.77	49.92	17.22	9.6	1.0	5.9

...END OF TEST REPORT...



*[Signature]*  
 For N.D. International  
 K.P. De - CEO (Authorized Signatory)

- 1 The test report shall not be reproduced, except in full, without written approval of the company.
- 2 Results relate only to the parameter tested.
- 3 The remaining sample after test will be retained for 15 days from the date of issue of certificate.


SKR



# N.D. INTERNATIONAL

## GOVERNMENT REGISTERED

### An ISO 9001:2015 Company Certificate : 20DQHH82



**eiāci**  
 شركة التقييم والاعتماد  
 Emirates International Accreditation Centre  
 035-CB-QMS

### TEST REPORT

SAMPLE DRAWN BY US:

Certificate No. NL(M)/23-2410180

Date: May ,2023

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants

Address : GE-61,Rajdanga Main road,East Kolkata Township Project,E.M Bypass,Kol-107

: Site Address: - MIN\_EBUR\_24 (Ausgram-II).

Description of Sample : Ambient Air

### TEST FINDINGS:

Sl. No.	Date of Monitoring	Collection Source : L-4					
		PM 10 ( $\mu\text{g}/\text{m}^3$ )	PM 2.5 ( $\mu\text{g}/\text{m}^3$ )	SO <sub>2</sub> ( $\mu\text{g}/\text{m}^3$ )	NO <sub>x</sub> ( $\mu\text{g}/\text{m}^3$ )	CO(ppm)	Si ( $\mu\text{g}/\text{m}^3$ )
1	02-Mar-23	81	54	15	9	< 1.0	6.1
2	05-Mar-23	71	41	17	8	< 1.0	8.8
3	08-Mar-23	71	45	14	7	<1.0	3.1
4	11-Mar-23	66	47	19	8	< 1.0	6.6
5	14-Mar-23	74	51	20	8	< 1.0	6.4
6	17-Mar-23	78	55	21	9	< 1.0	6.7
7	20-Mar-23	70	46	20	10	1	6.7
8	23-Mar-23	81	51	21	10	< 1.0	5.8
9	26-Mar-23	70	44	22	9	< 1.0	4.6
10	29-Mar-23	74	56	19	9	< 1.0	6.2
11	01-Apr-23	81	54	15	9	< 1.0	6.1
12	04-Apr-23	71	41	17	8	< 1.0	8.4
13	07-Apr-23	71	45	14	7	< 1.0	4.1
14	10-Apr-23	66	48	19	8	< 1.0	6.6
15	13-Apr-23	70	47	14	10	1	6.1
16	16-Apr-23	74	50	15	8	1	5.1
17	19-Apr-23	78	47	18	9	1	4.4
18	22-Apr-23	70	55	22	10	1	4.8
19	25-Apr-23	81	51	26	10	1	6.4
20	28-Apr-23	69	46	20	9	< 1.0	8
21	01-May-23	48	47	21	11	1	8.5
22	04-May-23	74	48	14	10	< 1.0	8.1
23	07-May-23	81	54	15	14	1	6.6
24	10-May-23	71	58	11	12	1	6.2
25	13-May-23	71	52	21	12	< 1.0	6.1
26	16-May-23	66	58	14	11	1	9
27	19-May-23	69	54	11	14	2	8
28	22-May-23	74	52	13	11	< 1.0	6.6
29	25-May-23	78	46	14	17	2	8.3
30	28-May-23	70	47	16	14	1	5.8
MAX		81	58	26	17	2	8.5
MIN		64	41	11	7	1	3.1
Average		72.2	50.6	18.1	12.3	1.3	5.7

...END OF TEST REPORT...



*For N.D. International*  
 C.P. De - CEO (Authorized Signatory)

- 1 The test report shall not be reproduced, except in full, without written approval of the company.
- 2 Results relate only to the parameter tested.
- 3 The remaining sample after test will be retained for 15 days from the date of issue of certificate.

SLR



# Annexure VIII: Weather Data Report




## N.D. INTERNATIONAL

GOVERNMENT REGISTERED

An ISO 9001:2015 Company Certificate : 20DQHH82

### TEST REPORT



SAMPLE DRAWN BY US:

Certificate No. NL(M)/23-2410180

Date: May, 2023

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants  
Address : GE-6, Rajdanga Main road, East Kolkata Township Project, E.M Bypass, Kol-107  
Site Address : - MIN\_EBUR\_24 (Ausgram-II)  
Description of Sample : Weather Monitoring  
Sampling Location : L-1

#### TEST FINDINGS:

Sl. No	Date	Time	Temperature ( $^{\circ}\text{C}$ )	Humidity (%)	Wind Direction (Degree)	Wind Speed (m/Sec)
1	12-Mar-23	6:00 AM	20.3	88	143	4.4
2	12-Mar-23	10:00 AM	24.6	71	231	5.3
3	12-Mar-23	2:00 PM	21.7	57	129	3.1
4	12-Mar-23	6:00 AM	23.4	77	53	0.6
5	12-Mar-23	10:00 AM	30.7	84	42	4.7
6	13-Mar-23	2:00 PM	22.4	76	332	3.6
7	13-Mar-23	6:00 AM	27.8	65	231	4.8
8	13-Mar-23	10:00 AM	24.5	71	352	3.7
9	13-Mar-23	2:00 PM	23.1	66	180	5.5
10	13-Mar-23	6:00 AM	31.5	61	277	4.1
11	13-Mar-23	10:00 AM	34.3	79	183	5.9
12	14-Mar-23	2:00 PM	22.6	58	177	1.3
13	14-Mar-23	6:00 AM	30.7	63	339	0.6
14	14-Mar-23	10:00 AM	22.4	53	27	2.8
15	14-Mar-23	2:00 PM	27.8	73	99	5.7
16	14-Mar-23	6:00 AM	24.5	71	57	3.6
17	14-Mar-23	10:00 AM	23.1	71	13	4.8
18	15-Mar-23	2:00 PM	20.3	66	177	3.7
19	15-Mar-23	6:00 AM	24.6	61	236	5.5
20	15-Mar-23	10:00 AM	21.7	79	183	3.7
21	15-Mar-23	2:00 PM	30.7	58	177	5.5
22	15-Mar-23	6:00 AM	22.4	63	339	4.1
23	16-Mar-23	10:00 AM	27.8	79	27	5.9
24	16-Mar-23	2:00 PM	24.5	58	99	4.4
25	16-Mar-23	6:00 AM	23.1	63	53	5.3
26	16-Mar-23	10:00 AM	34.3	53	42	3.1
27	16-Mar-23	2:00 PM	22.6	73	332	3.7
28	17-Mar-23	6:00 AM	30.7	88	231	5.5
29	18-Mar-23	10:00 AM	22.4	71	352	4.1
30	19-Mar-23	2:00 PM	21.7	57	183	5.9
31	20-Mar-23	6:00 AM	23.4	76	177	1.3
32	21-Mar-23	10:00 AM	30.7	65	339	0.6
33	22-Mar-23	2:00 PM	22.4	71	27	5.5
34	23-Mar-23	6:00 AM	27.8	67	99	3.7
35	24-Mar-23	10:00 AM	28.4	73	57	5.5

...END OF TEST REPORT...



For N.D. International  
H.P. De - CEO (Authorised Signatory)

- The test report shall not be reproduced, except in full, without written approval of the company.
- Results relate only to the parameters tested.
- The remaining sample after test will be retained for 15 days from the date of issue of certificate.


NR



# N.D. INTERNATIONAL

GOVERNMENT REGISTERED

An ISO 9001:2015 Company Certificate : 200QHH82



## TEST REPORT

### SAMPLE DRAWN BY US:

Certificate No. NL(M)/23-2410180

Date: May, 2023

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants

Address : GE-6, Rajdanga Main road, East Kolkata Township Project, E.M Bypass, Kol-107

: Site Address: - MIN\_EBUR\_24 (Ausgram-II).

Description of Sample : Ambient Noise Level

Sampling Location : L-1, L-2, L-3 & L-4

### TEST FINDINGS:

Date	Time	Day Time Noise Level in dB (A)-Leg				
		L1	L2	Date	L3	L4
17-03-2023	6 AM - 7 AM	40.5	44.6	19-03-2023	47	38.2
	7AM - 8 AM	47	55		45.2	42
	8 AM - 9 AM	45.2	45.9		50.4	41.8
	9 AM - 10 AM	50.4	41.7		43.9	45.2
	10 AM - 11 AM	48.7	40.8		44	50.4
	11 AM - 12 PM	49	41.4		46	43.9
	12 PM - 1 PM	51.5	43.9		44.6	44
	1 PM - 2 PM	45.2	44		51	46
	2 PM - 3 PM	50.4	46		50.4	44.6
	3 PM - 4 PM	44.6	43.1		48.7	44.6
	4 PM - 5 PM	42.3	43.9		49	42.3
	5 PM - 6 PM	49.8	44		44.6	49.8
	6 PM - 7 PM	54.1	50.4		42.3	44
	7 PM - 8 PM	52.8	48.7		49.8	46
	8 PM - 9 PM	47	49		54.1	44.6
	9 PM - 10 PM	45.2	42.3		45.2	40.8
Date	Time	Night Time Noise Level in dB (A)-Leg				
		L1	L2	Date	L3	L4
17-03-2023	10 PM - 11 PM	41.7	45.2	19-03-2023	44	48.7
	11 PM - 12 AM	40.8	50.4		46	49
18-03-2023	12 AM - 1 AM	41.4	44.6	20-03-2023	44.6	44.6
	1 AM - 2 AM	43.9	42.3		44.6	42.3
	2 AM - 3 AM	44	49.8		42.3	49.8
	3 AM - 4 AM	43.1	45.2		49.8	44
	4 AM - 5 AM	43.9	50.4		44.6	46
	5 AM - 6 AM	41.7	48.7		40.8	44.6

Note: Limits as per CPCB for Residential Area, Day Time (6:00 am to 10:00 pm): 55 dB(A), Night Time (10:00 pm to 6:00 am): 45 dB(A) Commercial area Day Time (6:00 am to 10:00 pm), Night Time (10:00 pm to 6:00 am): 55 dB(A)

...END OF TEST REPORT...



For N.D. International  
 U.P. De - CEO (Authorised Signatory)

- The test report shall not be reproduced, except in full, without written approval of the company.
- Results relate only to the parameters tested.
- The remaining sample after test will be retained for 15 days from the date of issue of certificate.

583


# Annexure X: Ground Water Quality Monitoring Report



## N.D. INTERNATIONAL

GOVERNMENT REGISTERED

An ISO 9001:2015 Company Certificate : 20DQHH82



### TEST REPORT

Certificate No. NL(M)/23-2410180

Date: 20.03.2023

SAMPLE DRAWN BY US:

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants  
Address : GE-6, Rajdanga Main road, East Kolkata Township Project, E.M Bypass, Kol-107  
Description of Sample : Ground Water  
Collection Source : MEN\_EBUR\_24 (Ausgram-II) L.  
Sampling Done by : Mr. A. Mondal & R. Mondal  
Environmental Condition : Temperature : 42 C, Humidity : 67%  
Sample Drawn on : 12.03.2023  
Sample Received on : 12.03.2023  
Analysis Started on : 12.03.2023  
Analysis Completed on : 20.03.2023  
Method of Sampling : IS-1622:1981, IS-17614(P-25):2022(Bact), IS-17614(P-5):2021(Chem),  
Mode of Sampling : Grab Sampling Plan:NDI/FM/52A

#### A. MICROBIOLOGICAL TEST FINDINGS :

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012
1	Total Coliform/ 100ml @ 37°C for 24 hours	IS 1622	CFU	<1 (DL:1)	Not Detectable
2	E. coli/100 ml @ 44.5°C for 24 hours	IS 1622	-	Absent	Not Detectable

#### B. ORGANOLEPTIC & PHYSICAL PARAMETERS:

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012	
					AL(Max.)	PL(Max.)
3	pH at 25 c	APHA 23rd Edn.4500 H <sup>+</sup> B	-	7.3	6.5-8.5	No relaxation
4	Total Dissolved Solid	APHA 231'd Ed n2540-C	mg/L	144	500	2000

#### C. GENERAL PARAMETERS CONCERNING SUBSTANCES UNDESIRABLE :

5	Chloride (as Cl)	APHA 23rd Edn.4500 Cl-B	mg/L	18.7	250	1000
6	Fluoride (as F)	APHA 23rd Edn. 4500-F-C	mg/L	<0.1 (DL:0.1)	1.0	1.5
7	Iron (as Fe)	APHA 23rd Edn. 3150- Fe B	mg/L	0.26	0.3	No relaxation
8	Nitrate (as NO <sub>3</sub> )	APHA 23rd Edn.4500- NO <sub>3</sub> B	mg/L	1.43	45	No relaxation
9	Sulphate (as SO <sub>4</sub> )	APHA 23rd Edn. 4500 SO <sub>4</sub> -B	mg/L	24.65	200	400
10	Sulphide as (H <sub>2</sub> S)	APHA 23rd Edn. 4500 S <sub>2</sub> -D	mg/L	<0.05 (DL:0.05)	0.05	No relaxation
11	Total Hardness (as CaCO <sub>3</sub> )	APHA 23rd Edn. 2340 C	mg/L	71	200	600
12	Arsenic (as As)	APHA 23rd Edn. 3113B	mg/L	<0.002 (DL:0.002)	0.01	0.05
13	Total Chromium (as Cr)	APHA 23rd Edn. 3111 D	mg/L	<0.01 (DL:0.01)	0.05	No relaxation
14	Total Suspended Solids	APHA 23rd Edn. 2540 D	mg/L	10	100 mg/L (max)	
15	Biochemical Oxygen Demand at 27°C for 3 days	IS 3025 (Part - 44) 1993	mg/L	3.1	30 mg/L (max)	
16	Chemical Oxygen Demand	APHA 23rd Edn. 5220 B	mg/L	19	250 mg/L (max)	

Note : 1. AL- Acceptable Limit. 2. PL- Permissible Limit. 3. DL- Detection Limit

As per IS 10500:2012 Total Coliform should be Not Detectable/100ml, which is equivalent to <1 CFU/100 ml as per IS : 1622.

Remarks : Bacteriologically : Satisfactory for the above tested parameters


Chemically : Satisfactory for the above tested parameters.

Statement of Conformity is applied considering Decision Rule as per ISO Guide 98-4

...END OF TEST REPORT...

For, N.D. International

Sweta Mukherjee  
(Microbiologist)  
(Authorised Signatory)



For, N.D. International

K.P. Das - CEO  
Authorised Signatory

- The test report shall not be reproduced, except in full, without written approval of the company.
- Results relate only to the parameters tested.
- The remaining sample after test will be retained for 15 days from the date of issue of certificate.

MS-1

**N.D. INTERNATIONAL****GOVERNMENT REGISTERED****An ISO 9001:2015 Company Certificate : 20DQHH82**

**eiāci**  
 International Accreditation  
 033-03-035

**TEST REPORT**

Certificate No. NL(M)/23-2410180

Date: 20.03.2023

SAMPLE DRAWN BY US:

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants  
 Address : GE-6, Rajdanga Main road, East Kolkata Township Project, E.M Bypass, Kol-107  
 Description of Sample : Ground Water  
 Collection Source : MIN\_EBUR\_24 (Ausgram-II) Ls  
 Sampling Done by : Mr. A. Mondal & R. Mondal  
 Environmental Condition : Temperature : 42 C, Humidity : 67%  
 Sample Drawn on : 12.03.2023  
 Sample Received on : 12.03.2023  
 Analysis Started on : 12.03.2023  
 Analysis Completed on : 20.03.2023

Method of Sampling : IS-1622:1981, IS-17614(P-25):2022(Bact), IS-17614(P-5):2021(Chem),

Mode of Sampling : Grab Sampling Plan:NDI/FM/52A

**A. MICROBIOLOGICAL TEST FINDINGS :**

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012
1	Total Coliform/ 100ml @ 37°C for 24 hours	IS 1622	Cfu	<1 (DL:1)	Not Detectable
2	E. coli/100 ml @ 44.5°C for 24 hours	IS 1622	-	Absent	Not Detectable

**B. ORGANOLEPTIC & PHYSICAL PARAMETERS:**

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012	
					AL(Max.)	PL(Max.)
3	pH at 25 c	APHA 23rd Edn.4500 H <sup>+</sup> B	-	6.8	6.5-8.5	No relaxation
4	Total Dissolved Solid	APHA 231'd Ed n2540-C	mg/L	140	500	2000

**C. GENERAL PARAMETERS CONCERNING SUBSTANCES UNDESIRABLE :**

5	Chloride (as Cl)	APHA 23rd Edn.4500 Cl-B	mg/L	18.8	250	1000
6	Fluoride (as F)	APHA 23rd Edn. 4500-F-C	mg/L	<0.1 (DL:0.1)	1.0	1.5
7	Iron (as Fe)	APHA 23rd Edn. 31500- Fe B	mg/L	0.24	0.3	No relaxation
8	Nitrate (as NO <sub>3</sub> )	APHA 23rd Edn.4500- NO <sub>3</sub> B	mg/L	1.11	45	No relaxation
9	Sulphate (as SO <sub>4</sub> )	APHA 23rd Edn. 4500 SO <sub>4</sub> -B	mg/L	22.6	200	400
10	Sulphide as (H <sub>2</sub> S)	APHA 23rd Edn. 4500 S <sup>2-</sup> -D	mg/L	<0.05 (DL:0.05)	0.05	No relaxation
11	Total Hardness (as CaCO <sub>3</sub> )	APHA 23rd Edn. 2340 C	mg/L	66	200	600
12	Arsenic (as As)	APHA 23rd Edn. 3113B	mg/L	<0.002 (DL:0.002)	0.01	0.05
13	Total Chromium (as Cr)	APHA 23rd Edn. 3111 D	mg/L	<0.01 (DL:0.01)	0.05	No relaxation
14	Total Suspended Solids	APHA 23rd Edn. 2540 D	mg/L	14	100 mg/L. (max)	
15	Biochemical Oxygen Demand at 27°C for 3 days	IS 3025 (Part - 44) 1993	mg/L	3.4	30 mg/L. (max)	
16	Chemical Oxygen Demand	APHA 23rd Edn. 5220 B	mg/L	17	250 mg/L. (max)	

Note : 1. AL- Acceptable Limit. 2. PL- Permissible Limit. 3. DL- Detection Limit

As per IS 10500:2012 Total Coliform should be Not Detectable/100ml, which is equivalent to &lt;1 Cfu/100 ml as per IS : 1622.

**Remarks :** Bacteriologically : Satisfactory for the above tested parameters

Chemically : Satisfactory for the above tested parameters.

Statement of Conformity is applied considering Decision Rule as per ISO Guide 98-4

**...END OF TEST REPORT...**

For, N.D. International

Sweta Mukherjee  
 (Microbiologist)  
 (Authorised Signatory)



For, N.D. International

K.P. Das - CEO  
 Authorised Signatory

1. The test report shall not be reproduced, except in full, without written approval of the company.
2. Results relate only to the parameters tested.
3. The remaining sample after test will be retained for 15 days from the date of issue of certificate.


MB-II



# N.D. INTERNATIONAL

GOVERNMENT REGISTERED

An ISO 9001:2015 Company Certificate : 20DQHH82



elaci  
The Indian Institute of  
Environmental and Occupational Health  
015-08-085

## TEST REPORT

Certificate No. NL(M)/23-2410180

Date: 20.03.2023

SAMPLE DRAWN BY US:

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants  
Address : GE-6, Rajdanga Main road, East Kolkata Township Project, E.M Bypass, Kol-107  
Description of Sample : Ground Water  
Collection Source : MEN\_EBUR\_24 (Ausgram-II) Ls  
Sampling Done by : Mr. A. Mondal & R. Mondal  
Environmental Condition : Temperature : 42 C, Humidity : 67%  
Sample Drawn on : 12.03.2023  
Sample Received on : 12.03.2023  
Analysis Started on : 12.03.2023  
Analysis Completed on : 20.03.2023

Method of Sampling : IS-1622:1981, IS-17614(P-25):2022(Bact), IS-17614(P-5):2021(Chem),

Mode of Sampling : Grab Sampling Plan:NDI/FM/52A

### A. MICROBIOLOGICAL TEST FINDINGS :

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012
1	Total Coliform/ 100ml @ 37°C for 24 hours	IS 1622	CFU	<1 (DL:1)	Not Detectable
2	E. coli/100 ml @ 44.5°C for 24 hours	IS 1622	-	Absent	Not Detectable

### B. ORGANOLEPTIC & PHYSICAL PARAMETERS:

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012	
					AL(Max.)	PL(Max.)
3	pH at 25 c	APHA 23rd Edn.4500 H <sup>+</sup> B	-	7.0	6.5-8.5	No relaxation
4	Total Dissolved Solid	APHA 231'd Ed n2540-C	mg/L	118	500	2000

### C. GENERAL PARAMETERS CONCERNING SUBSTANCES UNDESIRABLE :

5	Chloride (as Cl)	APHA 23rd Edn.4500 Cl-B	mg/L	19.2	250	1000
6	Fluoride (as F)	APHA 23rd Edn. 4500-F-C	mg/L	<0.1 (DL:0.1)	1.0	1.5
7	Iron (as Fe)	APHA 23rd Edn. 31500- Fe B	mg/L	0.28	0.3	No relaxation
8	Nitrate (as NO <sub>3</sub> )	APHA 23rd Edn.4500- NO <sub>3</sub> B	mg/L	0.94	45	No relaxation
9	Sulphate (as SO <sub>4</sub> )	APHA 23rd Edn. 4500 SO <sub>4</sub> -B	mg/L	18.33	200	400
10	Sulphide as (H <sub>2</sub> S)	APHA 23rd Edn. 4500 S <sup>2-</sup> -D	mg/L	<0.05 (DL:0.05)	0.05	No relaxation
11	Total Hardness (as CaCO <sub>3</sub> )	APHA 23rd Edn. 2340 C	mg/L	55	200	600
12	Arsenic (as As)	APHA 23rd Edn. 3113B	mg/L	<0.002 (DL:0.002)	0.01	0.05
13	Total Chromium (as Cr)	APHA 23rd Edn. 3111 D	mg/L	<0.01 (DL:0.01)	0.05	No relaxation
14	Total Suspended Solids	APHA 23rd Edn. 2540 D	mg/L	9	100 mg/L (max)	
15	Biochemical Oxygen Demand at 27°C for 3 days	IS 3025 (Part - 44) 1993	mg/L	3.6	30 mg/L (max)	
16	Chemical Oxygen Demand	APHA 23rd Edn. 5220 B	mg/L	157	250 mg/L (max)	

Note : 1. AL- Acceptable Limit. 2. PL- Permissible Limit. 3. DL- Detection Limit

As per IS 10500:2012 Total Coliform should be Not Detectable/100ml, which is equivalent to <1 CfU/100 ml as per IS : 1622.

Remarks : Bacteriologically : Satisfactory for the above tested parameters


Chemically : Satisfactory for the above tested parameters.

Statement of Conformity is applied considering Decision Rule as per ISO Guide 98-4

...END OF TEST REPORT...

For, N.D. International

Sweta Mukherjee  
(Microbiologist)  
(Authorised Signatory)



For, N.D. International

K.P. De - CEO  
Authorised Signatory

- The test report shall not be reproduced, except in full, without written approval of the company.
- Results relate only to the parameters tested.
- The remaining sample after test will be retained for 15 days from the date of issue of certificate.

MS-1






# N.D. INTERNATIONAL

## GOVERNMENT REGISTERED

### An ISO 9001:2015 Company Certificate : 20DQHH82



**elaci**  
 شركة الاستشارات الهندسية  
 Engineering Consultancy  
 033-CB-QMS

### TEST REPORT

Certificate No. NL(M)/23-2410180

Date: 20.03.2023

SAMPLE DRAWN BY US:

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants  
 Address : GE-6, Rajdanga Main road, East Kolkata Township Project, E.M Bypass, Kol-107  
 Description of Sample : Surface Water  
 Collection Source : MEN\_EBUR\_24 (Ausgram-II) L1  
 Sampling Done by : Mr. A. Mondal & R. Mondal  
 Environmental Condition : Temperature : 42 C, Humidity : 67%  
 Sample Drawn on : 12.03.2023  
 Sample Received on : 12.03.2023  
 Analysis Started on : 12.03.2023  
 Analysis Completed on : 20.03.2023  
 Method of Sampling : IS-1622:1981, IS-17614(P-23):2022(Bact), IS-17614(P-5):2021(Chem),  
 Mode of Sampling : Grab Sampling Plan:NDI/FM/52A

#### A. MICROBIOLOGICAL TEST FINDINGS :

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012
1	Total Coliform/ 100ml @ 37°C for 24 hours	IS 1622	CFU	<1 (DL:1)	Not Detectable
2	E. coli/100 ml @ 44.5°C for 24 hours	IS 1622	-	Absent	Not Detectable

#### B. ORGANOLEPTIC & PHYSICAL PARAMETERS:

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012	
					AL(Max.)	PL(Max.)
3	pH at 25 c	APHA 23rd Edn.4500 H <sup>+</sup> B	-	6.9	6.5-8.5	No relaxation
4	Total Dissolved Solid	APHA 231'd Ed n2540-C	mg/L	98	500	2000

#### C. GENERAL PARAMETERS CONCERNING SUBSTANCES UNDESIRABLE :

5	Chloride (as Cl)	APHA 23rd Edn.4500 Cl-B	mg/L	23.81	250	1000
6	Fluoride (as F)	APHA 23rd Edn. 4500-F-C	mg/L	<0.1 (DL:0.1)	1.0	1.5
7	Iron (as Fe)	APHA 23rd Edn. 31500- Fe B	mg/L	0.26	0.3	No relaxation
8	Nitrate (as NO <sub>3</sub> )	APHA 23rd Edn.4500- NO <sub>3</sub> B	mg/L	0.92	45	No relaxation
9	Sulphate (as SO <sub>4</sub> )	APHA 23rd Edn. 4500 SO <sub>4</sub> -B	mg/L	22.6	200	400
10	Sulphide as (H <sub>2</sub> S)	APHA 23rd Edn. 4500 S <sup>2-</sup> -D	mg/L	<0.05 (DL:0.05)	0.05	No relaxation
11	Total Hardness (as CaCO <sub>3</sub> )	APHA 23rd Edn. 2340 C	mg/L	52	200	600
12	Arsenic (as As)	APHA 23rd Edn. 3113B	mg/L	<0.002 (DL:0.002)	0.01	0.05
13	Total Chromium (as Cr)	APHA 23rd Edn. 3111 D	mg/L	<0.01 (DL:0.01)	0.05	No relaxation
14	Total Suspended Solids	APHA 23rd Edn. 2540 D	mg/L	8	100 mg/L (max)	
15	Biochemical Oxygen Demand at 27°C for 3 days	IS 3025 (Part - 44) 1993	mg/L	3.0	30 mg/L (max)	
16	Chemical Oxygen Demand	APHA 23rd Edn. 5220 B	mg/L	19	250 mg/L (max)	

Note : 1. AL- Acceptable Limit. 2. PL- Permissible Limit. 3. DL- Detection Limit  
 As per IS 10500:2012 Total Coliform should be Not Detectable/100ml, which is equivalent to <1 CFU/100 ml as per IS : 1622.

Remarks : Bacteriologically : Satisfactory for the above tested parameters

Chemically : Satisfactory for the above tested parameters.

Statement of Conformity is applied considering Decision Rule as per ISO Guide 98-4

...END OF TEST REPORT...

For, N.D. International

Sweta Mukherjee  
 (Microbiologist)  
 (Authorised Signatory)



For, N.D. International

K.P. Das - CEO  
 Authorised Signatory

- The test report shall not be reproduced, except in full, without written approval of the company.
- Results relate only to the parameters tested.
- The remaining sample after test will be retained for 15 days from the date of issue of certificate.

MS-II

**N.D. INTERNATIONAL****GOVERNMENT REGISTERED****An ISO 9001:2015 Company Certificate : 20DQHH82**

**eiāci**  
 International Accreditation Centre  
 033-68-095

**TEST REPORT**

Certificate No. NL(M)/23-2410180

Date: 20.03.2023

SAMPLE DRAWN BY US:

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants  
 Address : GE-6, Rajdanga Main road, East Kolkata Township Project, EM Bypass, Kol-107  
 Description of Sample : Surface Water  
 Collection Source : MIN EBUR 24 (Ausgram-II) L:  
 Sampling Done by : Mr. A. Mondal & R. Mondal  
 Environmental Condition : Temperature: 42 C, Humidity : 67%  
 Sample Drawn on : 12.03.2023  
 Sample Received on : 12.03.2023  
 Analysis Started on : 12.03.2023  
 Analysis Completed on : 20.03.2023  
 Method of Sampling : IS-1622:1981, IS-17614(P-25):2022(Bact), IS-17614(P-5):2021(Chem),  
 Mode of Sampling : Grab Sampling Plan:NDI/FM/52A

**A. MICROBIOLOGICAL TEST FINDINGS :**

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012
1	Total Coliform/ 100ml @ 37°C for 24 hours	IS 1622	CFU	<1 (DL:1)	Not Detectable
2	E. coli/100 ml @ 44.5°C for 24 hours	IS 1622	-	Absent	Not Detectable

**B. ORGANOLEPTIC & PHYSICAL PARAMETERS:**

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012	
					AL(Max.)	PL(Max.)
3	pH at 25 c	APHA 23rd Edn.4500 H <sup>+</sup> B	-	7.2	6.5-8.5	No relaxation
4	Total Dissolved Solid	APHA 231'd Ed n2540-C	mg/L	119	500	2000

**C. GENERAL PARAMETERS CONCERNING SUBSTANCES UNDESIRABLE :**

5	Chloride (as Cl)	APHA 23rd Edn.4500 Cl-B	mg/L	24.88	250	1000
6	Fluoride (as F)	APHA 23rd Edn. 4500-F-C	mg/L	<0.1 (DL:0.1)	1.0	1.5
7	Iron (as Fe)	APHA 23rd Edn. 31500- Fe B	mg/L	0.20	0.3	No relaxation
8	Nitrate (as NO <sub>3</sub> )	APHA 23rd Edn.4500- NO <sub>3</sub> B	mg/L	0.82	45	No relaxation
9	Sulphate (as SO <sub>4</sub> )	APHA 23rd Edn. 4500 SO <sub>4</sub> -B	mg/L	24.7	200	400
10	Sulphide as (H <sub>2</sub> S)	APHA 23rd Edn. 4500 S <sup>2-</sup> -D	mg/L	<0.05 (DL:0.05)	0.05	No relaxation
11	Total Hardness (as CaCO <sub>3</sub> )	APHA 23rd Edn. 2340 C	mg/L	49	200	600
12	Arsenic (as As)	APHA 23rd Edn. 3113B	mg/L	<0.002 (DL:0.002)	0.01	0.05
13	Total Chromium (as Cr)	APHA 23rd Edn. 3111 D	mg/L	<0.01 (DL:0.01)	0.05	No relaxation
14	Total Suspended Solids	APHA 23rd Edn. 2540 D	mg/L	10	100 mg/L (max)	
15	Biochemical Oxygen Demand at 27°C for 3 days	IS 3025 (Part - 44) 1993	mg/L	2.9	30 mg/L (max)	
16	Chemical Oxygen Demand	APHA 23rd Edn. 5220 B	mg/L	17	250 mg/L (max)	

Note : 1. AL- Acceptable Limit. 2. PL- Permissible Limit. 3. DL- Detection Limit

As per IS 10500:2012 Total Coliform should be Not Detectable/100ml, which is equivalent to &lt;1 CFU/100 ml as per IS : 1622.

Remarks : Bacteriologically : Satisfactory for the above tested parameters

Chemically : Satisfactory for the above tested parameters.

Statement of Conformity is applied considering Decision Rule as per ISO Guide 98-4

**...END OF TEST REPORT...**

For, N.D. International

Sweta Mukherjee  
 (Microbiologist)  
 (Authorised Signatory)



For, N.D. International

K.P. De - CEO  
 Authorised Signatory

1. The test report shall not be reproduced, except in full, without written approval of the company.
2. Results relate only to the parameters tested.
3. The remaining sample after test will be retained for 15 days from the date of issue of certificate.

MS-II



# N.D. INTERNATIONAL

GOVERNMENT REGISTERED

An ISO 9001:2015 Company Certificate : 20DQHH82



**eiāci**  
 International Accreditation Centre  
 035-CB-QMS

## TEST REPORT

Certificate No. NL(M)/23-2410180

Date: 20.03.2023

SAMPLE DRAWN BY US:

Page -1 of 1

Name of Customer : Indian Mine Planners and Consultants  
 Address : GE-61, Rajdanga Main road, East Kolkata Township Project, E.M Bypass, Kol-107  
 Description of Sample : Surface Water  
 Collection Source : MIN\_EBUR\_24 (Ausgram-II) L  
 Sampling Done by : Mr. A. Mondal & R. Mondal  
 Environmental Condition : Temperature: 42 C, Humidity: 67%  
 Sample Drawn on : 12.03.2023  
 Sample Received on : 12.03.2023  
 Analysis Started on : 12.03.2023  
 Analysis Completed on : 20.03.2023

Method of Sampling : IS-1622:1981, IS-17614(P-25):2022(Bact), IS-17614(P-5):2021(Chem),  
 Mode of Sampling : Grab Sampling Plan:NDI/FM/52A

### A. MICROBIOLOGICAL TEST FINDINGS :

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012
1	Total Coliform/ 100ml @ 37°C for 24 hours	IS 1622	Cfu	<1 (DL:1)	Not Detectable
2	E. coli/100 ml @ 44.5°C for 24 hours	IS 1622	-	Absent	Not Detectable

### B. ORGANOLEPTIC & PHYSICAL PARAMETERS:

Sl. No.	Test Parameters	Test Method	Unit	Results	Norms as per IS 10500 : 2012	
					AL(Max.)	PL(Max.)
3	pH at 25 c	APHA 23rd Edn.4500 H <sup>+</sup> B	-	7.5	6.5-8.5	No relaxation
4	Total Dissolved Solid	APHA 231'd Ed n2540-C	mg/L	98	500	2000

### C. GENERAL PARAMETERS CONCERNING SUBSTANCES UNDESIRABLE :

5	Chloride (as Cl)	APHA 23rd Edn.4500 Cl-B	mg/L	24.51	250	1000
6	Fluoride (as F)	APHA 23rd Edn. 4500-F-C	mg/L	<0.1 (DL:0.1)	1.0	1.5
7	Iron (as Fe)	APHA 23rd Edn. 31500- Fe B	mg/L	0.28	0.3	No relaxation
8	Nitrate (as NO <sub>3</sub> )	APHA 23rd Edn.4500- NO <sub>3</sub> B	mg/L	0.34	45	No relaxation
9	Sulphate (as SO <sub>4</sub> )	APHA 23rd Edn. 4500 SO <sub>4</sub> -B	mg/L	25.3	200	400
10	Sulphide as (H <sub>2</sub> S)	APHA 23rd Edn. 4500 S <sup>2-</sup> -D	mg/L	<0.05 (DL:0.05)	0.05	No relaxation
11	Total Hardness (as CaCO <sub>3</sub> )	APHA 23rd Edn. 2340 C	mg/L	44	200	600
12	Arsenic (as As)	APHA 23rd Edn. 3113B	mg/L	<0.002 (DL:0.002)	0.01	0.05
13	Total Chromium (as Cr)	APHA 23rd Edn. 3111 D	mg/L	<0.01 (DL:0.01)	0.05	No relaxation
14	Total Suspended Solids	APHA 23rd Edn. 2540 D	mg/L	9	100 mg/L. (max)	
15	Biochemical Oxygen Demand at 27°C for 3 days	IS 3025 (Part - 44) 1993	mg/L	2.7	30 mg/L. (max)	
16	Chemical Oxygen Demand	APHA 23rd Edn. 5220 B	mg/L	23	250 mg/L. (max)	

Note : 1. AL- Acceptable Limit. 2. PL- Permissible Limit. 3. DL- Detection Limit

As per IS 10500:2012 Total Coliform should be Not Detectable/100ml, which is equivalent to <1 Cfu/100 ml as per IS : 1622.

Remarks : Bacteriologically : Satisfactory for the above tested parameters

Chemically : Satisfactory for the above tested parameters.

Statement of Conformity is applied considering Decision Rule as per ISO Guide 98-4

...END OF TEST REPORT...

For, N.D. International

Sweta Mukherjee  
 (Microbiologist)  
 (Authorised Signatory)



For, N.D. International

K.P. De - CEO  
 Authorised Signatory

1. The test report shall not be reproduced, except in full, without written approval of the company.
2. Results relate only to the parameters tested.
3. The remaining sample after test will be retained for 15 days from the date of issue of certificate.

MS-II

Annexure XII: Transportation Route Map







National Accreditation Board for  
Testing and Calibration Laboratories

**CERTIFICATE OF ACCREDITATION**

**N. D. INTERNATIONAL**

has been assessed and accredited in accordance with the standard

**ISO/IEC 17025:2017**

**"General Requirements for the Competence of Testing &  
Calibration Laboratories"**

for its facilities at

17, JNAN GOSWAMI SARANI, 107B, BLOCK-F, NEW ALIPORE, KOLKATA, WEST BENGAL, INDIA

in the field of

**TESTING**

Certificate Number: TC-5910

Issue Date: 07/06/2022

Valid Until: 06/06/2024

This certificate remains valid for the Scope of Accreditation as specified in the annexure subject to continued satisfactory compliance to the above standard & the relevant requirements of NABL.  
(To see the scope of accreditation of this laboratory, you may also visit NABL website [www.nabl-india.org](http://www.nabl-india.org))

Name of Legal Identity : N. D. INTERNATIONAL

Signed for and on behalf of NABL



N. Venkateswaran  
Chief Executive Officer



**Annexure XV: NABET Accreditation Certificate**



**National Accreditation Board for Education and Training**



QCI/NABET/ENV/ACO/23/2896

September 29, 2023

To,

**Indian Mine Planners and Consultants**  
DLF Galleria, Room No 409,  
New Town, Action Area-1,  
Kolkata, West Bengal-700156  
(Kind Attention: Dr. N. B. Chanda)

**Sub.:** Extension in the validity of Accreditation till December 28, 2023— regarding  
**Ref.:** 1. Certificate no. NABET/EIA/2023/SA 0182  
2. Request e-mail dated September 29, 2023

Dear Sir,

This has reference to the Accreditation of your organization under the QCI-NABET EIA Scheme and your request email dated September 29, 2023. It is to inform your good self that the validity of **Indian Mine Planners and Consultants**, is hereby extended till December 28, 2023, or the completion of the accreditation process, whichever is earlier.

2. The above extension is subject to the submission of required documents/information concerning your existing application, timely submission/closure of NC/Obs (if any), and applicable fee (pending if any) during the application process.
3. You are requested not to use this letter after the expiry of the above-stated date.

With best regards.

(A K Jha)  
Senior Director  
QCI-NABET

**Annexure XVI: NON-CLUSTER**



**Government of West Bengal**  
Department of Industry, Commerce and Enterprises  
Mines Branch  
4, Abanindranath Tagore Sarani (Camac Street), Kolkata-700016

**Memo No.:** 521(ii) -ICE/O/MIN/GEN-MIS/02/2023

**Date:** 11-08-2023

**NON – CLUSTER CERTIFICATE**

This is to certify that, Sand Block No. MIN\_EBUR\_24, of M/S West Bengal Mineral Development & Trading Corporation Limited, comprising of an area of 9.15 Ha, falls in Ajay River and Administratively covers under AUSGRAM - II block in PURBA BARDHAMAN District is "**Not Clustering**" with any existing Mining Lease within 500 metre radius granted by the Department of Industry, Commerce and Enterprises, Govt. of West Bengal. The Geo - Coordinates of this Sand Block are furnished below:

POINT No.	LATITUDE	LONGITUDE
1	23° 36' 15.902" N	87° 38' 52.154" E
2	23° 36' 16.831" N	87° 38' 52.243" E
3	23° 36' 18.877" N	87° 39' 17.521" E
4	23° 36' 15.973" N	87° 39' 19.306" E
5	23° 36' 12.582" N	87° 39' 08.933" E
6	23° 36' 12.638" N	87° 39' 04.989" E
7	23° 36' 13.755" N	87° 38' 59.313" E

This is also to be stated, that if any Sand Blocks are found in future which may form a cluster situation with the Sand Block MIN\_EBUR\_24, West Bengal Mineral Development and Trading Corporation Limited has to conduct the Cumulative Impact Study as per the prevailing norms and prepare the EIA – EMP including Sand Block MIN\_EBUR\_24 for processing of Environmental Clearance for the future Sand Mine Block.

  
Deputy Secretary  
to the Govt. of West Bengal  
SAMIK PANIGRAHI, W.D.C.S. (Exe.)  
Deputy Secretary  
Dept. of Industry, Commerce & Enterprises  
Govt. of West Bengal



**QUALITY COUNCIL<sup>®</sup>  
OF INDIA**  
Creating an Ecosystem for Quality



## National Accreditation Board for Education and Training



### Certificate of Accreditation

#### **Indian Mine Planners and Consultants, Kolkata**

GE-61, Rajdanga Main Road, Behind Gateway Hotel, Em-Bypass, Kolkata- 700107, West Bengal.

The organization is accredited as Category-A under the QCI-NABET Scheme for Accreditation of EIA Consultant Organization, Version 3: for preparing EIA-EMP reports in the following Sectors –

S. No	Sector Description	Sector (as per)		Cat.
		NABET	MoEFCC	
1	Mining of minerals including opencast/ underground mining	1	1 (a) (i)	A

*Note: Names of approved EIA Coordinators and Functional Area Experts are mentioned in SAAC minutes dated August 02, 2022 posted on QCI-NABET website.*

The Accreditation shall remain in force subject to continued compliance to the terms and conditions mentioned in QCI-NABET's letter of accreditation bearing no. QCI/NABET/ENV/ACO/22/2621 dated December 20, 2022. The accreditation needs to be renewed before the expiry date by Indian Mine Planners and Consultants, Kolkata, following due process of assessment.

**Sr. Director, NABET**

**Dated: December 20, 2022**

**Certificate No.**

**NABET/EIA/2023/SA 0182**

**Valid up to**

**March 14, 2023**

For the updated List of Accredited EIA Consultant Organizations with approved Sectors please refer to QCI-NABET website.

